

200 Miller Street, North Sydney, NSW 2060 | ABN 32 353 260 317
All correspondence PO Box 12, North Sydney, NSW 2059
P (02) 9936 8100 | E council@northsydney.nsw.gov.au
W www.northsydney.nsw.gov.au

Margaret Beazley Level 6, 120 Sussex Street SYDNEY NSW 2000

> D216/21 SB (CIS)

# ENVIRONMENTAL PLANNING AND ASSESSMENT ACT, 1979 AS AMENDED NOTICE OF DETERMINATION - Approval

<b>Development Application Number:</b>	216/21	
Land to which this applies:	21 King George Street, Lavender Bay Lot No.: 7, DP: 520996	
Applicant:	Margaret Beazley	
Proposal:	Demolition of existing structures and construction of a new two storey dwelling house plus basement and associated landscaping and stormwater works	
Determination of Development Application:	Subject to the provisions of Section 4.17 of the Environmental Planning and Assessment Act 1979, approval has been granted subject to conditions in the notice of determination.	
Date of Determination:	19 August 2022	
Reasons for Approval	The development application was considered by the North Sydney Local Planning Panel (NSLPP) on 2 March 2022. The Recommendation to approve the application was endorsed by the Panel subject to amended plans being required to incorporate changes to the rumpus room, first floor terrace and provision for further rooftop landscaping.	
	Delegation to determine the application was granted to the Manager Development Services to issue determination following submission of amended plans satisfying these requirements.	
	Amended plans provided by the applicant on 25 March 2022 have are consistent with the changes required by the Panel.	
	Having regard to the provisions of Section 4.15(1) of the Environmental Planning and Assessment Act 1979, the application is considered to be satisfactory and therefore recommended for approval.	

Consent to operate from:	19 August 2022
Consent will lapse on:	20 August 2027
Period of Consent	Subject to Section 4.20 of the Act, this consent become effective and operates from the date listed above. The consent lapses five years after the date of consent accordance with Section 4.53 of the Act and cannot be extended. To activate this consent, works must physical commence onsite 27 July 2027.
	The owners of adjoining properties and the Lavender Ba Precinct were notified of the amended development propos on 27 January 2022 in accordance with Council's endorse Community Participation Plan. The notification has attracte eleven (11) unique submissions including one from th Lavender Bay Precinct Committee.
How community views were taken into account:	The concerns raised in the submissions were considered to the Panel at its meetings of 1 December 2021 and 2 Marc 2022. The Panel considered the concerns raised by the resident submitters and considered that an increased set back from the Bay View Street boundary at the ground floor (to better reflect setbacks on Bayview Street) and changes to the first-floor terrace would achieve a reasonable balance between view sharing and the development rights an amenity of the future occupants.
	Subject to these amendments, the Panel considered the vie impacts of the proposal to be reasonable.
Review of determination and right of appeal:	Within six months after the date of notification of the decision, a review of this determination can be requested under Division 8.2 of the Act or an appeal to the Land and Environment Court made pursuant to the provisions of Section 8.7 of the Act. A review of determination should be lodged as soon as possible, and preferably no later two months after the date of notification of the decision to enable the review to be completed within the six-month period.

**Endorsed for and on behalf of North Sydney Council** 

19 August 2022

DATE

Signature on behave f consent authority

**TEAM LEADER - ASSESSMENTS** 

## (i) Conditions

Consent is granted subject to the following conditions imposed pursuant to Section 4.17 of the Environmental Planning and Assessment Act 1979 ("the Act") and the provisions of the Environmental Planning and Assessment Regulation 2000 ("the Regulation") such conditions being reasonable and relevant to the development as assessed pursuant to Section 4.17 of the Act.

#### (ii) Definitions

Unless specified otherwise, words have the same meaning as defined by the *Act*, the *Regulation* and the *Interpretation Act* 1987 as in force at the date of consent.

Applicant means the applicant for this consent.

**Approved Plans** means the plans endorsed by Council referenced by this consent as amended by conditions of this consent.

**AS** or **AS/NZS** means Australian Standard® or Australian/New Zealand Standard®, respectively, published by Standards Australia International Limited.

**NCC** means the National Construction Code as published by the Australian Building Codes Board as in force at the date of issue of any *Construction Certificate*.

Council means North Sydney Council.

**Court** means the Land and Environment Court.

Local Native Plants means species of native plant endemic to North Sydney LGA.

Stormwater Drainage System means all works, facilities and documentation relating to:

- The collection of stormwater,
- The retention of stormwater,
- The reuse of stormwater,
- The detention of stormwater,
- The controlled release of stormwater; and

control of the carrying out of the building work.

Connections to easements and public stormwater systems.

**Owner** means the owner of the *site* and successors in title to the *site*.

Owner Builder has the same meaning as in the Home Building Act 1989.

**Principal Certifier** for building or subdivision work means the certifier appointed as the principal certifier for the building work under section 6.6 (1) or for the subdivision work under section 6.12 (1). **Principal Contractor** for building work means the person responsible for the overall coordination and

Note: If any residential building work is involved, the principal contractor must be the holder of a contractor licence under the *Home Building Act 1989*.

Professional Engineer has the same meaning as in the NCC.

Public Place has the same meaning as in the Local Government Act 1993.

**Road** has the same meaning as in the Roads Act 1993.

SEE means the final version of the Statement of Environmental Effects lodged by the Applicant.

**Site** means the land being developed subject to this consent.

**NSLEP 2013** means North Sydney Local Environmental Plan 2013

NSDCP 2013 means North Sydney Development Control Plan 2013

Work for the purposes of this consent means:

- the use of land in connection with development,
- the subdivision of land,
- the erection of a building,
- the carrying out of any work,
- the use of any site crane, machine, article, material, or thing,
- the storage of any waste, materials, site crane, machine, article, material, or thing,
- the demolition of a building,
- the piling, piercing, cutting, boring, drilling, rock breaking, rock sawing or excavation of land,
- the delivery to or removal from the site of any machine, article, material, or thing, or
- the occupation of the site by any person unless authorised by an occupation certificate.

Note: **Interpretation of Conditions** - Where there is any need to obtain an interpretation of the intent of any condition this must be done in writing to Council and confirmed in writing by Council.

## **INDEX OF CONDITIONS**

A.	Conditions that Identify Approved Plans	Page No.
A1. A2.	Development in Accordance with Plans/Documentation Plans on Site	7 7
В.	Matters to be Completed before the lodgement of an Application for a Construction Cert	ificate
B1.	Construction and Traffic Management Plan (Major DAs and Sites with Difficult Access)	8
с.	Prior to the Issue of a Construction Certificate (and ongoing, where indicated)	
C1.	Dilapidation Report Damage to Public Infrastructure	9
C2.	Dilapidation Report Private Property (Excavation)	10
C3.	Dilapidation Survey Private Property (Neighbouring Buildings)	10
C4.	Shoring for Adjoining Property	11
C5.	Structural Adequacy of Adjoining Properties - Excavation Works	11
C6.	Geotechnical Report	11
C7.	Sediment Control	12
C8.	Conservation of the Heritage Sandstone Wall on the Site	13
C9.	Waste Management Plan	13
C10.	Work Zone	13
C11.	Maintain Property Boundary Alignment Levels	14
C12.	Required Infrastructure Works - Roads Act 1993	14
C13.	Obtain Driveway Crossing Permit under S.138 Roads Act 1993	15
C14.	Stormwater Management and Disposal Design Plan -	
	Construction Issue Detail	16
C15.	Bond for Damage and Completion of Infrastructure Works - Stormwater,	
	Kerb and Gutter, Footpaths, Vehicular Crossing and Road Pavement	17
C16.	Protection of Trees	18
C17.	Section 7.12 Contributions	18
C18.	Security Deposit/Guarantee Schedule	19
C19.	Approval for Removal of Trees	19
C20.	BASIX Certificate	20
C21.	Roofing Materials - Reflectivity	20
C22.	Amended landscape plan required	20
D.	Prior to the Commencement of any Works (and continuing where indicated)	
D1.	Photographic Survey (Heritage Items)	20
D2.	Protection of Trees	21
D3.	Temporary Fences and Tree Protection	21
D4.	Public Liability Insurance - Works on Public Land	21
D5.	Asbestos Material Survey	21
D6.	Commencement of Works' Notice	22
E.	During Demolition and Building Work	
E1.	Reuse of Sandstone	22
E2.	Parking Restrictions	23

F2		
E3.	Road Reserve Safety	23
E4.	Temporary Disposal of Stormwater Runoff	23
E5.	Geotechnical Stability during Works	23
E6.	Council Inspection of Public Infrastructure Works	23
E7.	Dust Emission and Air Quality	24
E8.	Noise and Vibration	24
E9.	No Work on Public Open Space	24
E10.	Developer's Cost of Work on Council Property	24
E11.	Protection of Trees	24
E12.	Trees to be Removed	25
E13.	Noxious Plants	25
E14.	Special Permits	25
E15.	Construction Hours	26
E16.	Installation and Maintenance of Sediment Control	27
E17.	Sediment and Erosion Control Signage	27
E18.	Site Amenities and Facilities	27
E19.	Health and Safety	27
E20.	Archaeological Discovery During Works	27
E21.	Prohibition on Use of Pavements	28
E21.		
	Plant and Equipment Kept Within Site	28
E23.	Waste Disposal	28
E24.	Asbestos Removal	28
F.	Prescribed Conditions imposed under EP&A Act and Regulations and other relevant Legislation	on
F1.	National Construction Code	28
F1. F2.	National Construction Code Home Building Act	28 29
F2.	Home Building Act	29
F2. F3.	Home Building Act Appointment of a Principal Certifying Authority (PCA)	29 29
F2. F3. F4.	Home Building Act Appointment of a Principal Certifying Authority (PCA) Construction Certificate	29 29 29
F2. F3. F4. F5.	Home Building Act Appointment of a Principal Certifying Authority (PCA) Construction Certificate Occupation Certificate	29 29 29 30
F2. F3. F4. F5. F6.	Home Building Act Appointment of a Principal Certifying Authority (PCA) Construction Certificate Occupation Certificate Critical Stage Inspections	29 29 29 30 30
F2. F3. F4. F5. F6. F7.	Home Building Act Appointment of a Principal Certifying Authority (PCA) Construction Certificate Occupation Certificate Critical Stage Inspections Commencement of Works	29 29 29 30 30
F2. F3. F4. F5. F6. F7. F8.	Home Building Act Appointment of a Principal Certifying Authority (PCA) Construction Certificate Occupation Certificate Critical Stage Inspections Commencement of Works Excavation/Demolition	29 29 29 30 30 30
F2. F3. F4. F5. F6. F7. F8.	Home Building Act Appointment of a Principal Certifying Authority (PCA) Construction Certificate Occupation Certificate Critical Stage Inspections Commencement of Works Excavation/Demolition Protection of Public Places	29 29 29 30 30 30 30
F2. F3. F4. F5. F6. F7. F8.	Home Building Act Appointment of a Principal Certifying Authority (PCA) Construction Certificate Occupation Certificate Critical Stage Inspections Commencement of Works Excavation/Demolition Protection of Public Places Site Sign	29 29 29 30 30 30
F2. F3. F4. F5. F6. F7. F8.	Home Building Act Appointment of a Principal Certifying Authority (PCA) Construction Certificate Occupation Certificate Critical Stage Inspections Commencement of Works Excavation/Demolition Protection of Public Places	29 29 29 30 30 30 30
F2. F3. F4. F5. F6. F7. F8. F9. F10.	Home Building Act Appointment of a Principal Certifying Authority (PCA) Construction Certificate Occupation Certificate Critical Stage Inspections Commencement of Works Excavation/Demolition Protection of Public Places Site Sign	29 29 29 30 30 30 30
F2. F3. F4. F5. F6. F7. F8. F9. F10.	Home Building Act Appointment of a Principal Certifying Authority (PCA) Construction Certificate Occupation Certificate Critical Stage Inspections Commencement of Works Excavation/Demolition Protection of Public Places Site Sign  Prior to the Issue of an Occupation Certificate	29 29 30 30 30 30 30 31
F2. F3. F4. F5. F6. F7. F8. F9. F10.	Home Building Act Appointment of a Principal Certifying Authority (PCA) Construction Certificate Occupation Certificate Critical Stage Inspections Commencement of Works Excavation/Demolition Protection of Public Places Site Sign  Prior to the Issue of an Occupation Certificate  Infrastructure Repair and Completion of Works	29 29 30 30 30 30 31
F2. F3. F4. F5. F6. F7. F8. F9. F10. G.	Home Building Act Appointment of a Principal Certifying Authority (PCA) Construction Certificate Occupation Certificate Critical Stage Inspections Commencement of Works Excavation/Demolition Protection of Public Places Site Sign  Prior to the Issue of an Occupation Certificate  Infrastructure Repair and Completion of Works Certification - Civil Works Works as Executed Drawings and Video	29 29 30 30 30 30 31 31 31 31
F2. F3. F4. F5. F6. F7. F8. F9. F10. G. G1. G2. G3. G4.	Home Building Act Appointment of a Principal Certifying Authority (PCA) Construction Certificate Occupation Certificate Critical Stage Inspections Commencement of Works Excavation/Demolition Protection of Public Places Site Sign  Prior to the Issue of an Occupation Certificate  Infrastructure Repair and Completion of Works Certification - Civil Works Works as Executed Drawings and Video Damage to Adjoining Properties	29 29 30 30 30 30 31 31 31 32 32
F2. F3. F4. F5. F6. F7. F8. F9. F10. G1. G2. G3. G4. G5.	Home Building Act Appointment of a Principal Certifying Authority (PCA) Construction Certificate Occupation Certificate Critical Stage Inspections Commencement of Works Excavation/Demolition Protection of Public Places Site Sign  Prior to the Issue of an Occupation Certificate  Infrastructure Repair and Completion of Works Certification - Civil Works Works as Executed Drawings and Video Damage to Adjoining Properties Utility Services	29 29 30 30 30 30 31 31 31 32 32 32
F2. F3. F4. F5. F6. F7. F8. F9. F10. G. G1. G2. G3. G4. G5. G6.	Home Building Act Appointment of a Principal Certifying Authority (PCA) Construction Certificate Occupation Certificate Critical Stage Inspections Commencement of Works Excavation/Demolition Protection of Public Places Site Sign  Prior to the Issue of an Occupation Certificate  Infrastructure Repair and Completion of Works Certification - Civil Works Works as Executed Drawings and Video Damage to Adjoining Properties Utility Services Certification of Tree Condition	29 29 30 30 30 30 31 31 31 32 32 32
F2. F3. F4. F5. F6. F7. F8. F9. F10. G. G1. G2. G3. G4. G5. G6. G7.	Home Building Act Appointment of a Principal Certifying Authority (PCA) Construction Certificate Occupation Certificate Critical Stage Inspections Commencement of Works Excavation/Demolition Protection of Public Places Site Sign  Prior to the Issue of an Occupation Certificate  Infrastructure Repair and Completion of Works Certification - Civil Works Works as Executed Drawings and Video Damage to Adjoining Properties Utility Services Certification of Tree Condition BASIX Completion Certificate	29 29 30 30 30 30 31 31 31 32 32 32 32 33
F2. F3. F4. F5. F6. F7. F8. F9. F10. G. G1. G2. G3. G4. G5. G6.	Home Building Act Appointment of a Principal Certifying Authority (PCA) Construction Certificate Occupation Certificate Critical Stage Inspections Commencement of Works Excavation/Demolition Protection of Public Places Site Sign  Prior to the Issue of an Occupation Certificate  Infrastructure Repair and Completion of Works Certification - Civil Works Works as Executed Drawings and Video Damage to Adjoining Properties Utility Services Certification of Tree Condition	29 29 30 30 30 30 31 31 31 32 32 32

## A. Conditions that Identify Approved Plans

## **Development in Accordance with Plans/Documentation**

A1. The development must be carried out in accordance with the following drawings and documentation and endorsed with Council's approval stamp, except where amended by the following conditions and this consent.

Drawing Number	Rev	Title	Drawn By	Dated
DA091	В	Demolition Plan	Saville Isaacs	29-10-2021
DA098	Α	Site Analysis Plan	Saville Isaacs	09-06-2021
DA102	D	Plan Basement	Saville Isaacs	13-12-2021
DA103	E	Plan Ground Floor	Saville Isaacs	18-03-2022
DA104	E	Plan First Floor	Saville Isaacs	18-03-2022
DA105	F	Roof Plan	Saville Isaacs	18-03-2022
DA201	D	Elevation North	Saville Isaacs	18-03-2022
DA202	D	Elevation East	Saville Isaacs	18-03-2022
DA203	D	Elevation South	Saville Isaacs	18-03-2022
DA204	В	Elevation West	Saville Isaacs	14-09-2021
DA205	В	Elevation South Boundary	Saville Isaacs	18-03-2022
DA251	F	Section A-A	Saville Isaacs	18-03-2022
DA252	В	Section B-B	Saville Isaacs	14-09-2021
DA253	Α	Section C-C	Saville Isaacs	14-09-2021
DA111	В	Area Plan	Saville Isaacs	18-03-2022
DA355	В	External Finishes - View A	Saville Isaacs	21-09-2021
DA356	В	External Finishes - View B	Saville Isaacs	21-09-2021
L100	F	Landscape Concept Plan	Spirit Level	23-03-2022
L102	E	Landscape Planting Plan	Spirit Level	12-05-2021

(Reason:

To ensure that the form of the development undertaken is in accordance with the determination of Council, Public Information)

#### Plans on Site

A2. A copy of all stamped approved plans, specifications and documents (including the plans, specifications and documents submitted and approved with the Construction Certificate) must be kept on site at all times so as to be readily available for perusal by any officer of Council or the Principal Certifying Authority.

All documents kept on site in accordance with this condition must be provided to any officer of the Council or the certifying authority upon their request.

(Reason:

To ensure that the form of the development undertaken is in accordance with the determination of Council, Public Information and to ensure ongoing compliance)

## B. Matters to be Completed before the lodgement of an Application for a Construction Certificate

## **Construction and Traffic Management Plan**

- B1. Prior to issue of any Construction Certificate, a Construction and Traffic Management Plan must be prepared. The following matters must be specifically addressed in this Plan:
  - a) A plan view (min 1:100 scale) of the entire site and frontage roadways indicating:
    - Dedicated construction site entrances and exits, controlled by a certified traffic controller, to safely manage pedestrians and construction related vehicles in the frontage roadways;
    - ii. RMS signage type and location to manage pedestrians in the vicinity;
    - iii. The locations of any proposed Work Zones in the frontage roadways;
    - iv. Locations and type of any hoardings proposed;
    - v. Area of site sheds and the like;
    - vi. Location of any proposed crane standing areas;
    - vii. A dedicated unloading and loading point within the site for all construction vehicles, plant and deliveries;
    - viii. Material, plant and spoil bin storage areas within the site, where all materials are to be dropped off and collected; and
    - ix. The provision of an on-site parking area for employees, tradesperson and construction vehicles as far as possible.
  - b) A Traffic Control Plan(s) for the site incorporating the following:
    - i. Traffic control measures proposed in the road reserve that are in accordance with the RMS publication "Traffic Control Worksite Manual," and designed by a person licensed to do so (minimum RMS 'red card' qualification).
    - ii. The main stages of the development requiring specific construction management measures are to be identified and specific traffic control measures identified for each.
  - c) A detailed description and map of the proposed route for vehicles involved in spoil removal, material delivery and machine floatage must be provided detailing light traffic roads and those subject to a load or height limit must be avoided at all times.
    - A copy of this route is to be made available to all contractors and must be clearly depicted at a location within the site.
  - d) A Waste Management Plan in accordance with the provisions of Part B Section 19 of the North Sydney DCP 2013 must be provided. The Waste Management Plan must include, but not be limited to, the estimated volume of waste and method of disposal for the construction and operation phases of the development, design of on-site waste storage and recycling area and administrative arrangements for waste and recycling management during the construction process;
  - e) Evidence of RMS concurrence where construction access is provided directly or within 20 m of an Arterial and/or Classified Road;
  - f) A schedule of site inductions to be held on regular occasions and as determined necessary to ensure all new employees are aware of the construction management obligations. These must specify that construction-related vehicles to comply with the approved requirements; and

g) For those construction personnel that drive to the site, the Site Manager shall attempt to provide on-site parking so that their personnel's vehicles do not impact on the current parking demand in the area.

A suitably qualified and experienced traffic engineer or consultant must prepare the Construction and Traffic Management Plan.

As this plan has a direct impact on the local road network, it must be submitted to and reviewed by Council prior to the issue of any Construction Certificate. A certificate of compliance with this condition from Council's Traffic Engineers as to the result of this review must be obtained and must be submitted as part of the supporting documentation lodged with the Certifying Authority for approval of the application for a Construction Certificate.

The construction management measures contained in the approved Construction and Traffic Management Plan must be implemented prior to the commencement of, and during, works on-site. To obtain the permit, an application must be made to Council on a 'Application to satisfy development consent' form with payment of the adopted assessment.

All works must be undertaken in accordance with the approved Construction and Traffic Management Plan.

A copy of the approved Construction and Traffic Management Plan must be kept on the site at all times and be made available to any officer of the Council on request.

#### Notes:

- 1. North Sydney Council's adopted fee for certification of compliance with this condition must be paid upon lodgement, or in any event, prior to the issue of the relevant approval.
- 2. Any use of Council property will require appropriate approvals and demonstration of liability insurances prior to such work commencing.
- 3. Failure to provide complete and detailed information may result in delays. It is recommended that your Construction and Traffic Management Plan be lodged with Council as early as possible.
- 4. Dependent on the circumstances of the site, Council may request additional information to that detailed in the condition above.

(Reason:

To ensure appropriate measures have been considered for site access, storage and the operation of the site during all phases of the demolition and construction process in a manner that respects adjoining owner's property rights and residential amenity in the locality, without unreasonable inconvenience to the community)

C. Prior to the Issue of a Construction Certificate (and ongoing, where indicated)

## **Dilapidation Report Damage to Public Infrastructure**

C1. A dilapidation survey and report (including photographic record) must be prepared by a suitably qualified consultant which details the pre-developed condition of the existing public infrastructure in the vicinity of the development site. Particular attention must be paid to accurately recording any pre-developed damaged areas so that Council is fully informed when assessing any damage to public infrastructure caused as a result of the development. A copy of the dilapidation survey and report is to be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate.

The developer may be held liable for all damage to public infrastructure in the vicinity of the site, where such damage is not accurately recorded and demonstrated as pre-existing under the requirements of this condition.

The developer shall bear the cost of carrying out works to restore all public infrastructure damaged as a result of the carrying out of the development, and no occupation of the development shall occur until damage caused as a result of the carrying out of the development is rectified.

A copy of the dilapidation survey and report must be lodged with North Sydney Council by the Certifying Authority with submission of the Construction Certificate documentation.

(Reason: To record the condition of public infrastructure prior to the commencement of construction)

## **Dilapidation Report Private Property (Excavation)**

C2. A full dilapidation survey and report on the visible and structural condition of all neighbouring structures within the 'zone of influence' of the required excavations must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The zone of influence is to be defined as the horizontal distance from the edge of the excavation face to twice the excavation depth.

The dilapidation report and survey is to be prepared by a consulting structural/geotechnical engineer agreed to by both the applicant and the owner of any affected adjoining property.

All costs incurred in achieving compliance with this condition shall be borne by the person entitled to act on this Consent.

In the event that access for undertaking the dilapidation survey is denied by an adjoining owner, the applicant MUST DEMONSTRATE, in writing, to the satisfaction of Council that all reasonable steps have been taken to obtain access and advise the affected property owner of the reason for the survey and that these steps have failed. Written concurrence must be obtained from Council in such circumstances.

Note: This documentation is for record keeping purposes only and may be used by the developer or affected property owner to assist in any action required to resolve any dispute over damage to adjoining properties arising from the works. It is in the applicant's and adjoining owner's interest for it to be as full and detailed as possible.

(Reason: To record the condition of property/ies prior to the commencement of construction)

## **Dilapidation Survey Private Property (Neighbouring Buildings)**

C3. A photographic survey and dilapidation report of adjoining properties No. 19 King George Street and No. 38 Bay View Street, detailing the physical condition of those properties, both internally and externally, including, but not limited to, such items as walls, ceilings, roof, structural members and other similar items, SHALL BE submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The survey and report is to be prepared by an appropriately qualified person agreed to by both the applicant and the owner of the adjoining property. A copy of the report is to be provided to Council, if Council is not the Certifying Authority, prior to the issue of any Construction Certificate.

All costs incurred in achieving compliance with this condition shall be borne by the person entitled to act on this Consent.

In the event that access for undertaking the photographic survey and dilapidation report is denied by an adjoining owner, the applicant MUST DEMONSTRATE, in writing, to the satisfaction of Council that all reasonable steps have been taken to obtain access and advise the affected property owner of the reason for the survey and that these steps have failed. Written concurrence must be obtained from Council in such circumstances.

Note: This documentation is for record keeping purposes only and may be used by an applicant or affected property owner to assist in any action required to resolve any dispute over damage to adjoining properties arising from the works. It is in the applicant's and adjoining owner's interest for it to be as full and detailed as possible.

(Reason: Proper management of records)

## **Shoring for Adjoining Property**

C4. Where any shoring for excavation is to be located on or is supporting Council's property, or any adjoining private property, engineering drawings certified as being adequate for their intended purpose by an appropriately qualified and practising structural engineer, showing all details, including the extent of excavation, encroachment and the method of removal and de-stressing of shoring elements, backfilling and compacting of over-excavated cavities on Council's and/or private property with fill suitable for its purpose, must be submitted to the Certifying Authority for approval with the Construction Certificate. A copy of this documentation must be provided to the Council for record purposes. Backfilling and compacting of over-excavated cavities must be addressed as the build-up is progressing through the basements to ensure that compaction is reliable. To obtain the permit for tieback anchors, an 'Application to satisfy development consent' form with payment of the adopted assessment fees, must be made to Council.

Note: Approval of engineering drawings for shoring works to be located on adjoining property by the Certifying Authority does not authorize a trespass on private or public land. All relevant permissions/ legal rights must be obtained to undertake any works on adjoining land.

(Reason: To ensure the protection of existing public infrastructure and adjoining properties)

#### Structural Adequacy of Adjoining Properties - Excavation Works

C5. A report prepared by an appropriately qualified and practising structural engineer detailing the structural adequacy of adjoining properties No. 19 King George Street and No. 38 Bay View Street, which certifies their ability to withstand the proposed excavation and outlines any measures required to be implemented to ensure that no damage will occur to adjoining properties during the course of the works, must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The measures outlined in the certified report must be complied with at all times.

(Reason: To ensure the protection and structural integrity of adjoining properties in close proximity during excavation works)

#### **Geotechnical Report**

- C6. A report prepared by an appropriately qualified Geotechnical Engineer certifying that the existing rock formations and substrate on the site is capable of:
  - a) withstanding the proposed loads to be imposed;
  - b) withstanding the extent of the proposed excavation, including any recommendations for shoring works that may be required to ensure the stability of the excavation;

- c) providing protection and support of adjoining properties; and
- d) the provision of appropriate subsoil drainage during and upon completion of construction works

must be submitted for approval by the Certifying Authority prior to the issue of any Construction Certificate.

Recommendations made in the certified report must be complied with at all times.

Building plans and specifications submitted for approval with any construction certificate application must comply with (a), (b), (c) and (d) above and the certified report, including any recommendations made in the said certified report.

The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To ensure the structural integrity of the subject site and adjoining sites during the excavation process)

## **Sediment Control**

C7. Where construction or excavation activity requires the disturbance of the soil surface or existing vegetation, erosion and sediment control techniques, as a minimum, are to be in accordance with the publication *Managing Urban Stormwater: Soils and Construction* (4th edition, Landcom, 2004) commonly referred to as the "Blue Book" or a suitable and effective alternative method.

A Sediment Control Plan must be prepared and submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate and prior to any works commencing. The Sediment Control Plan must be consistent with the Blue Book and disclose:

- a) All details of drainage to protect and drain the site during the construction processes;
- b) All sediment control devices, barriers and the like;
- c) Sedimentation tanks, ponds or the like;
- d) Covering materials and methods; and
- e) A schedule and programme of the sequence of the sediment and erosion control works or devices to be installed and maintained.
- f) Methods for the temporary and controlled disposal of stormwater during construction.

All works must be undertaken in accordance with the approved Sediment Control plan.

The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To protect the environment from the effects of sedimentation and erosion from development sites)

## Conservation of the Heritage-listed Sandstone Wall on the Site

- C8. The recommendations of the Cantilever Consulting Engineers report with regard to the sandstone perimeter wall on the street boundaries of the site are to be implemented as follows:
  - a) Demolition work should be undertaken by a specialist contractor with experience in heritage projects. During demolition work, the wall should be temporarily braced using suitable bracing methods to ensure stability during construction. The temporary bracing work should be undertaken by a suitably qualified engineer with experience in heritage projects
  - b) The footing for the new 190 mm reinforced concrete wall is to be installed behind the sandstone wall. Geotechnical advice should be sought to determine the distance between the footing and the wall.
  - c) The new 190 mm reinforced concrete wall is to be installed after the concrete footings have cured. Wall ties should be installed during construction of the 190 mm reinforced concrete wall. Wall ties are to be embedded in the mortar of the sandstone wall.
  - d) All cracked/split sandstone blocks are to be replaced
  - e) Where there are cracks in the mortar of the wall, a masonry crack stitching product may be used in order to prevent any future movement. The specification of the crack stitching product should be determined by a specialist contractor.
  - f) The existing mortar is to be reviewed and repointed as required with new mortar of the same consistency by a specialist contractor

(Reason: Conservation of heritage item)

## **Waste Management Plan**

- C9. A Waste Management Plan is to be submitted for approval by the Certifying Authority prior to the issue of any Construction Certificate. The plan must include, but not be limited to:
  - a) The estimated volume of waste and method of disposal for the construction and operation phases of the development;
  - b) The design of the on-site waste storage and recycling area; and
  - c) Administrative arrangements for waste and recycling management during the construction process.

The approved Waste Management Plan must be complied with at all times in the carrying out of the development.

(Reason: To encourage the minimisation of waste and recycling of building waste)

#### **Work Zone**

C10. If a Work Zone is proposed, an application must be made to the North Sydney Local Traffic Committee to install the 'Work Zone'. A Work Zone permit is required to be issued by the Council prior to the issue of any Construction Certificate.

Work Zones are provided specifically for the set down and pick up of materials and not for the parking of private vehicles associated with the site. Works Zones will generally not be approved where there is sufficient space on-site for the setting down and picking up of goods being taken to or from a construction site. If the Works Zone is approved by the Committee, the Applicant must obtain a written copy of the related resolution from the North Sydney Local Traffic Committee and submit a copy of this to the Certifying Authority to enable issue of the Construction Certificate.

Where approval of the 'Work Zone' is given by the Committee, the requirements of the Committee, including installation of the necessary 'Work Zone' signage and payment of any fees, must occur prior to commencement of any works on the site. Further, at the expiration of the Work Zone approval, the developer is required to remove the Work Zone signs and reinstate any previous signs, all at the developer's cost. The requirements imposed by the Committee on the Work Zone permit (or permits) must be complied with at all times.

(Reason: Amenity and convenience during construction)

## **Maintain Property Boundary Alignment Levels**

C11. Except where otherwise approved by Council, the property boundary alignment levels must match the levels which existed prior to the commencement of works. Plans and specifications which document existing and proposed levels adjacent to the site boundaries and which comply with the requirements of this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate.

The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To ensure interface between property and public land remains uniform)

#### **Required Infrastructure Works - Roads Act 1993**

C12. Prior to issue of any Construction Certificate engineering design plans and specifications must be prepared by a qualified civil design engineer. The plans and specifications must be to a detail suitable for construction issue purposes and must provide detail and specification for the following infrastructure works to be completed as part of the development:

## **Road Works**

- a) The redundant laybacks and crossovers on King George Street must be reinstated as kerb gutter and footpath,
- b) construction of a fully new replacement concrete footpath is required adjacent to the redundant laybacks in King George Street. The footpath shall be designed at a single straight grade of approximately 3% falling to the top of kerb, so that it is uniform without showing signs of dipping or rising particularly at entrances.
- reconstruction of the carriageway shoulder will be required, extending out 600 mm from the gutter lip in AC10 50 mm thick, adjacent to all new kerb/gutter works,

Certifying Authorities must not issue a Construction Certificate without the formal written approval of Council (as Roads Authority) under the Roads Act 1993.

The required plans and specifications are to be designed in accordance with North Sydney Council's current documents Infrastructure Specification for Road Works, Drainage and Miscellaneous Works and Performance Guide for Engineering Design and Construction. The drawings must detail existing utility services and trees affected by the works, erosion control requirements and traffic management requirements during the course of works. A detailed survey must be undertaken as

required. Traffic management is to be certified on the drawings as being in accordance with the documents SAA HB81.1 - 1996 - Field Guide for Traffic Control at Works on Roads - Part 1 and RMS Traffic Control at Work Sites (1998). Construction of the works must proceed only in accordance with any conditions attached to the Council Roads Act 1993 approval.

Note: A minimum of 21 days will be required for Council to assess Roads Act submissions. Early submission is recommended to avoid any delays in obtaining a Construction Certificate. A fee to cover cost of assessment (set out in Council's adopted fees and charges) is payable and Council will withhold any consent and approved plans until full payment of the correct fees. Plans and specifications must be marked to the attention of Council's Development Engineers. In addition, a copy of this condition must be provided, together with a covering letter stating the full address of the property and the accompanying DA number.

(Reason: To ensure infrastructure works are designed and constructed to appropriate standards and requirements of the Roads Act 1993)

## Obtain Driveway Crossing Permit under S.138 Roads Act 1993

C13. A driveway crossing and roads infrastructure works permit to suit the approved off-street parking facilities must be granted by the Council prior to the issue of any Construction Certificate. In order to obtain a permit under S.138 of the Roads Act 1993, an application must be made to Council on the 'Vehicular Access Application' form with payment of the adopted assessment/inspection fees. Council will require civil design construction drawings and certification from the applicant's Civil Engineer to verify design details and enable issue of the permit. The requirements of the permit must be complied with at all times.

The civil design drawings must include the following at a minimum:

- a) the vehicular access way must comply with AS 2890.1 and Council's current Vehicular Access Application Guidelines and Specification (gutter bridges not permitted) to ensure that a B85 vehicle will not scrape/strike the surface of the carriageway, layback, vehicular crossing or parking floor,
- b) the width of the vehicular layback must be 4.0 metres (including the wings),
- c) the vehicular crossover must be set square to the kerb,
- d) the crossing (between the layback and the property boundary) must be placed on a single straight grade of approximately 4.5%, falling to the back of the layback,
- e) the gutter levels and boundary footpath levels must match the existing levels and shall not be altered,
- f) the footpath, kerb gutter, and road shoulder must be transitioned at least 2.0 m on both sides of the crossing to ensure uniformity in the road reserve,
- g) the works will require reconstruction of the carriageway shoulder extending out 600mm from the gutter lip in AC10 50mm thick, adjacent to all new gutter works, layback, kerb/gutter,

- h) any twisting of driveway access must occur entirely within the subject property,
- i) all inspection openings, utility services must be adjusted to match the proposed driveway levels,
- sections along centreline and extremities are required at a scale of 1:50 to be taken from the centreline of the roadway through to the parking area itself and must include all changes of grade and levels both existing and proposed,
- k) a longitudinal section along the gutter line at a scale of 1:50 showing how it is intended to blend the vehicular crossing with the existing kerb and gutter,
- a longitudinal section along the footpath property boundary at a scale of 1:50 is required,
- m) the sections must show the calculated clearance to the underside of any overhead structure,

The permit must be granted by Council prior to the issue of any Construction Certificate.

All driveway and infrastructure works on the road reserve must be undertaken in accordance with the terms of the permit issued by Council. Inspections by Council will be required as specified. The Certifying Authority issuing the Construction Certificate must ensure that the permit issued by Council is obtained and referenced on and accompanies the Construction Certificate issued.

(Reason: To facilitate appropriate vehicular access to private sites, without disruption to pedestrian and vehicular traffic)

## Stormwater Management and Disposal Design Plan - Construction Issue Detail

- C14. Prior to issue of the Construction Certificate, the applicant shall have a site drainage management plan prepared by a qualified drainage design engineer. The site drainage management plan must detail the following requirements of North Sydney Council:
  - a) Compliance with BCA drainage requirements, Councils Engineering Performance compliance with BCA drainage requirements, Councils Engineering Performance guide and current Australian Standards and guidelines, such as AS/NZ3500.3.2 1998, National Plumbing and Drainage Code,
  - b) stormwater runoff and subsoil drainage generated by the approved development must be conveyed in a controlled manner by gravity to the kerb and gutter in Bay View Street,
  - the stormwater drainage system shall be designed for an average recurrence interval (A.R.I.) of 1 in 20 years,
  - d) all redundant stormwater pipelines within the footpath area shall be removed and footpath and kerb shall be reinstated,
  - e) pipelines within the footpath area shall be hot dipped galvanised steel hollow section with a minimum wall thickness of 4.0 millimetres and a section height of 100 millimetres,

- f) the design and installation of the rainwater tank(s) must comply with BASIX and Sydney Water requirements. Overflow from the tank(s) shall be connected by gravity to the stormwater disposal system,
- g) any proposed fence/building structure is to be constructed so as not to impede the natural overland flow, and
- h) provision is to be made for the collection and disposal in an approved manner of any overland flow entering the subject property or concentrated as a result of the proposed works,
- surface inlet pits shall be located to catch surface flows and shall be provided at all pipe junctions, changes in pipe direction exceeding 45 degrees, prior to connection to the public drainage system and shall be of sufficient size to accept the flow,
- j) all sub-soil seepage drainage shall be discharged via a suitable silt arrester pit. Details of all plans certified as being adequate for their intended purpose and compliant with the provisions of AS3500.3.2 by an appropriately qualified and practising civil engineer shall be submitted with the application for a Construction Certificate,
- k) prevent any stormwater egress into adjacent properties by creating physical barriers and surface drainage interception,
- l) provide subsoil drainage to all necessary areas with pump out facilities as required.

A site drainage management plan which complies with this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To ensure controlled stormwater management and disposal without nuisance)

## Bond for Damage and Completion of Infrastructure Works - Stormwater, Kerb and Gutter, Footpaths, Vehicular Crossing and Road Pavement

- C15. Prior to the issue of any Construction Certificate, security deposit or bank guarantee must be provided to Council to the sum of \$10,000.00 to be held by Council for the payment of cost for any/all of the following:
  - a. making good any damage caused to any property of the Council as a consequence of the doing of anything to which this consent relates,
  - completing any public work (such as road work, kerbing and guttering, footway construction, stormwater drainage and environmental controls) required in connection with this consent
  - c. Remedying any defects in any such public work that arise within one year for stormwater and 6 months for major road works and two months for vehicular crossing and small associated footpath works, after the work is completed.

The security in accordance with the schedule contained later in these conditions and must be provided by way of a deposit with the Council; or a guarantee satisfactory to Council (such as a satisfactory bank guarantee).

The security will be refundable following the expiration of defect risk period for the particular type of work as specified above (under c)), from the issue of any final Occupation Certificate or completion of public work required to be completed (whichever is the latest) but only upon inspection and release by Council's Engineers.

Council shall have full authority to make use of the bond for such restoration works as deemed necessary by Council in circumstances including the following:

- where the damage constitutes a hazard in which case Council may make use of the security immediately;
- the applicant has not repaired or commenced repairing damage within 48 hours of the issue by Council in writing of instructions to undertake such repairs or works;
- works in the public road associated with the development are to an unacceptable quality; and
- the Certifying Authority must ensure that security is provided to North Sydney Council prior to issue of any Construction Certificate.

(Reason: To ensure appropriate security for works on public land and an appropriate quality for new public infrastructure)

#### **Protection of Trees**

C16. The following tree(s) are required to be protected and retained as part of the development consent in accordance with AS 4970-2009 - Protection of trees on development sites:

Tree	Location	Height
Cypressus leylandii (T2-T6)	Along western boundary	(9 m)

Plans and specifications complying with this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

Any tree(s) shown as being retained on the approved plans (regardless of whether they are listed in the above schedule or not) must be protected and retained in accordance with this condition.

(Reason: Protection of existing environmental and community assets)

## **Section 7.12 Contributions**

C17. A monetary contribution pursuant to the provisions of Section 7.12 of the Environmental Planning and Assessment Act 1979, is to be paid to Council in accordance with the North Sydney Council's Contributions Plan, to be provided for local infrastructure improvements.

Based on the cost of development at the date of determination, the total contribution payable to Council is **\$26,400.00**.

#### Indexation

The monetary contribution required under this consent will be indexed at the time of payment in accordance with quarterly movements in the Consumer Price Index (All Ground Index) for Sydney as published by the Australian Bureau of Statistics.

## **Timing of Payment**

The contribution must be paid to Council prior to issue of any Construction Certificate for any work approved by this consent.

A copy of the North Sydney Contribution Plan can be viewed at North Sydney Council's Customer Service Centre, 200 Miller Street, North Sydney or downloaded via Council's website at <a href="https://www.northsydney.nsw.gov.au">www.northsydney.nsw.gov.au</a>.

(Reason: To provide for local infrastructure identified in the North Sydney Council Local

Contributions Plan 2020)

## **Security Deposit/Guarantee Schedule**

C18. All fees and security deposits/ guarantees in accordance with the schedule below must be provided to Council prior to the issue of any Construction Certificate:

Security Deposit/Guarantee	Amount (\$)
Infrastructure Damage Bond	\$10,000.00
TOTAL BONDS	\$10,000.00

Note: The following fees applicable

Fees	
Section 7.12 Contributions	\$26,400.00
TOTAL FEES	\$26,400.00

The security required by the above schedule must be provided by way of a deposit with the Council; or other such guarantee that is satisfactory to Council (such as a bank guarantee). Any guarantee provided as security must name North Sydney Council as the nominated beneficiary and must not be subject to an expiry date.

(Reason: Compliance with the development consent)

## **Approval for Removal of Trees**

C19. The following tree(s) are approved for removal in accordance with the development consent:

Trees that are acceptable to remove	Location	Height
T1 Lagerstroemia	SW corner of the existing dwelling	(10 m)

Removal of any other tree on the site is not approved, excluding species exempt under Council's Tree Preservation Order.

Any tree(s) shown as being retained on the approved plans (regardless of whether they are listed in the above schedule or not) must be protected and retained in accordance with this condition.

(Reason: Protection of existing environmental and community assets)

#### **BASIX Certificate**

C20. Under clause 97A(3) of the Environmental Planning and Assessment Regulation 2000, it is a condition of this development consent that all the commitments listed in BASIX Certificate No. 1205141S\_03 for the development are fulfilled. Plans and specifications complying with this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To ensure the proposed development will meet the Government's requirements for

sustainability and statutory requirements)

#### **Roofing Materials - Reflectivity**

C21. Roofing materials must be factory pre-finished with low glare and reflectivity properties to be compatible with the colours of neighbouring buildings. The selected roofing material must not cause a glare nuisance or excessive reflectivity to adjoining or nearby properties. Plans and specifications which comply with this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To ensure that excessive glare or reflectivity nuisance from roofing materials does not occur as a result of the development)

## Amended Landscape Plan Required

C22. An amended landscape plan is to be provided with the Construction Certificate plans which includes a landscape schedule to provide for roof top planting to roof of the ground floor rumpus room. The landscaping to this area is to include suitable planting species which will not exceed 300mm above the finished level of the rumpus room roof at maturity. The Certifying Authority be satisfied that the amendments required by this condition are included in the landscape plans approved with the relevant construction certificate:

(Reason: To provide for suitable roof top landscaping to the rumpus room roof area)

D. Prior to the Commencement of any Works (and continuing where indicated)

## Photographic Survey (Heritage Items)

D1. Prior to any works commencing a photographic survey recording, in accordance with the NSW Heritage Office Guidelines "Photographic recording of Heritage Items using file or digital capture", is to be prepared to the satisfaction of Council's Historian and Conservation Planner. Two (2) copies of the photographic survey must be provided to Council.

(Reason: To provide a historical record of heritage significant fabric on site for archival purposes)

#### **Protection of Trees**

D2. All trees that are specifically nominated to be retained by notation on plans or by condition as a requirement of this consent must be maintained and protected during demolition, excavation and construction on the site in accordance with AS4970-2009 (Protection of trees on development sites). A report containing recommendations, and methods of tree protection prepared by an appropriately qualified person must be provided to the Certifying Authority for approval by an appropriately qualified person prior to commencement of any works on the site. Any recommendations must be undertaken for the duration of works on the site.

(Reason: To ensure compliance with the requirement to retain significant planting on the site)

#### **Temporary Fences and Tree Protection**

D3. All protected trees on-site that are specifically nominated as per condition C17 to be retained by notation on plans or by condition as a requirement of this consent must be tagged with luminous tape or the like for purposes of identification prior to demolition, excavation or construction works and must remain so for the duration of works on the site. No materials or builder's waste are to be stored in the vicinity of the nominated tree/trees at any time.

Appropriate fencing or barricades in accordance with AS4970-2009 (Protection of trees on development sites), not less than the distance shown in the schedule hereunder, must be installed to the satisfaction of the Certifying Authority prior to demolition or commencement of any works and must be maintained for the duration of the works: -

(Reason: To protect the trees to be retained on the site during construction works)

## **Public Liability Insurance - Works on Public Land**

D4. Any person or contractor undertaking works on public land must take out Public Risk Insurance with a minimum cover of \$20 million in relation to the occupation of public land and the undertaking of approved works within Council's road reserve or public land, as approved by this consent. The Policy is to note and provide protection/full indemnification for North Sydney Council, as an interested party. A copy of the Policy must be submitted to Council prior to commencement of any works. The Policy must be valid for the entire period that the works are being undertaken.

(Note: Applications for hoarding permits, vehicular crossings etc will require evidence of insurance upon lodgement of the application.)

(Reason: To ensure the community is protected from the cost of any claim for damages arising from works on public land)

## **Asbestos Material Survey**

D5. Prior to the commencement of any works, a report must be prepared by a suitably qualified person in relation to the existing building fabric to be demolished and/or disturbed identifying the presence or otherwise of asbestos contamination and, if asbestos contamination is present, making recommendations as to the work required to safely address the contamination.

Any demolition works or other works identified in the report as having to be carried out must be carried out in accordance with the recommendations of the report and the following:

- a) the removal of asbestos must be undertaken by a WorkCover licensed contractor;
- b) all removal must be in strict accordance with the requirements of the WorkCover Authority in relation to the removal, handling and disposal of material containing asbestos and any Work Safe Australia requirements.
- c) during the removal of any asbestos a sign stating "DANGER ASBESTOS REMOVAL IN PROGRESS" must be erected in a visible position at the boundary of the site; and
- d) Waste disposal receipts must be provided to the Certifying Authority as proof of correct disposal of asbestos laden waste.

The report must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the report, and other plans, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To ensure the long-term health of workers on site and occupants of the building is not

put at risk unnecessarily)

#### **Commencement of Works' Notice**

D6. Building work, demolition or excavation in accordance with this development consent must not be commenced until the developer has given at least two days' notice to North Sydney Council of the person's intention to commence building work, demolition or excavation in accordance with this development consent.

(Reason: To ensure appropriate safeguarding measures are in place prior to the commence-ment

of any building work, demolition or excavation

## E. During Demolition and Building Work

#### Re-use of Sandstone

E1. Sandstone blocks (if any) removed from the site are to be either stored for re-use on site or offered to Council in the first instance.

Note: The provisions of the Heritage Act may also apply to altering any sandstone elements on any

site)

(Reason: To allow for preservation of cultural resources within the North Sydney Council area)

## **Parking Restrictions**

E2. Existing public parking provisions in the vicinity of the site must be maintained at all times during works. The placement of any barriers, traffic cones, obstructions or other device in the road shoulder or kerbside lane is prohibited without the prior written consent of Council. Changes to existing public parking facilities/restrictions must be approved by the North Sydney Local Traffic Committee. The Developer will be held responsible for any breaches of this condition and will incur any fines associated with enforcement by Council regulatory officers.

(Reason: To ensure that existing kerbside parking provisions are not compromised during works)

## **Road Reserve Safety**

E3. All public footways and roadways fronting and adjacent to the site must be maintained in a safe condition at all times during the course of the development works, with no obstructions caused to the said footways and roadways. Construction materials and plant must not be stored in the road reserve without approval of Council. A safe pedestrian circulation route and a pavement/route free of trip hazards must be maintained at all times on or adjacent to any public access ways fronting the construction site.

Where public infrastructure is damaged, repair works must be carried out in when and as directed by Council officers (at full Developer cost). Where pedestrian circulation is diverted on to the roadway or verge areas, clear directional signage and protective barricades must be installed in accordance with AS1742-3 (1996) "Traffic Control Devices for Work on Roads". If pedestrian circulation is not satisfactorily maintained across the site frontage, and action is not taken promptly to rectify the defects, Council may undertake proceedings to stop work.

(Reason: Public Safety)

## **Temporary Disposal of Stormwater Runoff**

E4. During construction, stormwater runoff must be disposed in a controlled manner that is compatible with the erosion and sediment controls on the site. Immediately upon completion of any impervious areas on the site (including roofs, driveways, paving) and where the final drainage system is incomplete, the necessary temporary drainage systems must be installed to reasonably manage and control runoff as far as the approved point of stormwater discharge. Such ongoing measures must be to the satisfaction of the Certifying Authority.

(Reason: Stormwater control during construction)

## **Geotechnical Stability during Works**

E5. A contractor with specialist excavation experience must undertake the excavations for the development and a suitably qualified and consulting geotechnical engineer must oversee the excavation procedure.

Geotechnical aspects of the development work, namely appropriate excavation method and vibration control, support and retention of excavated faces, and hydrogeological considerations must be undertaken in accordance with the recommendations of the report on Geotechnical Investigation Project ID 99916.00 prepared by Douglas Partners, dated January 2021 and all subsequent geotechnical inspections carried out during the excavation and construction phase.

Approval must be obtained from all affected property owners, including North Sydney Council where rock anchors (both temporary and permanent) are proposed below adjacent private or public property.

(Reason: Ensure appropriate professional are engaged at appropriate stages during construction)

## **Council Inspection of Public Infrastructure Works**

- E6. During the works on public infrastructure reverting to Council's care and control, Council's development engineer may undertake inspections of the works at the following hold points:
  - a) Formwork for layback, kerb/gutter, footpath, etc.

All works must proceed in accordance with Roads Act 1993 approvals or other permits relating to roads issued by Council. A minimum of 48 hours' notice must be given to Council to book an inspection. Work must not proceed until the works or activity covered by the inspection is approved.

(Reason: To ensure quality of construction joints and connections in the drainage system)

#### **Dust Emission and Air Quality**

- E7. The following must be complied with at all times:
  - (a) Materials must not be burnt on the site.
  - (b) Vehicles entering and leaving the site with soil or fill material must be covered.
  - (c) Dust suppression measures must be carried out to minimise wind-borne emissions in accordance with the NSW Department of Housing's 1998 guidelines Managing Urban Stormwater: Soils and Construction.
  - (d) Odour suppression measures must also be carried out where appropriate so as to prevent nuisance occurring at adjoining properties.

(Reason: To ensure residential amenity is maintained in the immediate vicinity)

#### **Noise and Vibration**

E8. The works must be undertaken in accordance with the "Interim Construction Noise Guideline," published by the NSW Environment Protection Authority, to ensure excessive levels of noise and vibration do not occur so as to minimise adverse effects experienced on any adjoining land.

(Reason: To ensure residential amenity is maintained in the immediate vicinity)

## No Work on Public Open Space

E9. No work can be undertaken within adjoining public lands (i.e., Parks, Reserves, Roads, etc) without the prior written consent of Council. In this regard the developer is to liaise with Council prior to the commencement of any design works or preparation of a Construction and Traffic Management Plan.

(Reason: Protection of existing public infrastructure and land and to ensure public safety and proper management of public land)

#### **Developer's Cost of Work on Council Property**

E10. The developer must bear the cost of all works associated with the development that occurs on Council's property, including the restoration of damaged areas.

(Reason: To ensure the proper management of public land and funds)

#### **Protection of Trees**

E11. All trees required to be retained, as part of this consent must be protected from any damage during construction works in accordance with AS4970-2009.

In the event that any tree required to be retained is damaged during works on the site, notice of the damage must be given to Council forthwith.

#### Notes:

- a. If the nominated tree is damaged to a significant degree or removed from the site without prior written approval being obtained from Council, the issuing of fines or legal proceedings may be commenced for failure to comply with the conditions of this consent.
- b. An application to modify this consent pursuant to Section 96 of *the Environmental Planning and Assessment Act 1979* will be required to address the non-compliance with any of the conditions of consent relating to the retention of nominated trees, and Council may require tree replenishment.

(Reason: Protection of existing environmental infrastructure and community assets)

#### Trees to be Removed

E12. All trees on the site must be protected and retained save for those expressly identified below as being approved for removal: -

Trees that are acceptable to remove	Location	Height
T1 Lagerstroemia	SW corner of the existing dwelling	(10 m)

(Reason: To ensure compliance with the terms of this development consent)

#### **Noxious Plants**

E13. All lantana, privet, rubber trees, asthma weed, and other declared noxious plants on the site, must be eradicated before the commencement of landscape works.

(Reason: To ensure that plants identified as weed species are not allowed to proliferate or

interfere with a quality landscaping outcome)

#### **Special Permits**

E14. Unless otherwise specifically approved in writing by Council, all works, processes, storage of materials, loading and unloading associated with the development must occur entirely on the property.

The developer, owner or builder may apply for specific permits available from Council's Customer Service Centre for the undermentioned activities on Council's property. In the event that a permit is granted by Council for the carrying out of works, processes, storage of materials, loading and unloading associated with the development on Council's property, the development must be carried out in accordance with the requirements of the permit. A minimum of forty-eight (48) hours' notice is required for any permit:

## 1) On-street mobile plant

Eg. cranes, concrete pumps, cherry-pickers, etc. - restrictions apply to the hours of operation, the area of operation, etc. Separate permits are required for each occasion and each piece of equipment. It is the developer's, owner's and builder's responsibilities to take whatever steps are necessary to ensure that the use of any equipment does not violate adjoining property owner's rights.

(Reason: Proper management of public land)

## 2) Hoardings

Permits are required to erect Class A and Class B hoardings. If an 'A' Class hoarding is to alienate a section of Council's property, that section will require a permit for the occupation of Council's property.

(Reason: Proper management of public land)

## 3) Storage of building materials and building waste containers (skips) on Council's property

Permits to utilise Council property for the storage of building materials and building waste containers (skips) are required for each location. Failure to obtain the relevant permits will result in the building materials or building waste containers (skips) being impounded by Council with no additional notice being given. Storage of building materials and waste containers on open space reserves and parks is prohibited.

(Reason: Proper management of public land)

## 4) Kerbside restrictions, construction zones

Attention is drawn to the existing kerbside restrictions adjacent to the development. Should alteration of existing kerbside restrictions be required, or the provision of a construction zone, the appropriate application must be made and the fee paid to Council. Alternatives to such restrictions may require referral to Council's Traffic Committee and may take considerable time to be resolved. An earlier application is suggested to avoid delays in construction programs.

(Reason: Proper management of public land)

#### **Construction Hours**

E15. Construction activities and works approved under this consent must be carried out only within the hours stipulated in the following table

Standard Construction Hours		
Location	Day	Hours
All Other Zones	Monday - Friday	7.00 am - 5.00 pm
(Excl. B3 Commercial Core and	Saturday	8.00 am - 1.00 pm
B4 Mixed-use zone)	Sunday, Public holiday	No work permitted

Construction activities for development approval under this consent must be carried out in accordance with the standard construction hours above and any Construction Noise Management Plan required under this consent.

In the event of breach to the approved hours of construction Council may take enforcement action under Part 9 of the EP&A Act 1979 and in accordance with Council's adopted Compliance and Enforcement Policy.

(Reason: To ensure that works do not interfere with reasonable amenity expectations of

residents and the community)

#### **Installation and Maintenance of Sediment Control**

E16. Erosion and sediment controls must be installed and maintained at all times in accordance with the Sediment and erosion control plan submitted and approved with the Construction Certificate.

Erosion and sediment measures must be maintained in accordance with the publication Managing Urban Stormwater: Soils and Construction (4th edition, Landcom, 2004), commonly referred to as the "Blue Book" and can only be removed when development activities have been completed and the site fully stabilised.

(Reason: To protect the environment from the effects of sedimentation and erosion from

development sites)

#### **Sediment and Erosion Control Signage**

E17. A durable sign must be erected during building works in a prominent location on site, warning of penalties should appropriate erosion and sedimentation control devices not be maintained. A sign of the type referred to in this condition is available from Council.

(Reason: To protect the environment from the effects of sedimentation and erosion from

development sites)

#### Site Amenities and Facilities

E18. Where work involved in the erection and demolition of a building is being carried out, amenities which satisfy applicable occupational health and safety and construction safety regulations, including any WorkCover Authority requirements, must be provided and maintained at all times. The type of work place determines the type of amenities required.

Further information and details can be obtained from the Internet at <a href="www.workcover.nsw.gov.au">www.workcover.nsw.gov.au</a>.

(Reason: To ensure the health and safety of the community and workers on the site)

## **Health and Safety**

E19. All work undertaken must satisfy applicable occupational health and safety and construction safety regulations, including any WorkCover Authority requirements to prepare a health and safety plan. Site fencing must be installed sufficient to exclude the public from the site. Safety signs must be erected that warn the public to keep out of the site and provide a contact telephone number for enquiries.

Further information and details regarding occupational health and safety requirements for construction sites can be obtained from the internet at <a href="https://www.workcover.nsw.gov.au">www.workcover.nsw.gov.au</a>.

(Reason: To ensure the health and safety of the community and workers on the site)

## **Archaeological Discovery During Works**

E20. Should any historical or Aboriginal relic be discovered on the site during demolition, excavation or site preparatory works, all excavation or disturbance to the area is to stop immediately and the Heritage Council of NSW must be informed in accordance with the provisions of the Heritage Act 1977 and/or National Parks and Wildlife Act, 1974. Works must not recommence until such time as approval to recommence is given in writing by Council or a permit from the Director of the NPWS is issued.

(Reason: To prevent the unnecessary destruction or removal of unrecorded historical or

Aboriginal relics)

#### **Prohibition on Use of Pavements**

E21. Building materials must not be placed on Council's footpaths, roadways, parks or grass verges, (unless a permit is obtained from Council beforehand). A suitable sign to this effect must be erected adjacent to the street alignment.

(Reason: To ensure public safety and amenity on public land)

#### **Plant and Equipment Kept Within Site**

E22. All plant and equipment used in the undertaking of the development/ works, including concrete pumps, wagons, lifts, mobile cranes, hoardings etc, must be situated within the boundaries of the site (unless a permit is obtained from Council beforehand) and so placed that all concrete slurry, water, debris and the like must be discharged onto the building site, and is to be contained within the site boundaries.

Details of Council requirements for permits on public land for standing plant, hoardings, storage of materials and construction zones and the like are available on Council's website at <a href="https://www.northsydney.nsw.gov.au">www.northsydney.nsw.gov.au</a>.

(Reason: To ensure public safety and amenity on public land)

#### **Waste Disposal**

E23. All records demonstrating the lawful disposal of waste must be retained and kept readily accessible for inspection by regulatory authorities such as North Sydney Council and the Environmental Protection Authority.

(Reason: To ensure the lawful disposal of construction and demolition waste)

#### **Asbestos Removal**

E24. All demolition works involving the removal and disposal of asbestos cement must only be undertaken by contractors who hold a current WorkCover Asbestos or "Demolition Licence" and a current WorkCover "Class 2" (Restricted) Asbestos Licence and removal must be carried out in accordance with National Occupational Health and Safety Commission.

(Reason: To ensure works are carried out in accordance with relevant WorkCover requirements).

F. Prescribed Conditions imposed under EP&A Act and Regulations and other relevant Legislation

#### **National Construction Code**

F1. All building work must be carried out in accordance with the provisions of the National Construction Code.

(Reason: Prescribed - Statutory)

## **Home Building Act**

- F2. 1) Building work that involves residential building work (within the meaning and exemptions provided in the Home Building Act 1989) for which the *Home Building Act* 1989 requires there to be a contract of insurance under Part 6 of that Act must not be carried out unless the Principal Certifying Authority for the development to which the work relates has given North Sydney Council written notice of the contract of insurance being issued and of the following:
  - a) in the case of work for which a principal contractor is required to be appointed:
    - i) the name and licence number of the principal contractor, and
    - ii) the name of the insurer by which the work is insured under Part 6 of that Act, or
  - (b) in the case of work to be done by an owner-builder:
    - (i) the name of the owner-builder, and
    - (ii) if the owner-builder is required to hold an owner-builder permit under that Act, the number of the owner-builder permit.
  - 2) If arrangements for doing residential building work are changed while the work is in progress such that the information submitted to Council in accordance with this conditions is out of date, work must cease and no further work may be carried out unless the Principal Certifying Authority for the development to which the work relates (not being the Council), has given the Council written notice of the updated information.

Note: A certificate purporting to be issued by an approved insurer under Part 6 of the Home Building Act 1989 that states that a person is the holder of an insurance policy issued for the purposes of that Part is, for the purposes of this clause, sufficient evidence that the person has complied with the requirements of that Part.

(Reason: Prescribed - Statutory)

## Appointment of a Principal Certifying Authority (PCA)

F3. Building work, demolition or excavation in accordance with the development consent must not be commenced until the developer has appointed a Principal Certifying Authority for the building work in accordance with the provisions of the EP&A Act and its Regulations.

(Reason: Statutory; To ensure appropriate safeguarding measures are in place prior to the commencement of any building work, demolition or excavation)

#### **Construction Certificate**

F4. Building work, demolition or excavation in accordance with the development consent must not be commenced until a Construction Certificate for the relevant part of the building work has been issued in accordance with the provisions of the EP&A Act and its Regulations.

(Reason: Statutory; To ensure appropriate safeguarding measures are in place prior to the commencement of any building work, demolition or excavation)

## **Occupation Certificate**

F5. A person must not commence occupation or use of the whole or any part of a new building (new building includes an altered portion of, or an extension to, an existing building) unless an Occupation Certificate has been issued in relation to the building or part. Only the Principal Certifying Authority appointed for the building work can issue an Occupation Certificate.

(Reason: Statutory)

## **Critical Stage Inspections**

F6. Building work must be inspected by the Principal Certifying Authority on the critical stage occasions prescribed by the EP&A Act and its Regulations, and as directed by the appointed Principal Certifying Authority.

(Reason: Statutory)

## **Commencement of Works**

F7. Building work, demolition or excavation in accordance with this development consent must not be commenced until the developer has given at least two days' notice to North Sydney Council of the person's intention to commence the erection of the building.

(Reason: Statutory; To ensure appropriate safeguarding measures are in place prior to the commencement of any building work, demolition or excavation)

## **Excavation/Demolition**

- F8. 1) All excavations and backfilling associated with the erection or demolition of a building must be executed safely and in accordance with appropriate professional standards.
  - 2) All excavations associated with the erection or demolition of a building must be properly guarded and protected to prevent them from being dangerous to life or property.
  - 3) Demolition work must be undertaken in accordance with the provisions of AS2601- Demolition of Structures.

(Reason: To ensure that work is undertaken in a professional and responsible manner and protect adjoining property and persons from potential damage)

## **Protection of Public Places**

- F9. 1) A hoarding and site fencing must be erected between the work site and adjoining public place.
  - 2) If necessary, an awning is to be erected, sufficient to prevent any substance from, or in connection with, the work falling into the public place.
  - 3) The work site must be kept lit between sunset and sunrise if it is likely to be hazardous to persons in the public place.
  - 4) Any such hoarding, fence or awning is to be removed when the work has been completed.

5) No access across public reserves or parks is permitted.

lote: Prior to the erection of any temporary fence or hoarding over property owned or managed by Council, written approval must be obtained. Any application needs to be accompanied by plans indicating the type of hoarding and its layout. Fees are assessed and will form part of any approval given. These fees must be paid prior to the approval being given. Approval for hoardings will generally only be given in association with approved building works, maintenance or to ensure protection of the public. An application form for a Hoarding Permit can be downloaded from Council's website.

(Reason: To ensure public safety and the proper management of public land)

## Site Sign

- F10. 1) A sign must be erected in a prominent position on the site
  - a) stating that unauthorised entry to the work site is prohibited;
  - b) showing the name of the principal contractor (or person in charge of the work site), and a telephone number at which that person may be contacted at any time for business purposes and outside working hours; and
  - c) showing the name, address and telephone number of the Principal Certifying Authority for the work.
  - 2) Any such sign must be maintained while to building work or demolition work is being carried out but must be removed when the work has been completed.

(Reason: Prescribed - Statutory)

## G. Prior to the Issue of an Occupation Certificate

## Infrastructure Repair and Completion of Works

- G1. Prior to the issue of any Occupation Certificate any and all works relating to the development:
  - a. in the road reserve must be fully completed; and
  - b. to repair and make good any damaged public infrastructure caused as a result of any works relating to the development (including damage caused by, but not limited to, delivery vehicles, waste collection, contractors, sub-contractors, concrete vehicles) must be fully repaired;

To the satisfaction of Council Engineers at no cost to Council.

(Reason: Maintain quality of Public assets)

## **Certification- Civil Works**

An appropriately qualified and practising Civil Engineer must certify to the Certifying Authority that the stormwater drainage system is constructed in accordance with this consent and the provisions of the applicable Australian Standard. A copy of the certificate must be submitted to Council (if it is not the Certifying Authority) upon completion of the development works and prior to the issue of an Occupation Certificate.

b) An appropriately qualified and practicing Civil Engineer must certify to the Certifying Authority that the vehicular crossing and associated works and road works were constructed in accordance with this consent and any approval for works in the road reserve issued by the Council. A copy of the certificate must be submitted to Council (if it is not the Certifying Authority), upon completion of the development works and prior to the issue of an Occupation Certificate.

(Reason: Compliance with the Consent)

## **Works as Executed Drawings**

G3. A works-as-executed survey drawing (W.A.E.) of the completed stormwater drainage system must be obtained. The W.A.E. survey drawing must show the alignment, depth and grade of the stormwater drainage pipelines, pits and ancillary plumbing. The W.A.E. survey drawing must be reviewed by a qualified and practising civil engineer and certification provided to the Certifying Authority that the asbuilt system achieves the design intent of the plans approved with the Construction Certificate. Certification must be provided with the W.A.E. survey drawing to the Certifying Authority prior to the issue of an Occupation Certificate.

A copy of the WAE survey drawing and certification must be submitted to the Council if it is not the Certifying Authority.

(Reason: Compliance with the Consent)

## **Damage to Adjoining Properties**

G4. All precautions must be taken to prevent any damage likely to be sustained to adjoining properties. Adjoining owner property rights and the need for owner's permission must be observed at all times, including the entering onto land for the purpose of undertaking works.

(Reason: To ensure adjoining owner's property rights are protected).

## **Utility Services**

G5. All utility services shall be adjusted to the correct levels and/or location/s required by this consent, prior to issue of an occupation certificate. This shall be at no cost to Council.

(Reason: To ensure compliance with the terms of this consent)

## **Certification of Tree Condition**

G6. Prior to the issue of an Occupation Certificate, a report prepared by an appropriately qualified person (being an arborist or the like) must be submitted to the Certifying Authority, describing the health of the tree(s) specifically nominated below:

Tree	Location	Height
Cypressus leylandii (T2-T6)	Along western boundary	(9 m)

The report must detail the condition and health of the nominated tree(s) upon completion of the works and shall certify that the tree(s) has/have not been significantly damaged during the works on the site and has/have reasonable prospects for survival.

(Reason: To ensure compliance with the terms of this consent)

## **BASIX Completion Receipt**

G7. In accordance with Section 45 of the Environmental Planning and Assessment (Development Certification and Fire Safety) Regulation 2021, prior to issuing a final occupation certificate the Certifying Authority must provide a BASIX completion receipt.

(Reason: To ensure compliance with the Regulations)

#### Landscaping

G8. The landscaping shown in the landscape plans numbered L100F and L102 Rev E prepared by Spirit Level, referred to in Condition A1 and amended by Condition C23, must be completed prior to the issue of any Occupation Certificate.

The Tree management (TMPP) contained within arborist report prepared by George Palmer, Pty Ltd, dated January 2021, shall be adhered to.

- 1 x Lagerstroemia indica within the front setback (Bay View Street frontage) shall be 200 l as recommended in arborist report.
- 2 x Backhousia within rear setback shall be 100 l.

Roof top landscaping to the rumpus room roof is to be maintained to have a maximum height of 300mm above the finished level of the rumpus room roof.

(Reason: To ensure compliance)

## **Damage to Adjoining Properties**

- G9. On completion of the development the subject of this consent and prior to the issue of the Occupation Certificate, a report is to be prepared by an appropriately qualified consultant and is to be provided to the Certifying Authority (and a copy to Council if it is not the Certifying Authority) certifying:
  - a) whether any damage to adjoining properties has occurred as a result of the development;
  - b) the nature and extent of any damage caused to the adjoining property as a result of the development;
  - c) the nature and extent of works required to rectify any damage caused to the adjoining property as a result of the proposed development;
  - d) the nature and extent of works carried out to rectify any damage caused to the adjoining property as a result of the development; and
  - e) the nature and extent of any agreements entered into for rectification of any damage caused to the adjoining property as a result of the development.

The report and certification must reference the dilapidation survey and reports required to be provided to the Certifying Authority in accordance with this consent.

All costs incurred in achieving compliance with this condition shall be borne by the developer.

(Reason: To ensure adjoining owner's property rights are protected in so far as possible)