

200 Miller Street, North Sydney, NSW 2060 | ABN 32 353 260 317
All correspondence PO Box 12, North Sydney, NSW 2059
P (02) 9936 8100 | E council@northsydney.nsw.gov.au
W www.northsydney.nsw.gov.au

Claude Neon Pty Ltd c/- Project Flow Pty Ltd Suite 3, Level 1 30 Grose Street PARRAMATTA NSW 2150

NORTH SYDNEY COUNCIL

> D103/22 RB6 (CIS)

ENVIRONMENTAL PLANNING AND ASSESSMENT ACT, 1979 AS AMENDED NOTICE OF DETERMINATION - Approval

| Development Application Number: | 103/22 | |
|--|---|--|
| Land to which this applies: | 76 Berry Street, North Sydney Lot No.: 19, DP: 701376 | |
| Applicant: | Claude Neon Pty Ltd, C/- Project Flow Pty Ltd | |
| Proposal: | Signage: installation of three illuminated signs on the building | |
| Determination of Development Application: | Subject to the provisions of Section 4.17 of <i>the Environmental Planning and Assessment Act 1979,</i> approval has been granted subject to conditions in the notice of determination. | |
| Date of Determination: | 21 October 2022 | |
| Reasons for Approval | The development application as amended on 15 August 2022 has been assessed against all applicable environmental planning instruments and was found to be generally satisfactory, including in relation to the <i>North Sydney Local Environmental Plan 2013</i> and <i>North Sydney Development Control Plan 2013</i> subject to conditions to address amenity concerns in relation to illumination, light spillage, wayfinding and clear and effective communication of a single corporate entity. | |

Amenity and environmental impacts are addressed by conditions to address light spill, with a curfew of 8.00 pm-7.00 am for the sign on the eastern elevation, no illumination to be permitted for the sign on the northern elevation. The existing sign on the western elevation to be removed. and the consent under DA 275/14 surrendered. A condition requires the signage to provide for a single corporate entity for the building, being 'TATA' logo which is permitted on both the eastern and northern elevations.

Subject to compliance with these conditions, the application is considered to achieve the criteria and provisions for building identification signage as outlined in the SEPP 64, Transport Corridor Outdoor Advertising and Signage Guidelines, *North Sydney Local Environmental Plan 2013* and North Sydney Development Control Plan 2013.

| Consent to operate from: | 21 October 2022 | |
|--|--|--|
| Consent will lapse on: | 21 October 2027 | |
| Period of Consent | Subject to Section 4.20 of the Act, this consent becomes effective and operates from the date listed above. The consent lapses five years after the date of consent in accordance with Section 4.53 of the Act and cannot be extended. To activate this consent, works must physically commence onsite 21 October 2027. | |
| | The subject development application was notified to adjoin- ing properties and the Central Business District/ Stanton Precinct for 14 days. There were three submissions received in response to the notification period that raised concerns in relation to light spillage from the proposed illumination of the three proposed business identification signs. Consideration has been given to adverse social impacts due | |
| How community views were taken into account: | to uncontrolled light spillage, and suitable conditions have been imposed to address adverse residential amenity impacts requiring a curfew of 8.00 pm-7.00am seven days for the sign on the eastern elevation and no illumination to be permitted for the sign on the northern elevation. The amended application was not renotified as there was a reduction in impacts from the amended proposal which reduced the amount of signage from multiple signs on three elevations to a sign on the eastern and northern elevations. Conditions of consent have been recommended to maintain the amenity of adjoining land uses and the character of the streetscape. | |

Review of determination and right of appeal:

Within six months after the date of notification of the decision, a review of this determination can be requested under Division 8.2 of the Act or an appeal to the Land and Environment Court made pursuant to the provisions of Section 8.7 of the Act. A review of determination should be lodged as soon as possible, and preferably no later two months after the date of notification of the decision to enable the review to be completed within the six-month period.

Plans endorsed by the consent authority - please refer to condition A1.

Endorsed for and on behalf of North Sydney Council

22 October 2022

DATE



(i) Conditions

Consent is granted subject to the following conditions imposed pursuant to Section 4.17 of *the Environmental Planning and Assessment Act 1979* ("the *Act*") and the provisions of the *Environmental Planning and Assessment Regulation 2000* ("the *Regulation*") such conditions being reasonable and relevant to the development as assessed pursuant to Section 4.17 of the Act.

(ii) Definitions

Unless specified otherwise, words have the same meaning as defined by the *Act*, the *Regulation* and the *Interpretation Act* 1987 as in force at the date of consent.

Applicant means the applicant for this consent.

Approved Plans means the plans endorsed by Council referenced by this consent as amended by conditions of this consent.

AS or **AS/NZS** means Australian Standard[®] or Australian/New Zealand Standard[®], respectively, published by Standards Australia International Limited.

NCC means the National Construction Code as published by the Australian Building Codes Board as in force at the date of issue of any *Construction Certificate*.

Council means North Sydney Council.

Court means the Land and Environment Court.

Local Native Plants means species of native plant endemic to North Sydney LGA.

Stormwater Drainage System means all works, facilities and documentation relating to:

- The collection of stormwater,
- The retention of stormwater,
- The reuse of stormwater,
- The detention of stormwater,
- The controlled release of stormwater; and
- Connections to easements and public stormwater systems.

Owner means the owner of the *site* and successors in title to the *site*.

Owner Builder has the same meaning as in the Home Building Act 1989.

Principal Certifier for building or subdivision work means the certifier appointed as the principal certifier for the building work under section 6.6 (1) or for the subdivision work under section 6.12 (1).

Principal Contractor for building work means the person responsible for the overall coordination and control of the carrying out of the building work.

Note: If any residential building work is involved, the principal contractor must be the holder of a contractor licence under the *Home Building Act 1989*.

Professional Engineer has the same meaning as in the NCC.

Public Place has the same meaning as in the Local Government Act 1993.

Road has the same meaning as in the *Roads Act* 1993.

SEE means the final version of the Statement of Environmental Effects lodged by the Applicant.

Site means the land being developed subject to this consent.

NSLEP 2013 means *North Sydney Local Environmental Plan* 2013

NSDCP 2013 means North Sydney Development Control Plan 2013

Work for the purposes of this consent means:

- the use of land in connection with development,
- the subdivision of land,
- the erection of a building,
- the carrying out of any work,
- the use of any site crane, machine, article, material, or thing,
- the storage of any waste, materials, site crane, machine, article, material, or thing,
- the demolition of a building,
- the piling, piercing, cutting, boring, drilling, rock breaking, rock sawing or excavation of land,
- the delivery to or removal from the site of any machine, article, material, or thing, or
- the occupation of the site by any person unless authorised by an occupation certificate.
- Note: **Interpretation of Conditions** Where there is any need to obtain an interpretation of the intent of any condition this must be done in writing to Council and confirmed in writing by Council.

INDEX OF CONDITIONS

| | | Page No. |
|------|--|-----------|
| А. | Conditions that Identify Approved Plans | |
| A1. | Development in Accordance with Plans/Documentation | 8 |
| A2. | Plans on Site | 8 |
| A3. | No Demolition of Extra Fabric | 8 |
| A4. | Terms of Consent | 8 |
| С. | Prior to the Issue of a Construction Certificate (and ongoing, where indicated) | |
| C1. | Dilapidation Report Damage to Public Infrastructure | 9 |
| C2. | Waste Management Plan | 10 |
| C3. | Bond for Damage and Completion of Infrastructure Works - Stormwater, | |
| | Kerb and Gutter, Footpaths, Vehicular Crossing and Road Pavement | 10 |
| C4. | Location of Plant | 11 |
| C5. | Noise from Plant and Equipment | 11 |
| C6. | Vibration from Plant and Equipment | 11 |
| C7. | Security Deposit/Guarantee Schedule | 12 |
| C8. | Outdoor Lighting | 12 |
| C9. | Signage Design - Control of the Obtrusive Effects of Outdoor Lighting | 12 |
| C10. | Amended Plans to Show Signage Design and Scale - Single Corporate Entity | 13 |
| D. | Prior to the Commencement of any Works (and continuing where indicated) | |
| D1. | Public Liability Insurance - Works on Public Land | 13 |
| D2. | Commencement of Works' Notice | 13 |
| D3. | Removal of Signs Approved under DA 275/14 | 13 |
| Е. | During Demolition and Building Work | |
| E1. | Parking Restrictions | 14 |
| E2. | Road Reserve Safety | 14 |
| E3. | Temporary Disposal of Stormwater Runoff | 14 |
| E4. | Removal of Extra Fabric | 14 |
| E5. | Noise and Vibration | 15 |
| E6. | No Work on Public Open Space | 15 |
| E7. | Developer's Cost of Work on Council Property | 15 |
| E8. | No Removal of Trees on Public Property | 15 |
| E9. | Special Permits | 15 |
| E10. | Construction Hours | 16 |
| E11. | Health and Safety | 17 |
| E12. | Prohibition on Use of Pavements | 17 |
| E13. | Plant and Equipment Kept Within Site | 17 |
| E14. | Waste Disposal | 17 |
| F. | Prescribed Conditions imposed under EP&A Act and Regulations and other relevant Le | gislation |

| F1. | National Construction Code | 17 |
|-----|---|----|
| F2. | Home Building Act | 18 |
| F3. | Appointment of a Principal Certifying Authority (PCA) | 18 |
| F4. | Construction Certificate | 18 |

| F5. | Occupation Certificate | 18 |
|------|---|----|
| F6. | Critical Stage Inspections | 18 |
| F7. | Commencement of Works | 18 |
| F8. | Demolition | 18 |
| F9. | Protection of Public Places | 19 |
| F10. | Site Sign | 19 |
| G. | Prior to the Issue of an Occupation Certificate | |
| G1. | Damage to Adjoining Properties | 19 |
| G2. | Utility Services | 20 |
| G3. | Compliance with Certain Conditions | 20 |
| I. | Ongoing/Operational Conditions | |
| 11. | Hours of Illumination | 20 |
| 12. | Signage Illumination Intensity | 20 |
| 13. | Roof Top Lighting | 20 |
| 14. | Automated Timing Device | 21 |
| 15. | No Flashing | 21 |
| 16. | Maintenance of Signage Structure | 21 |

A. Conditions that Identify Approved Plans

Development in Accordance with Plans/Documentation

A1. The development must be carried out in accordance with the following drawings endorsed with Council's approval stamp and other documentation listed in the table to this clause, or included in other conditions, except where amended by other conditions of this consent.

| Plan No. | Rev | Title | Drawn by | Dated |
|----------------------------|-----|---|----------|------------|
| Page 1 of 4, Job N55681 | D | Sky Sign - Eastern and Northern Elevation - Existing, Proposed and Night Visuals | TD | 11/08/2022 |
| Page 2 of 4, Job N55681 | D | Sign 1 and 2: Illuminated Sky Sign - Front View, Isometric, Typical Section and Construction Notes | TD | 11/08/2022 |
| Page 3 of 4, Job N55681 | D | Eastern Elevation | TD | 11/08/2022 |
| Page 4 of 4, Job N55681 | D | Site Plan showing Proposed Location for Sky Signs on Eastern and Northern Elevation | TD | 11/08/2022 |

The above plans are to be amended, as shown clouded red on the plans, in accordance with **Condition C10** *Amended Plans to show Signage Design and Scale - Single Corporate Entity.*

(Reason: To ensure that the form of the development undertaken is in accordance with the determination of Council, Public Information)

Plans on Site

A2. A copy of all stamped approved plans, specifications and documents (including the plans, specifications and documents submitted and approved with the Construction Certificate) must be kept on site at all times so as to be readily available for perusal by any officer of Council or the Principal Certifying Authority.

All documents kept on site in accordance with this condition must be provided to any officer of the Council or the certifying authority upon their request.

(Reason: To ensure that the form of the development undertaken is in accordance with the determination of Council, Public Information and to ensure ongoing compliance)

No Demolition of Extra Fabric

A3. Alterations to, and demolition of the existing building shall be limited to that documented on the approved plans.

(Reason: To ensure compliance with the approved development)

Terms of Consent

A4. Approval is granted for the removal of the existing signage on the eastern elevation and western elevation, and the construction of two (2) building identification signs, on the eastern elevation, which is to be illuminated with curfew, and on the northern elevation which is to be non-illuminated. The signage on both elevations is to display one single corporate entity only, being 'TATA' with logo.

The sign incorporating 'TATA' at the base and logo-centred above includes:

- Material white polycarbonate face, with 160 mm deep returns painted white
- LED illuminated lighting within for the sign on the eastern elevation only
- Dimensions of signage: the sign and logo in combination have an overall width of 4042 mm and height of 4060 mm
- Location: It is proposed to be located on the parapet of the building on the eastern elevation and the northern elevation
- The fabricated letters and logo are to be fixed to the existing parapet walls with engineers certified fixings.

Illumination will be permitted for the sign on the eastern elevation, subject to a curfew of 8.00 pm to 7.00 am, seven days.

No illumination is permitted for the sign on the northern elevation.

The approved signage under DA 275/14 is to be removed prior to the commencement of any works.

No approval is granted or implied for any additional works not covered by this consent.

(Reason: To ensure the terms of the consent are clear. Only one single corporate entity is to be identified to ensure effective communication and wayfinding. Identification of two separate corporate entities is not permitted as confusion results. Illumination is subject to curfew to protect residential amenity. No illumination is permitted on the northern elevation to protect residential amenity due to light spillage.)

C. Prior to the Issue of a Construction Certificate (and ongoing, where indicated)

Dilapidation Report Damage to Public Infrastructure

C1. A dilapidation survey and report (including photographic record) must be prepared by a suitably qualified consultant which details the pre-developed condition of the existing public infrastructure in the vicinity of the development site. Particular attention must be paid to accurately recording any pre-developed damaged areas so that Council is fully informed when assessing any damage to public infrastructure caused as a result of the development. A copy of the dilapidation survey and report is to be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate.

The developer may be held liable for all damage to public infrastructure in the vicinity of the site, where such damage is not accurately recorded and demonstrated as pre-existing under the requirements of this condition.

The developer shall bear the cost of carrying out works to restore all public infrastructure damaged as a result of the carrying out of the development, and no occupation of the development shall occur until damage caused as a result of the carrying out of the development is rectified.

A copy of the dilapidation survey and report must be lodged with North Sydney Council by the Certifying Authority with submission of the Construction Certificate documentation.

(Reason: To record the condition of public infrastructure prior to the commence-ment of construction)

Waste Management Plan

- C2. A Waste Management Plan is to be submitted for approval by the Certifying Authority prior to the issue of any Construction Certificate. The plan must include, but not be limited to:
 - a) The estimated volume of waste and method of disposal for the construction and operation phases of the development;
 - b) The design of the on-site waste storage and recycling area; and
 - c) Administrative arrangements for waste and recycling management during the construction process.

The approved Waste Management Plan must be complied with at all times in the carrying out of the development.

(Reason: To encourage the minimisation of waste and recycling of building waste)

Bond for Damage and Completion of Infrastructure Works - Stormwater, Kerb and Gutter, Footpaths, Vehicular Crossing and Road Pavement

- C3. Prior to the issue of any Construction Certificate, security deposit or bank guarantee must be provided to Council to the sum of **\$2,000.00** to be held by Council for the payment of cost for any/all of the following:
 - a) making good any damage caused to any property of the Council as a consequence of the doing of anything to which this consent relates,
 - b) completing any public work (such as road work, kerbing and guttering, footway construction, stormwater drainage and environmental controls) required in connection with this consent.
 - c) remedying any defects in any such public work that arise within six months after the work is completed.

The security required by this condition and in the schedule contained later in these conditions must be provided by way of a deposit with the Council; or other such guarantee that is satisfactory to Council (such as a bank guarantee). Any guarantee provided as security must name North Sydney Council as the nominated beneficiary and must not be subject to an expiry date.

The security will be refundable following the expiration of six months from the issue of any final Occupation Certificate or completion of public work required to be completed (whichever is the latest) but only upon inspection and release by Council's Engineers.

Council shall have full authority to make use of the bond for such restoration works as deemed necessary by Council in circumstances including the following:

- where the damage constitutes a hazard in which case Council may make use of the security immediately;
- the applicant has not repaired or commenced repairing damage within 48 hours of the issue by Council in writing of instructions to undertake such repairs or works;

- works in the public road associated with the development are to an unacceptable quality; and
- the Certifying Authority must ensure that security is provided to North Sydney Council prior to issue of any Construction Certificate.
- (Reason: To ensure appropriate security for works on public land and an appropriate quality for new public infrastructure)

Location of Plant

- C4. All plant and equipment (including but not limited to air conditioning equipment) is to be located within the basement of the building and is not to be located on balconies or the roof. Plans and specifications complying with this condition must be submitted to the Certifying Authority for Approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.
 - (Reason: Minimise impact on surrounding properties, improved visual appearance and amenity for locality)

Noise from Plant and Equipment

- C5. The use of all plant and equipment installed on the premises must not:
 - (a) Contribute an LAeq(15min) which will cause the total LAeq(15min) from all plant and equipment operating contemporaneously on the site or in the strata scheme or in the mixed strata schemes to exceed the RBL by more than 5dB when measured at the boundary of any affected receiver. The modifying factor adjustments in Section 4 of the EPA Industrial Noise Policy shall be applied.
 - (b) Cause "offensive noise" as defined in the *Protection of the Environment Operations Act 1997.*

"affected receiver" includes residential premises (including any lot in the strata scheme or another strata scheme), premises for short-term accommodation, schools, hospitals, places of worship, commercial premises and parks and such other affected receiver as may be notified by the Council in writing.

"boundary" includes any window or elevated window of an affected receiver.

Terms in this condition have the same meaning as in the Noise Guide for Local Government and the Industrial Noise Policy published by the NSW Environment Protection Authority.

(Reason: To maintain an appropriate level of amenity for adjoining land uses)

Vibration from Plant and Equipment

C6. The use of all plant and equipment to be installed on the premises must comply with the vibration limits specified in "Assessing Vibration: a technical guideline" issued by the NSW Environment Protection Authority, at the boundary of any affected receiver.

A certificate from an appropriately qualified acoustical consultant eligible for membership of the Association of Australian Acoustic Consultants must be submitted to the Certifying Authority, certifying that all plant and equipment on the site, together with the proposed plant and equipment, operating contemporaneously will comply with the requirements of this condition.

The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

"affected receiver" includes residential premises (including any lot in the strata scheme or another strata scheme), premises for short-term accommodation, schools, hospitals, places of worship and commercial premises and such other affected receiver as may be notified by the Council in writing.

"boundary" includes any window or elevated window of an affected residence.

"contemporaneously" means *existing at or occurring in the same period of time* (Macquarie Dictionary 3rd rev. ed. 2004).

(Reason: To maintain an appropriate level of amenity for adjoining land uses)

Security Deposit/Guarantee Schedule

C7. All fees and security deposits/guarantees in accordance with the schedule below must be provided to Council prior to the issue of any Construction Certificate:

| Security Deposit/Guarantee | Amount (\$) |
|----------------------------|-------------|
| Footpath Damage Bond | 2,000.00 |
| TOTAL BONDS | \$2,000.00 |

The security required by the above schedule must be provided by way of a deposit with the Council; or other such guarantee that is satisfactory to Council (such as a bank guarantee). Any guarantee provided as security must name North Sydney Council as the nominated beneficiary and must not be subject to an expiry date.

(Reason: Compliance with the development consent)

Outdoor Lighting

C8. All outdoor lighting must comply with, where relevant AS/NZ1158.3:1999 Pedestrian Area (Category P) Lighting and AS4282:1997 Control of the Obtrusive Effects of Outdoor lighting. Details demonstrating compliance with these requirements must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the building plans and specifications submitted fully satisfy the requirements of this condition.

(Reason: To maintain the amenity of adjoining land uses)

Signage Design - Control of the Obtrusive Effects of Outdoor Lighting

C9. The signage must be designed in accordance with AS 4282-1997 control of obtrusive effects of outdoor lighting.

Plans and specifications complying with this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To maintain the amenity of adjoining land uses)

Amended Plans to show Signage Design and Scale - Single Corporate Entity

- C10. Amended architectural plans are to be submitted prior to issue of any construction certificate to the Principal Certifier, to demonstrate:
 - One single corporate identity, being 'TATA' with logo to be identified
 - Same size of sign on both the eastern and northern elevations
 - No signage permitted on the western and southern elevations
 - The signage details as outlined in **Condition A4** Terms of Consent

(Reason: To ensure the proposed signage is of appropriate scale in accordance with the terms of consent; signage to effectively communicate one single corporate entity)

D. Prior to the Commencement of any Works (and continuing where indicated)

Public Liability Insurance - Works on Public Land

- D1. Any person or contractor undertaking works on public land must take out Public Risk Insurance with a minimum cover of \$20 million in relation to the occupation of public land and the undertaking of approved works within Council's road reserve or public land, as approved by this consent. The Policy is to note and provide protection/full indemnification for North Sydney Council, as an interested party. A copy of the Policy must be submitted to Council prior to commencement of any works. The Policy must be valid for the entire period that the works are being undertaken.
 - Note: Applications for hoarding permits, vehicular crossings etc will require evidence of insurance upon lodgement of the application.
 - (Reason: To ensure the community is protected from the cost of any claim for damages arising from works on public land)

Commencement of Works' Notice

- D2. Building work, demolition or excavation in accordance with this development consent must not be commenced until the developer has given at least two days' notice to North Sydney Council of the person's intention to commence building work, demolition or excavation in accordance with this development consent.
 - (Reason: To ensure appropriate safeguarding measures are in place prior to the commencement of any building work, demolition or excavation)

Removal of Signs Approved under DA 275/14

- D3. The approved signs on the western elevation and eastern elevation, approved under DA 275/14, are to be removed prior to the commencement of any works. The consent under DA 275/14 is to be surrendered to Council prior to issue of any occupation certificate.
 - (Reason: To comply with the terms of this consent, and to ensure effective communication and wayfinding)

E. During Demolition and Building Work

Parking Restrictions

- E1. Existing public parking provisions in the vicinity of the site must be maintained at all times during works. The placement of any barriers, traffic cones, obstructions or other device in the road shoulder or kerbside lane is prohibited without the prior written consent of Council. Changes to existing public parking facilities/restrictions must be approved by the North Sydney Local Traffic Committee. The Developer will be held responsible for any breaches of this condition and will incur any fines associated with enforcement by Council regulatory officers.
 - (Reason: To ensure that existing kerbside parking provisions are not compromised during works)

Road Reserve Safety

E2. All public footways and roadways fronting and adjacent to the site must be maintained in a safe condition at all times during the course of the development works, with no obstructions caused to the said footways and roadways. Construction materials and plant must not be stored in the road reserve without approval of Council. A safe pedestrian circulation route and a pavement/route free of trip hazards must be maintained at all times on or adjacent to any public access ways fronting the construction site.

Where public infrastructure is damaged, repair works must be carried out in when and as directed by Council officers (at full Developer cost). Where pedestrian circulation is diverted on to the roadway or verge areas, clear directional signage and protective barricades must be installed in accordance with AS1742-3 (1996) "Traffic Control Devices for Work on Roads". If pedestrian circulation is not satisfactorily maintained across the site frontage, and action is not taken promptly to rectify the defects, Council may undertake proceedings to stop work.

(Reason: Public Safety)

Temporary Disposal of Stormwater Runoff

E3. During construction, stormwater runoff must be disposed in a controlled manner that is compatible with the erosion and sediment controls on the site. Immediately upon completion of any impervious areas on the site (including roofs, driveways, paving) and where the final drainage system is incomplete, the necessary temporary drainage systems must be installed to reasonably manage and control runoff as far as the approved point of stormwater discharge. Such ongoing measures must be to the satisfaction of the Certifying Authority.

(Reason: Stormwater control during construction)

Removal of Extra Fabric

E4. Should any portion of the existing building, trees, or curtilage of the site which is indicated on the approved plans to be retained be damaged for whatever reason, all the works in the area of the damaged portion are to cease and written notification of the damage is to be given to Council forthwith. No work is to resume until the written approval of Council to do so is obtained. Failure to comply with the provisions of this condition may result in the Council taking further action including legal proceedings if necessary.

(Reason: To ensure compliance with the terms of this development consent)

Noise and Vibration

E5. The works must be undertaken in accordance with the "Interim Construction Noise Guideline" published by the NSW Environment Protection Authority, to ensure excessive levels of noise and vibration do not occur so as to minimise adverse effects experienced on any adjoining land.

(Reason: To ensure residential amenity is maintained in the immediate vicinity)

No Work on Public Open Space

- E6. No work can be undertaken within adjoining public lands (i.e., Parks, Reserves, Roads etc) without the prior written consent of Council. In this regard the developer is to liaise with Council prior to the commencement of any design works or preparation of a Construction and Traffic Management Plan.
 - (Reason: Protection of existing public infrastructure and land and to ensure public safety and proper management of public land)

Developer's Cost of Work on Council Property

- E7. The developer must bear the cost of all works associated with the development that occurs on Council's property, including the restoration of damaged areas.
 - (Reason: To ensure the proper management of public land and funds)

No Removal of Trees on Public Property

E8. No trees on public property (footpaths, roads, reserves, etc.) unless specifically approved by this consent shall be removed or damaged during construction including for the erection of any fences, hoardings or other temporary works.

(Reason: Protection of existing environmental infrastructure and community assets)

Special Permits

E9. Unless otherwise specifically approved in writing by Council, all works, processes, storage of materials, loading and unloading associated with the development must occur entirely on the property.

The developer, owner or builder may apply for specific permits available from Council's Customer Service Centre for the undermentioned activities on Council's property. In the event that a permit is granted by Council for the carrying out of works, processes, storage of materials, loading and unloading associated with the development on Council's property, the development must be carried out in accordance with the requirements of the permit. A minimum of forty-eight (48) hours' notice is required for any permit:

1) **On-street mobile plant**

E.g., cranes, concrete pumps, cherry-pickers, etc. - restrictions apply to the hours of operation, the area of operation, etc. Separate permits are required for each occasion and each piece of equipment. It is the developer's, owner's and builder's responsibilities to take whatever steps are necessary to ensure that the use of any equipment does not violate adjoining property owner's rights.

(Reason: Proper management of public land)

2) Hoardings

Permits are required to erect Class A and Class B hoardings. If an 'A' Class hoarding is to alienate a section of Council's property, that section will require a permit for the occupation of Council's property.

(Reason: Proper management of public land)

3) Storage of building materials and building waste containers (skips) on Council's property

Permits to utilise Council property for the storage of building materials and building waste containers (skips) are required for each location. Failure to obtain the relevant permits will result in the building materials or building waste containers (skips) being impounded by Council with no additional notice being given. Storage of building materials and waste containers on open space reserves and parks is prohibited.

(Reason: Proper management of public land)

4) Kerbside restrictions, construction zones

Attention is drawn to the existing kerbside restrictions adjacent to the development. Should alteration of existing kerbside restrictions be required, or the provision of a construction zone, the appropriate application must be made, and the fee paid to Council. Alternatives to such restrictions may require referral to Council's Traffic Committee and may take considerable time to be resolved. An earlier application is suggested to avoid delays in construction programs.

(Reason: Proper management of public land)

Construction Hours

E10. Construction activities and works approved under this consent must be carried out only within the hours stipulated in the following table:

| Standard Construction Hours | | | | |
|-----------------------------|------------------------|-------------------|--|--|
| Location Day Hou | | | | |
| | Monday - Friday | 7.00 am - 5.00 pm | | |
| All Other Zones | Saturday | 8.00 am - 1.00 pm | | |
| | Sunday, Public holiday | No work permitted | | |

Construction activities for development approved under this consent must be carried out in accordance with the standard construction hours above and any Construction Noise Management Plan required under this consent.

In the event of breach to the approved hours of construction Council take may take enforcement action under Part 9 of the EP&A Act 1979 and in accordance with Council's adopted Compliance and Enforcement Policy.

(Reason: To ensure that works do not interfere with reasonable amenity expectations of residents and the community)

Health and Safety

E11. All work undertaken must satisfy applicable occupational health and safety and construction safety regulations, including any WorkCover Authority requirements to prepare a health and safety plan. Site fencing must be installed sufficient to exclude the public from the site. Safety signs must be erected that warn the public to keep out of the site and provide a contact telephone number for enquiries.

Further information and details regarding occupational health and safety requirements for construction sites can be obtained from the internet at <u>www.workcover.nsw.gov.au</u>.

(Reason: To ensure the health and safety of the community and workers on the site)

Prohibition on Use of Pavements

E12. Building materials must not be placed on Council's footpaths, roadways, parks or grass verges, (unless a permit is obtained from Council beforehand). A suitable sign to this effect must be erected adjacent to the street alignment.

(Reason: To ensure public safety and amenity on public land)

Plant and Equipment Kept Within Site

E13. All plant and equipment used in the undertaking of the development/ works, including concrete pumps, wagons, lifts, mobile cranes, hoardings etc, must be situated within the boundaries of the site (unless a permit is obtained from Council beforehand) and so placed that all concrete slurry, water, debris and the like must be discharged onto the building site, and is to be contained within the site boundaries.

Details of Council requirements for permits on public land for standing plant, hoardings, storage of materials and construction zones and the like are available on Council's website at <u>www.northsydney.</u> <u>nsw.gov.au</u>.

(Reason: To ensure public safety and amenity on public land)

Waste Disposal

E14. All records demonstrating the lawful disposal of waste must be retained and kept readily accessible for inspection by regulatory authorities such as North Sydney Council and the Environmental Protection Authority.

(Reason: To ensure the lawful disposal of construction and demolition waste)

F. Prescribed Conditions imposed under EP&A Act and Regulations and other relevant Legislation

National Construction Code

F1. All building work must be carried out in accordance with the provisions of the National Construction Code.

(Reason: Prescribed - Statutory)

Appointment of a Principal Certifying Authority (PCA)

- F2. Building work, demolition or excavation in accordance with the development consent must not be commenced until the developer has appointed a Principal Certifying Authority for the building work in accordance with the provisions of the EP&A Act and its Regulations.
 - (Reason: Statutory: To ensure appropriate safeguarding measures are in place prior to the commencement of any building work, demolition or excavation)

Construction Certificate

- F3. Building work, demolition or excavation in accordance with the development consent must not be commenced until a Construction Certificate for the relevant part of the building work has been issued in accordance with the provisions of the EP&A Act and its Regulations.
 - (Reason: Statutory: To ensure appropriate safeguarding measures are in place prior to the commencement of any building work, demolition or excavation)

Occupation Certificate

F4. A person must not commence occupation or use of the whole or any part of a new building (*new building* includes an altered portion of, or an extension to, an existing building) unless an Occupation Certificate has been issued in relation to the building or part. Only the Principal Certifying Authority appointed for the building work can issue an Occupation Certificate.

(Reason: Statutory)

Critical Stage Inspections

F5. Building work must be inspected by the Principal Certifying Authority on the critical stage occasions prescribed by the EP&A Act and its Regulations, and as directed by the appointed Principal Certifying Authority.

(Reason: Statutory)

Commencement of Works

- F6. Building work, demolition or excavation in accordance with this development consent must not be commenced until the developer has given at least two (2) days' notice to North Sydney Council of the person's intention to commence the erection of the building.
 - (Reason: Statutory: To ensure appropriate safeguarding measures are in place prior to the commencement of any building work, demolition or excavation)

Demolition

- F7. 1) Demolition work must be undertaken in accordance with the provisions of AS2601- Demolition of Structures.
 - (Reason: To ensure that work is undertaken in a professional and responsible manner and protect adjoining property and persons from potential damage)

Protection of Public Places

- F8. 1) A hoarding and site fencing must be erected between the work site and adjoining public place.
 - 2) If necessary, an awning is to be erected, sufficient to prevent any substance from, or in connection with, the work falling into the public place.
 - 3) The work site must be kept lit between sunset and sunrise if it is likely to be hazardous to persons in the public place.
 - 4) Any such hoarding, fence or awning is to be removed when the work has been completed.
 - 5) No access across public reserves or parks is permitted.
 - Note: Prior to the erection of any temporary fence or hoarding over property owned or managed by Council, written approval must be obtained. Any application needs to be accompanied by plans indicating the type of hoarding and its layout. Fees are assessed and will form part of any approval given. These fees must be paid prior to the approval being given. Approval for hoardings will generally only be given in association with approved building works, maintenance or to ensure protection of the public. An application form for a Hoarding Permit can be downloaded from Council's website.
 - (Reason: To ensure public safety and the proper management of public land)

Site Sign

- F9. 1) A sign must be erected in a prominent position on the site
 - a) stating that unauthorised entry to the work site is prohibited;
 - b) showing the name of the principal contractor (or person in charge of the work site), and a telephone number at which that person may be contacted at any time for business purposes and outside working hours; and
 - c) showing the name, address and telephone number of the Principal Certifying Authority for the work.
 - 2) Any such sign must be maintained while to building work or demolition work is being carried out but must be removed when the work has been completed.
 - (Reason: Prescribed Statutory)

G. Prior to the Issue of an Occupation Certificate

Damage to Adjoining Properties

G1. All precautions must be taken to prevent any damage likely to be sustained to adjoining properties. Adjoining owner property rights and the need for owner's permission must be observed at all times, including the entering onto land for the purpose of undertaking works.

(Reason: To ensure adjoining owner's property rights are protected)

Utility Services

- G2. All utility services shall be adjusted to the correct levels and/or location/s required by this consent, prior to issue of an occupation certificate. This shall be at no cost to Council.
 - (Reason: To ensure compliance with the terms of this consent)

Compliance with Certain Conditions

- G3. Prior to the issue of any Occupation Certificate **Conditions C10, C87, I4, I5 and I6** must be certified as having been implemented on site and complied with.
 - (Reason: To ensure the development is completed in accordance with the requirements of this consent)

I. Ongoing/Operational Conditions

Hours of Illumination

- 11. All illuminated signs approved by this consent on the eastern elevation must cease illumination between the hours of 8.00 pm and 7.00 am.
 - (Reason: To ensure appropriate forms of signage that are consistent with Council's controls and those that are desired for the locality, and do not interfere with amenity of nearby properties)

Signage Illumination Intensity

- 12. The sign(s) must be installed and used at all times in accordance with AS 4282-1997 control of obtrusive effects of outdoor lighting and must be restricted in accordance with the following:
 - (a) At no time is the intensity, period of intermittency and hours of illumination of the sign to cause objectionable glare or injury to the amenity of the neighbourhood.
 - (b) The level of illumination and/or lighting intensity used to illuminate the signage must not cause excessive light spill or nuisance to any nearby residential premises.
 - (c) The signage illumination must not flash.
 - (Reason: To ensure appropriate forms of signage that are consistent with Council's controls and those that are desired for the locality, and do not interfere with amenity of nearby properties)

Roof Top Lighting

- 13. Lighting on rooftop or podium level areas must not be illuminated between 11:00 pm and 7:00 am. The design and placement of the lighting must:
 - (a) be directed away from any residential dwelling;
 - (b) not create a nuisance or negatively affect the amenity of the surrounding neighbourhood; and
 - (c) comply with AS4282-1997 control of obtrusive effects of outdoor lighting.
 - (Reason: To ensure residential premises are not affected by inappropriate or excessive illumination)

Page **21** of **21**

Automated Timing Device

- 14. An automated timing device must be used at all times to control the hours of illumination of the building identification sign on the eastern elevation in accordance with **Condition I1** Hours of Illumination.
 - (Reason: To ensure signage illumination does not interfere with the amenity of surrounding residential and commercial uses)

No Flashing

15. The signage illumination, when operating, shall be a constant light and shall not flash or have any moving elements or animations.

(Reason: Visual impact and amenity)

Maintenance of Signage Structure

- 16. The signage must be maintained at all times to a structurally sound condition.
 - (Reason: To ensure that structures are maintained to an acceptable standard and do not become a potential public hazard)