

# 200 Miller Street, North Sydney, NSW 2060 | ABN 32 353 260 317 All correspondence PO Box 12, North Sydney, NSW 2059 P (02) 9936 8100 | E council@northsydney.nsw.gov.au W www.northsydney.nsw.gov.au

WINIM Development Pty Ltd Se 214, 40 Yeo Street NEUTRAL BAY NSW 2089

NORTH SYDNEY COUNCIL

> D291/22 MS3(CIS)

# ENVIRONMENTAL PLANNING AND ASSESSMENT ACT, 1979 AS AMENDED NOTICE OF DETERMINATION – Deferred Commencement

Issued under Section 4.18 of the Environmental Planning and Assessment Act 1979 ("the Act"). Clause 87 of the Environmental Planning and Assessment Regulation 2021 ("the Regulation")

Development Application Number:	291/2022
Land to which this applies:	13-15 Allister Street, Cremorne Lot No.: 0, SP: 19383
Applicant:	WINIM Development Pty Ltd
Proposal:	Demolition of the existing multi-dwelling housing (No. 13 Allister Street) and partial demolition of the existing residential flat building (No. 15 Allister Street), and alterations and additions to the existing residential flat building to construct a residential flat building on both lots, containing 13 apartments above two levels of basement parking, and associated works and landscaping.
Determination of Development Application:	The development application was considered by the <b>North</b> <b>Sydney Local Planning Panel (NSLPP)</b> on 5 July 2023. Subject to the provisions of Section 4.17 of the Environmental Planning and Assessment Act 1979, deferred commencement has been granted, subject to conditions in the notice of determination.
Date of Determination:	5 July 2023
Reason for Deferred Commencement:	The Panel is satisfied that the development is appropriate in its context for the subject site, provided that the heritage significant building can be retained. This will require details of the proposed underpinning and structural excavation to be demonstrated through a Deferred Commencement.

	The Panel is satisfied the heritage assessment included consideration under Clause 5.10 of the North Sydney LEP 2013 and treated the building as if it was a local heritage item and deferral of the matter was not warranted. The outcome for the heritage significant building with the development of the adjoining property is considered to provide a positive built form response for the locality. The use of a low overrun lift allows a better integration of this
	element into the overall built form.
Deferred Commencement Time Frame:	24 Months
Date of Lapsing:	11 July 2025
How community views were taken into account:	The submissions received by Council were addressed in the NSLPP report (see Council's website: <u>https://www.northsydney.nsw.gov.au/downloads/file/2574/lpp02-13-15-allister-street-cremorne-da-291-22-report</u> )
Review of determination and right of appeal:	Consideration should be given to providing the evidence to Council to allow sufficient time to consider the same and form a view as to whether the deferred commencement conditions are satisfied or not. Within 6 months after the date of notification of the decision, a review of this determination can be requested under Division 8.2 of the Act or an appeal to the Land and Environment Court made pursuant to the provisions of Section 8.7 of the Act. A review of determination should be lodged as soon as possible, and preferably no later two months after the date of notification of the decision to enable the review to be completed within the six-month period.

Endorsed for and on behalf of North Sydney Council

**11 July 2023** DATE

Altogo

Signature on behalf of consent authority MICHAEL STEPHENS A/TEAM LEADER (ASSESSMENTS)

#### (i) Conditions

Consent is granted subject to the following conditions imposed pursuant to Section 4.17 of the Environmental Planning & Assessment Act 1979 ("the Act") and the provisions of the Environmental Planning & Assessment Regulation 2000 ("the *Regulation*") such conditions being reasonable and relevant to the development as assessed pursuant to Section 4.17 of the Act.

#### (ii) Definitions

Unless specified otherwise, words have the same meaning as defined by the *Act*, the *Regulation* and the *Interpretation Act* 1987 as in force at the date of consent.

Applicant means the applicant for this consent.

*Approved Plans* means the plans endorsed by Council referenced by this consent as amended by conditions of this consent.

**AS** or **AS/NZS** means Australian Standard<sup>®</sup> or Australian/New Zealand Standard<sup>®</sup>, respectively, published by Standards Australia International Limited.

**NCC** means the National Construction Code as published by the Australian Building Codes Board as in force at the date of issue of any *Construction Certificate*.

*Council* means North Sydney Council.

*Court* means the Land and Environment Court.

Local Native Plants means species of native plant endemic to North Sydney LGA.

Stormwater Drainage System means all works, facilities and documentation relating to:

- The collection of stormwater,
- The retention of stormwater,
- The reuse of stormwater,
- The detention of stormwater,
- The controlled release of stormwater; and
- Connections to easements and public stormwater systems.

*Owner* means the owner of the *site* and successors in title to the *site*.

*Owner Builder* has the same meaning as in the *Home Building Act* 1989.

**Principal Certifier** for building or subdivision work means the certifier appointed as the principal certifier for the building work under section 6.6 (1) or for the subdivision work under section 6.12 (1).

*Principal Contractor* for building work means the person responsible for the overall coordination and control of the carrying out of the building work.

Note: If any residential building work is involved, the principal contractor must be the holder of a contractor licence under the *Home Building Act 1989*.

Professional Engineer has the same meaning as in the NCC.

Public Place has the same meaning as in the Local Government Act 1993.

*Road* has the same meaning as in the *Roads Act* 1993.

SEE means the final version of the Statement of Environmental Effects lodged by the Applicant.

*Site* means the land being developed subject to this consent.

**NSLEP 2013** means North Sydney Local Environmental Plan 2013

**NSDCP 2013** means North Sydney Development Control Plan 2013

*Work* for the purposes of this consent means:

- the use of land in connection with development,
- the subdivision of land,
- the erection of a building,
- the carrying out of any work,
- the use of any site crane, machine, article, material, or thing,
- the storage of any waste, materials, site crane, machine, article, material, or thing,
- the demolition of a building,
- the piling, piercing, cutting, boring, drilling, rock breaking, rock sawing or excavation of land,
- the delivery to or removal from the *site* of any machine, article, material, or thing, or
- the occupation of the *site* by any person unless authorised by an *occupation certificate*.
- Note: **Interpretation of Conditions** Where there is any need to obtain an interpretation of the intent of any condition this must be done in writing to Council and confirmed in writing by Council.

#### **INDEX OF CONDITIONS**

		Page No.
AA.	Deferred Commencement Conditions	
AA1.	Structural/Geotechnical Reports	9
А.	Conditions that Identify Approved Plans	
A1.	Development in Accordance with Plans/documentation	11
A2.	Plans on Site	12
A3.	No Demolition of Extra Fabric	12
A4.	External Finishes & Materials	12
В.	Matters to be Completed before the lodgement of an Application for a Construction Certifi	cate
B1.	Construction and Traffic Management Plan North Sydney Council Traffic Division Approval	12
С.	Prior to the Issue of a Construction Certificate (and ongoing, where indicated)	
C1.	Heritage Requirements	14
C2.	Charging Facility for Electric Vehicles	14
C3.	Dilapidation Report Damage to Public Infrastructure	15
C4.	Dilapidation Report Private Property (Excavation)	15
C5.	Dilapidation Survey Private Property (Neighbouring Buildings)	16
C6.	Structural Adequacy of Adjoining Properties – Excavation Works	17
C7.	Structural Adequacy of Existing Building	17
C8.	Sediment Control	17
C9.	Waste Management Plan	18
C10.	Heritage Architect to be Commissioned	18
C11.	Skylight(s)	18
C12.	External Colours and Finishes	19
C13.	Reflectivity Index of Glazing	19
C14.	Roofing Materials - Reflectivity	19
C15.	No External Service Ducts	20
C16.	Work Zone	20
C17.	Maintain Property Boundary Alignment Levels	20
C18.	Bicycle Storage and Parking	21
C19.	Accessible parking spaces to be provided	21
C20.	Allocation of Spaces	21
C21.	Basement Car park to comply with relevant standards	22
C22.	Required Infrastructure Works – Roads Act 1993	22
C23.	Stormwater Management and Disposal Design Plan – Construction Issue Detail	24
C24	On-Site Stormwater Detention	24
C24. C25.		20
CZ3.	Bond for Damage and Completion of Infrastructure Works – Stormwater, Kerb and Gutter, Footpaths, Vehicular Crossing and Road Pavement	26
C26.	Upgrade of existing building – Fire Spread and Safe Egress	20
C20. C27.	Project Arborist to be Commissioned	27
C27.	Tree Protection	28
		20

C29.	Tree Bond for Public Trees	29
C30.	Tree Protection Measures to be shown on Construction Drawings	29
C31.	Protection of Trees	30
C32.	Approval for removal of Trees	30
C33.	Pruning of Trees	30
C34.	Garbage and Recycling Facilities	31
C35.	Asbestos Material Survey	32
C36.	Location of Plant	32
C37.	Noise from Plant and Equipment	32
C38.	Vibration from Plant and Equipment	33
C39.	Air Conditioners in Residential Premises	33
C40.	Acoustic Privacy (Residential Apartments)	34
C41.	Noise and Vibration Compliance Certification Prior to Issue of	
	Construction Certificate	35
C42.	Mechanical Exhaust Ventilation	35
C43.	Construction Noise Management Plan	35
C44.	Provision of Accessible Paths of Travel	36
C45.	Underground Electricity and Other Services	37
C46.	Screen Planting	37
C47.	Adaptable Housing	37
C48.	Section 7.11 Contributions	38
C49.	Security Deposit/ Guarantee Schedule	38
C50.	BASIX Certificate	39
C51.	Outdoor Lighting	39
C52.	Amendments to the Landscape Plan	39
C53.	Root Mapping	40
D.	Prior to the Commencement of any Works (and continuing where indicated)	
D1.	Photographic Survey (Heritage Items)	41
D2.	Protection of Trees	41
D3.	Tree Protection Measures	41
D4.	Project Arborist to be Engaged	41
D5.	Protection of Public Trees	42
D6.	Temporary Fences and Tree Protection	43
D7.	Public Liability Insurance – Works on Public Land	43
D8.	Notification of New Addresses	43
D9.	Sydney Water Approvals	43
D10.	Asbestos Material Survey	44
D10. D11.	Commencement of Works Notice	44
DII.		
Ε.	During Demolition and Building Work	
E1.	Re-use of Sandstone	45
E2.	Parking Restrictions	45
E3.	Road Reserve Safety	45
E4.	Service Adjustments	46
E5.	Temporary Disposal of Stormwater Runoff	46
E6.	Structural and Geotechnical Stability during Works	46
E7.	Council Inspection of Public Infrastructure Works	46

E8.	Progress Survey	47
E9.	Removal of Extra Fabric	47
E10.	Dust Emission and Air Quality	48
E11.	Noise and Vibration	48
E12.	Compliance with Construction Noise Management Plan	48
E13.	No Work on Public Open Space	48
E14.	Applicant's Cost of Work on Council Property	48
E15.	No Removal of Trees on Public Property	49
E16.	Protection of Trees	49
E17.	Benchmarks	49
E18.	Special Permits	49
E19.	Construction Hours	50
E20.	Installation and Maintenance of Sediment Control	51
E21.	Sediment and Erosion Control Signage	51
E22.	Site Amenities and Facilities	51
E23.	Health and Safety	52
E24.	Community Information	52
E25.	Prohibition on Use of Pavements	52
E26.	Plant & Equipment Kept Within Site	52
E27.	Waste Disposal	53
E28.	Asbestos Removal	53

# F. Prescribed Conditions imposed under EP&A Act and Regulations and other relevant Legislation

F1.	National Construction Code	53
F2.	Home Building Act	53
F3.	Appointment of a Principal Certifier (previously known as a PCA)	54
F4.	Construction Certificate	54
F5.	Occupation Certificate	54
F6.	Mandatory Critical Stage Inspections	54
F7.	Excavation/Demolition	55
F8.	Protection of Public Places	55
F9.	Site Sign	55

# G. Prior to the Issue of an Occupation Certificate

G1.	Infrastructure Repair and Completion of Works	56
G2.	Line Marking	56
G3.	Noise Certification	56
G4.	Certification- Civil Works	57
G5.	Works as Executed Drawings and Video	57
G6.	Certification for Mechanical Exhaust Ventilation	57
G7.	Utility Services	57
G8.	Basement Pump-Out Maintenance	58
G9.	Notification of New Address Developments	58
G10.	Asbestos Clearance Certificate	58
G11.	Certification of Tree Condition	59
G12.	Signal System	59
G13.	Disposal Information	59
G14.	Sydney Water	59

G15.	BASIX Completion Certificate	60
G16.	House Numbering (Dwellings)	60
G17.	Landscaping	60
G18.	Damage to Adjoining Properties	60
G19.	Verification Statement (External Finishes and Materials)	61
G20.	Required Tree Planting	61
G21.	Unpaved Verge	62
G22.	Intercom	62
G23.	Allocation of Spaces	62
G24.	Compliance with Certain conditions	63
G25.	Covenant and Restriction (Use of Communal Areas)	63

# I. On-Going / Operational Conditions

11.	Maintenance	of Approved	Landscaping
-----	-------------	-------------	-------------

64

# AA. Deferred Commencement Conditions

This consent shall not operate until the following deferred commencement condition has been satisfied.

The applicant must satisfy Council as to the matters specified in the deferred commencement condition within 24 Months of the date of the grant of this consent.

If the applicant fails to satisfy Council as to the matters specified in the deferred commencement condition within 24 Months of the date of the grant of this consent. It will lapse in accordance with Section 4.53(6) of the Environmental Planning and Assessment Act 1979.

#### Structural/Geotechnical Reports

AA1 Prior to granting of an operative consent a Geotechnical/Civil Engineering report and Structural Engineering report must be prepared which addresses at a minimum (but is not limited to) the following:

#### Structural

a) A detailed structural design engineers report, including documentation of an inspection and detailed survey of the existing site/building conditions, confirming the proposed means of underpinning and support for the existing building at No. 15 Allister Street to ensure its retention and protection from potential damage.

# Geotechnical

- a) The type and extent of substrata formations by the provision of a minimum of four (4) representative bore hole logs which are to provide a full description of all material from ground surface to 1.0m below the finished basement floor level and include the location and description of any anomalies encountered in the profile. The surface and depth of the bore hole logs must be related to Australian Height Datum;
- b) The appropriate means of excavation/shoring in light of point (a) above and proximity to adjacent property and structures. Potential vibration caused by method of excavation and potential settlements affecting nearby footings/foundations must be discussed and mechanisms to ameliorate any such impacts recommended;
- c) The proposed method to temporarily and permanently support the excavation for the basement adjacent to adjoining property, structures and road reserve if nearby (full support must be provided within the subject site);
- d) The existing groundwater levels in relation to the basement structure, where influenced;

- e) The drawdown effects on adjacent properties (including road reserve), if any, the basement excavation will have on groundwater together with the appropriate construction methods to be utilized in controlling groundwater. Where it is considered there is the potential for the development to create a "dam" for natural groundwater flows, a groundwater drainage system must be designed to transfer groundwater through or under the proposed development without a change in the range of the natural groundwater level fluctuations. Where an impediment to the natural flow path is constructed, artificial drains such as perimeter drains and through drainage may be utilized; and
- f) Recommendations to allow the satisfactory implementation of the works. An implementation program is to be prepared along with a suitable monitoring program including control levels for vibration, shoring support, ground level and groundwater level movements during construction. The implementation program is to nominate suitable hold points at the various stages of the works for verification of the design intent before sign-off and before proceeding with subsequent stages.

The geotechnical report must be prepared by an appropriately qualified consulting geotechnical/ hydro geological engineer or suitable qualified expert with previous experience in such investigations and reporting.

It is the responsibility of the consulting geotechnical/ hydrological specialist to undertake the appropriate investigations, reporting and specialist recommendations to ensure a reasonable level of protection to adjacent property and structures both during and after construction. The report must contain site-specific geotechnical recommendations and shall specify the necessary hold/inspection points by relevant professionals as appropriate.

The design principles for the geotechnical report are as follows:

- a) no ground settlement or movement is to be induced which is sufficient enough to cause an adverse impact to adjoining property and/or infrastructure;
- b) no changes to the ground water level are to occur as a result of the development that are sufficient enough to cause an adverse impact to the surrounding property and infrastructure;
- c) no changes to the ground water level are to occur during the construction of the development that are sufficient enough to cause an adverse impact to the surrounding property and infrastructure;
- d) vibration is to be minimised or eliminated to ensure no adverse impact on the surrounding property and infrastructure occurs, as a result of the construction of the development;
- e) appropriate support and retention systems are to be recommended and suitable designs prepared to allow the proposed development to comply with these Design Principles; and
- f) an adverse impact can be assumed to be crack damage as identified within the relevant Australian Standard for determining such damage.

The reports, satisfying the requirements of this condition, must be submitted to the Council for approval prior to the issue of an operative consent.

The professional recommendations, implementation program, monitoring program, mitigation measures and the like contained in the report must be implemented in full during the relevant stages of excavation and construction.

(Reason: To ensure the structural integrity of the subject site and adjoining sites during the excavation process)

This consent shall not operate until such time as the written approval of Council's Manager of Development Services stating that the requirements of this condition has been satisfied has been provided.

Subject to the above deferred commencement condition being satisfied within 24 months of the date of this determination, the consent shall operate in accordance with the attached conditions including the following site specific and standard conditions:

#### A. Conditions that Identify Approved Plans

#### **Development in Accordance with Plans/Documentation**

A1. The development must be carried out in accordance with the following drawings and documentation and endorsed with Council's approval stamp, except where amended by the following conditions of this consent.

Plan Nos.	Issue	Description	Prepared by	Dated
DA01.03	P5	Site Plan		21 April 2023
DA01.04	P6	Existing (Demolition) Ground Floor Plan		30 January 2023
DA01.05	P7	Existing (Demolition) Level 1 Floor Plan		21 April 2023
DA01.06	P7	Existing (Demolition) Level 2 Floor Plan		21 April 2023
DA01.07	P7	Existing (Demolition) Level 3 Floor Plan		30 January 2023
DA01.11	P13	Basement Level 02 Plan		30 January 2023
DA01.12	P14	Basement Level 01 Plan		21 April 2023
DA01.13	P15	Ground Floor Plan		21 April 2023
DA01.14	P13	Level 1 Floor Plan	- Rothelowman	30 January 2023
DA01.15	P13	Level 2 Floor Plan	Rothelowman	30 January 2023
DA01.16	P16	Level 3 Floor Plan	]	21 April 2023
DA01.17	P12	Roof Plan		21 April 2023
DA02.01	P8	Elevations		21 April 2023
DA02.02	P8	Elevations		21 April 2023
DA02.03	P4	Elevations		21 April 2023
DA03.01	P7	Sections		21 April 2023
DA03.02	P8	Sections		21 April 2023
DA03.03	P2	Sections	]	30 January 2023
DA 1/2	F	Landscape Site Plan	Andrew Davies	24 January 2023
DA 2/2	F	Landscape Plant Schedule and Notes	]	24 January 2023

(Reason: To ensure that the form of the development undertaken is in accordance with the determination of Council, Public Information)

#### Plans on Site

A2. A copy of all stamped approved plans, specifications and documents (including the plans, specifications and documents submitted and approved with the Construction Certificate) must be kept on site at all times so as to be readily available for perusal by any officer of Council or the Principal Certifying Authority.

All documents kept on site in accordance with this condition must be provided to any officer of the Council or the certifying authority upon their request.

(Reason: To ensure that the form of the development undertaken is in accordance with the determination of Council, Public Information and to ensure ongoing compliance)

#### No Demolition of Extra Fabric

- A3. Alterations to, and demolition of the existing building shall be limited to that documented on the approved plans.
  - (Reason: To ensure compliance with the approved development)

#### **External Finishes and Materials**

- A4. External finishes and materials must be in accordance with the submitted Materials and Finishes Schedules on Drawings DA02.01, DA02.02 and DA02.03 as identified in Condition A1 and received by Council unless otherwise modified by Council in writing.
  - (Reason: To ensure that the form of the development undertaken is in accordance with the determination of Council, Public Information)

#### B. Matters to be Completed before the lodgement of an Application for a Construction Certificate

# Construction and Traffic Management Plan North Sydney Council Traffic Division Approval

- B1. A Construction Management Program prepared by a suitably qualified and experienced traffic consultant must be submitted for consideration by the North Sydney Traffic Committee and approved in writing by North Sydney Council's Traffic Division PRIOR TO THE ISSUE OF ANY Construction Certificate. Any use of Council property will require appropriate approvals prior to any work commencing. At a minimum, the Construction Management Program must specifically address the following matters:
  - a) A plan view (min 1:100 scale) of the entire site and frontage roadways indicating:
    - i. Dedicated temporary construction site driveway entrances and exits, controlled by a certified traffic controller, to safely manage pedestrians and construction related vehicles in the frontage roadways and footways;
    - ii. The proposed signage for pedestrian management to comply with the relevant Australian Standards, including pram ramps;
    - iii. Turning areas within the site for construction and spoil removal vehicles, allowing a forward egress for all construction vehicles on the site;

- iv. The locations of any proposed Work Zones in the frontage roadways (to be approved by Council's Traffic Committee);
- v. Locations of hoardings proposed;
- vi. Location of any proposed crane standing areas;
- vii. A dedicated unloading and loading point within the site for all construction vehicles, plant and deliveries;
- viii. Material, plant and spoil bin storage areas within the site, where all materials are to be dropped off and collected; and
- ix. The provision of an on-site parking area for employees, tradesperson and construction vehicles as far as possible.
- b) A detailed heavy vehicle access route map through the Council area to Arterial Roads. Provision is to be made to ensure through traffic is maintained at all times.
- c) The proposed phases of works on the site, and the expected duration of each phase.
- d) How access to neighbouring properties will be maintained at all times and the proposed manner in which adjoining property owners will be kept advised of the timeframes for completion of each phase of process.
- e) The road is not to be used as a waiting area for trucks delivering to or awaiting pick up of materials.
- f) The proposed method of support to any excavation adjacent to adjoining properties, or the road reserve. The proposed method of support is to be designed and certified by an appropriately qualified and practising structural engineer and must not involve any permanent or temporary encroachment onto Council's property.
- g) Proposed protection for Council and adjoining properties. Details are to include site fencing and the provision of "B" class hoardings over footpaths and laneways.
- h) A Waste Management Plan. The Waste Management Plan must include, but not be limited to, the estimated volume of waste and method of disposal for the construction and operation phases of the development, design of on-site waste storage and recycling area and administrative arrangements for waste and recycling management during the construction process.

All traffic control work and excavation, demolition and construction activities must be undertaken in accordance with the approved Construction Management Program and any conditions attached to the approved Program. A certificate of compliance with this condition must be obtained from Council's development engineers. The certificate and the approved Construction Management Program must be submitted as part of the documentation lodged with the application for approval of a construction certificate. A copy of the approved Construction Management Program and any conditions imposed on that Program, must be kept on the site at all times and made available to any officer of Council upon request. Notes:

- 1) North Sydney Council's adopted fee for certification of compliance with this condition shall be payable on lodgement, or in any event, prior to the issue of the relevant approval.
- 2) Any use of Council property will require appropriate approvals and demonstration of liability insurances prior to such work commencing.
- Failure to provide complete and detailed information may result in delays. It is recommended that your Construction Management Plan be lodged with Council as early as possible, as a minimum six (6) weeks' assessment period is required, including referral to the Traffic Committee.
- 4) Dependent on the circumstances of the site, Council may request additional information to that detailed above.
- (Reason: To ensure appropriate measures have been considered for site access, storage and the operation of the site during all phases of the demolition process in a manner that respects adjoining owner's property rights and residential amenity in the locality, without unreasonable inconvenience to the community)

# C. Prior to the Issue of a Construction Certificate (and ongoing, where indicated)

#### **Heritage Requirements**

- C1. The following heritage requirements are to be met for the existing building to be retained located on No. 15 Allister Street:
  - a) Face brickwork and decorative brickwork on the exterior and the interior of the original dwelling is not to be painted.
  - b) Unpainted original interior Interwar joinery is not to be painted.
  - c) Original Interwar glazed doors to the balconies are to be retained.
  - d) Original glazed apartment front doors to be retained. Should changes be required for fire upgrades, they are to be modified on the interior side with fire rated material.
  - e) Interior doors that are to be removed as part of the demolition works are to be salvaged for re-use on site, sold, or distributed to the community to retain the heritage asset.
  - f) New windows and doors to be timber-framed.
  - g) Original tiles in the common area lobby are to be retained and conserved.
  - h) Original wrought balustrade in the common area staircase is to be retained.

The Certifying Authority must also ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To ensure that the building is conserved)

# **Charging Facility for Electric Vehicles**

C2. Appropriate provisions/infrastructure must be incorporated in the design of the basement car park to allow the installation of charging facilities for electric vehicles at each designated parking spot.

Plans and specifications complying with this condition must be submitted to the Certifying Authority for approval prior to the issue of a Construction Certificate. The Certifying Authority must ensure that the building plans and specification submitted fully satisfy the requirements of this condition.

(Reason: To promote sustainability and energy efficiency)

#### **Dilapidation Report Damage to Public Infrastructure**

C3. A dilapidation survey and report (including photographic record) must be prepared by a suitably qualified consultant which details the pre-developed condition of the existing public infrastructure in the vicinity of the development site. Particular attention must be paid to accurately recording any pre-developed damaged areas so that Council is fully informed when assessing any damage to public infrastructure caused as a result of the development. A copy of the dilapidation survey and report is to be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate.

The developer may be held liable for all damage to public infrastructure in the vicinity of the site, where such damage is not accurately recorded and demonstrated as pre-existing under the requirements of this condition.

The developer shall bear the cost of carrying out works to restore all public infrastructure damaged as a result of the carrying out of the development, and no occupation of the development shall occur until damage caused as a result of the carrying out of the development is rectified.

A copy of the dilapidation survey and report must be lodged with North Sydney Council by the Certifying Authority with submission of the Construction Certificate documentation.

(Reason: To record the condition of public infrastructure prior to the commencement of construction)

#### **Dilapidation Report Private Property (Excavation)**

C4. A full dilapidation survey and report on the visible and structural condition of all neighbouring structures within the 'zone of influence' of the required excavations must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The zone of influence is to be defined as the horizontal distance from the edge of the excavation face to twice the excavation depth.

The dilapidation report and survey are to be prepared by a consulting structural/geotechnical engineer agreed to by both the applicant and the owner of any affected adjoining property.

All costs incurred in achieving compliance with this condition shall be borne by the person entitled to act on this Consent.

In the event that access for undertaking the dilapidation survey is denied by an adjoining owner, the applicant MUST DEMONSTRATE, in writing, to the satisfaction of Council that all reasonable steps have been taken to obtain access and advise the affected property owner of the reason for the survey and that these steps have failed. Written concurrence must be obtained from Council in such circumstances.

- Note: This documentation is for record keeping purposes only and may be used by the developer or affected property owner to assist in any action required to resolve any dispute over damage to adjoining properties arising from the works. It is in the applicant's and adjoining owner's interest for it to be as full and detailed as possible.
- (Reason: To record the condition of property/ies., prior to the commencement of construction)

#### **Dilapidation Survey Private Property (Neighbouring Buildings)**

C5. A photographic survey and dilapidation report of adjoining properties Nos. 1-11 Allister Street, 17 Allister Street, and 7, 11 and 13 Cranbrook Avenue detailing the physical condition of those properties, both internally and externally, including, but not limited to, such items as walls, ceilings, roof, structural members and other similar items, SHALL BE submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The survey and report are to be prepared by an appropriately qualified person agreed to by both the applicant and the owner of the adjoining property. A copy of the report is to be provided to Council, if Council is not the Certifying Authority, prior to the issue of any Construction Certificate.

All costs incurred in achieving compliance with this condition shall be borne by the person entitled to act on this Consent.

In the event that access for undertaking the photographic survey and dilapidation report is denied by an adjoining owner, the applicant MUST DEMONSTRATE, in writing, to the satisfaction of Council that all reasonable steps have been taken to obtain access and advise the affected property owner of the reason for the survey and that these steps have failed. Written concurrence must be obtained from Council in such circumstances.

- Note: This documentation is for record keeping purposes only and may be used by an applicant or affected property owner to assist in any action required to resolve any dispute over damage to adjoining properties arising from the works. It is in the applicant's and adjoining owner's interest for it to be as full and detailed as possible.
- (Reason: Proper management of records)

# Structural Adequacy of Adjoining Properties - Excavation Works

- C6. A report prepared by an appropriately qualified and practising structural engineer detailing the structural adequacy of adjoining property Nos. 1-11 Allister Street, 17 Allister Street, 7, 11 and 13 Cranbrook Avenue, which certifies their ability to withstand the proposed excavation and outlines any measures required to be implemented to ensure that no damage will occur to adjoining properties during the course of the works, must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The measures outlined in the certified report must be complied with at all times.
  - (Reason: To ensure the protection and structural integrity of adjoining properties in close proximity during excavation works)

# **Structural Adequacy of Existing Building**

C7. A report prepared by an appropriately qualified and practising structural engineer, certifying the structural adequacy of the building and its ability to withstand the proposed additional, or altered structural loads during all stages of construction shall be submitted to the Certifying Authority for approval prior to issue of any Construction Certificate. The certified report must also include all details of the methodology to be employed in construction phases to achieve the above requirements. The methodology in the certified report must be complied with at all times.

(Reason: To ensure the structural integrity of the building is maintained)

# Sediment Control

C8. Where construction or excavation activity requires the disturbance of the soil surface or existing vegetation, erosion and sediment control techniques, as a minimum, are to be in accordance with the publication *Managing Urban Stormwater: Soils and Construction* (4th edition, Landcom, 2004) commonly referred to as the "Blue Book" or a suitable and effective alternative method.

A Sediment Control Plan must be prepared and submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate and prior to any works commencing. The Sediment Control Plan must be consistent with the Blue Book and disclose:

- a) All details of drainage to protect and drain the site during the construction processes;
- b) All sediment control devices, barriers and the like;
- c) Sedimentation tanks, ponds or the like;
- d) Covering materials and methods; and
- e) A schedule and programme of the sequence of the sediment and erosion control works or devices to be installed and maintained.
- f) Methods for the temporary and controlled disposal of stormwater during construction.

All works must be undertaken in accordance with the approved Sediment Control plan.

The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To protect the environment from the effects of sedimentation and erosion from development sites)

#### Waste Management Plan

- C9. A Waste Management Plan is to be submitted for approval by the Certifying Authority prior to the issue of any Construction Certificate. The plan must include, but not be limited to:
  - a) The estimated volume of waste and method of disposal for the construction and operation phases of the development;
  - b) The design of the on-site waste storage and recycling area; and
  - c) Administrative arrangements for waste and recycling management during the construction process.

The approved Waste Management Plan must be complied with at all times in the carrying out of the development.

(Reason: To encourage the minimisation of waste and recycling of building waste)

#### Heritage Architect to be Commissioned

C10. An appropriately qualified and experienced heritage architect must be commissioned to assist the design development, contract documentation and overseeing of construction works on the site for their duration by undertaking regular inspections of the works in progress and providing advice in relation to heritage matters.

Written details of the engagement of the experienced heritage architect must be submitted to the Certifying Authority prior to the issue of any Construction Certificate.

- Note: If advice provided by the heritage architect is to the effect that works requiring development consent be carried out, such works would require an application under s4.55 of *the Environmental Planning and Assessment Act 1979* or further development application. This condition, and any advice given by the heritage architect, should not be construed as authorising the carrying of development with/ otherwise than in accordance with the development consent.
- (Reason: To ensure that all matters relating to significant fabric and spaces are resolved and recorded using best practice for heritage conservation)

#### Skylight(s)

C11. Skylight flashing(s) and frame(s) to be coloured to match the roof material. Skylight(s) to sit no higher than 300 mm above roof plane when in a closed position. Plans and specifications which comply with this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate.

The Certifying Authority must ensure that the building plans and specifications submitted fully satisfy the requirements of this condition.

(Reason: To minimise the visual impact of the skylight(s) on the roof plane)

#### **External Finishes and Materials**

- C12. The external colours and finishes must be in accordance with the approved schedule of finishes and materials. The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.
  - (Reason: To ensure quality built form of development)

# **Reflectivity Index of Glazing**

- C13. The reflectivity index (expressed as a per centum of the reflected light falling upon any surface) of external glazing for windows, walls or roof finishes of the proposed development is to be no greater than 20%. Plans and specifications which comply with this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.
  - Note: The reflectivity index of glazing elements can be obtained from glazing manufacturers. Glass with mirrored or reflective foil finishes is unlikely to achieve compliance with this requirement.
  - (Reason: To ensure that excessive glare or reflectivity nuisance from glazing does not occur as a result of the development)

# **Roofing Materials - Reflectivity**

- C14. Roofing materials must be factory pre-finished with low glare and reflectivity properties to be compatible with the colours of neighbouring buildings. The selected roofing material must not cause a glare nuisance or excessive reflectivity to adjoining or nearby properties. Plans and specifications which comply with this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.
  - (Reason: To ensure that excessive glare or reflectivity nuisance from roofing materials does not occur as a result of the development)

## No External Service Ducts

- C15. Service ducts must be provided within the building to keep external walls free of plumbing, drainage or any other utility installations. Plans and specifications which comply with this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.
  - (Reason: To ensure quality built form of the development)

#### Work Zone

C16. If a Work Zone is proposed, an application must be made to the North Sydney Local Traffic Committee to install the 'Work Zone'. A Work Zone permit is required to be issued by the Council prior to the issue of any Construction Certificate.

Work Zones are provided specifically for the set down and pick up of materials and not for the parking of private vehicles associated with the site. Works Zones will generally not be approved where there is sufficient space on-site for the setting down and picking up of goods being taken to or from a construction site. If the Work Zone is approved by the Committee, the Applicant must obtain a written copy of the related resolution from the North Sydney Local Traffic Committee and submit a copy of this to the Certifying Authority to enable issue of the Construction Certificate.

Where approval of the 'Work Zone' is given by the Committee, the requirements of the Committee, including installation of the necessary 'Work Zone' signage and payment of any fees, must occur prior to commencement of any works on the site. Further, at the expiration of the Work Zone approval, the developer is required to remove the Work Zone signs and reinstate any previous signs, all at the developer's cost. The requirements imposed by the Committee on the Work Zone permit (or permits) must be complied with at all times.

(Reason: Amenity and convenience during construction)

#### Maintain Property Boundary Alignment Levels

C17. Except where otherwise approved by Council, the property boundary alignment levels must match the levels which existed prior to the commencement of works. Plans and specifications which document existing and proposed levels adjacent to the site boundaries and which comply with the requirements of this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate.

The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To ensure interface between property and public land remains uniform)

# **Bicycle Storage and Parking**

- C18. The bicycle storage area must accommodate a minimum of 13 bicycles, and a visitor parking bicycle rail shall be provided for 2 bicycles. The bicycle storage lockers and bicycle rail shall be designed in accordance with the applicable Australian Standards. Plans and specifications which comply with this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the building plans and specifications, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.
  - (Reason: To promote and provide facilities for alternative forms of transport)

# Accessible Parking Spaces to be Provided

- C19. A total of 3 accessible parking spaces shall be provided as part of the total car-parking requirements. Consideration must be given to the means of access from the car-parking spaces to adjacent buildings, to other areas within the building and to footpath and roads. All details shall be prepared in consideration of, and construction completed in accordance with applicable Australian Standards to achieve compliance with the Disability Discrimination Act. Plans and specifications which comply with this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate.
  - (Reason: To ensure equity of access and appropriate facilities are available for people with disabilities in accordance with Federal legislation)

# Allocation of Spaces

C20. Car parking spaces must be provided and maintained at all times on the subject site. The spaces shall be allocated to uses within the building in accordance the following table:

Residential	Parking Spaces
One Bedroom Apartments (1 space per apartment)	3
Two Bedroom Apartments (1 space per apartment)	4
Three Bedroom Apartments (Including 3 Accessible Parking Spaces) (1	9
or 2 spaces per apartment)	
Visitor	3
Total	19

The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To ensure that adequate parking facilities to service the development are provided on site)

# Basement Car Park to Comply with Relevant Standards

- C21. The basement layout must comply with all requirements of Australian Standard AS2890.1. Certification from a suitably qualified and practicing Civil Engineer that the basement design will comply with the requirements of the Australian Standard must be provided to the Certifying Authority for approval prior to issue of any Construction Certificate.
  - (Reason: To ensure the basement layout complies with relevant standards)

# Required Infrastructure Works - Roads Act 1993

C22. Prior to issue of any Construction Certificate engineering design plans and specifications must be prepared by a qualified civil design engineer. The plans and specifications must be to a detail suitable for construction issue purposes and must provide detail and specification for the following infrastructure works to be completed as part of the development. To obtain the permit, an application must be made to Council on a *Application to satisfy development consent'* form with payment of the adopted assessment/inspection fees. The responsibility for accuracy of the design fully rests with the designing engineer. All responsibility on implementation and supervision of works specified on design plans fully rests on designing engineer or whoever is chosen to be applicant' engineering representative:

# Road Works

- a) All redundant layback crossings on Allister Street must be reinstated as upright kerb gutter, grass verge and concrete footpath.
- b) Construction of a fully new replacement concrete footpath is required across the entire site frontage in Allister Street. A longitudinal section is required along the footpath property boundary at a scale of 1:50 extending 5m past the property boundary line. The footpath shall be designed (at a single straight grade of 3% falling to top of kerb) so that it is uniform without showing signs of dipping or rising particularly at entrances.
- c) Construction of a fully new kerb and gutter is required across the entire site frontage in Allister Street. A longitudinal section is required along the gutter line (existing and proposed levels), at a scale of 1:50 extending 5m past the property boundary line.
- d) Cross sections at a scale of 1:50 along the centre-line of each access point to the building must be provided and are to show the calculated clearance to the underside of any overhead structure. All the entry points are to comply with the Building Code of Australia (BCA), including disability requirements. The Council approved footpath levels must be accommodated at the building entry points.
- e) Construction of a fully new road shoulder (maximum grade 5% down towards new gutter) extending to 1.2 metres out from the gutter alignment and across the entire development site frontage.
- f) The proposed vehicular access ways must comply with AS 2890.1 and Council's current Vehicular Access Application Guidelines and Specification (gutter bridges not permitted) to ensure that a B85 vehicle will not scrape/strike the surface of the carriageway, layback, vehicular crossing or parking floor.

- g) The width of the vehicular layback must be 6.5m (including the wings).
- h) The boundary footpath levels must match the existing levels and shall not be altered unless agreed to by Council.
- i) The crossing section over the footpath (between the property boundary and grass verge) must be perpendicular on a single straight grade of approximately 3% but no more than 4.5%, falling to the grass verge. The driveway crossing section over the grass verge (between the lip of the layback and footpath) must be perpendicular on a single straight which if necessary, may be greater than 4.5%, but taking into account that the change in cross fall grade in between the road shoulder and driveway crossing is no more than 15%.
- j) All inspection openings, utility services must be adjusted to match the proposed footpath and/or driveway levels and location.
- k) The design detail has to be provided and must include sections along centre-line and extremities of the crossing at a scale of 1:25. Sections are to be taken from the centre of the roadway through to the parking area itself and shall include all changes of grade and levels, **both** existing and proposed.
- A longitudinal section along the gutter line of Allister Street at a scale of 1:50 showing how it is intended to transition the layback with the existing gutter levels and shall include all changes of grade and levels, **both** existing and proposed.
- m) A longitudinal section along the footpath property boundary at a scale of 1:50 is required and shall include all changes of grade and levels, **both** existing and proposed.
- n) The sections must show the calculated clearance to the underside of any overhead structure.
- o) All details of internal ramps between parking levels.
- p) A swept path analysis is required demonstrating that an 85th percentile vehicle can manoeuvre in and out of the parking spaces in accordance with AS 2890.1 2004 "Off Street Parking".

# Drainage Works

Connection of the site stormwater system must be made directly to a newly constructed grated gully pit (with lintel), to front the site on Allister Street. To accommodate this requirement, the following drainage infrastructure works must be carried out on Council property at the Applicants expense:

a) Construction of a standard grated gully pit with extended kerb inlet (1.8m lintel) in the kerb fronting the subject site in Allister Street. The pit must be constructed in accordance with Councils "Infrastructure Specification for Roadworks, Drainage and Miscellaneous Works".

- b) Construction of a new in-ground drainage line under the kerb and gutter at standard depth. The line must connect the new gully pit to the existing Council pit located approximately 52m downstream of the site on Allister Street. The pipes within the road reserve are to be reinforced concrete class 2 with a minimum 375mm diameter and have bedding in accordance with Australian Standard AS 3725 (Loads on buried concrete pipes). The developer shall be responsible for carrying out any service investigations to allow a gravity connection.
- c) Construction of another standard grated gully pit with extended kerb inlet (1.8m lintel) in the kerb downstream somewhere just before the street band fronting the site 9-11 Allister Street. The pit must be constructed in accordance with Councils "Infrastructure Specification for Roadworks, Drainage and Miscellaneous Works".

Plans and specifications which comply with this condition must be submitted to the Certifying Authority for approval prior to the issue of the relevant Construction Certificate.

Certifying Authorities must not issue a Construction Certificate without the formal written approval of Council (as Roads Authority) under the Roads Act 1993.

The required plans and specifications are to be designed in accordance with North Sydney Council's current documents Infrastructure Specification for Road Works, Drainage and Miscellaneous Works and Performance Guide for Engineering Design and Construction. The drawings must detail existing utility services and trees affected by the works, erosion control requirements and traffic management requirements during the course of works. A detailed survey must be undertaken as required. Traffic management is to be certified on the drawings as being in accordance with the documents SAA HB81.1 – 1996 – Field Guide for Traffic Control at Works on Roads – Part 1 and RMS Traffic Control at Work Sites (1998). Construction of the works must proceed only in accordance with any conditions attached to the Council Roads Act 1993 approval.

- **Note:** A minimum of 21 days will be required for Council to assess Roads Act submissions. Early submission is recommended to avoid any delays in obtaining a Construction Certificate. A fee to cover cost of assessment (set out in Council's adopted fees and charges) is payable and Council will withhold any consent and approved plans until full payment of the correct fees. Plans and specifications must be marked to the attention of Council's Development Engineers. In addition, a copy of this condition must be provided, together with a covering letter stating the full address of the property and the accompanying DA number.
- (Reason: To ensure infrastructure works are designed and constructed to appropriate standards and requirements of the Roads Act 1993)

#### Stormwater Management and Disposal Design Plan - Construction Issue Detail

- C23. Prior to issue of any Construction Certificate, the applicant shall have a site drainage management plan prepared by a qualified drainage design engineer. The site drainage management plan must detail the following requirements of North Sydney Council:
  - a) Compliance with BCA drainage requirements, Councils Engineering Performance guide and current Australian Standards and guidelines, such as AS/NZ3500.3.2 1998, National Plumbing and Drainage Code.

- b) Stormwater roof and surface runoff generated by the approved dwellings must be conveyed in a controlled manner by gravity via a direct connection to Council's stormwater gully pit in Allister Street, which is to be constructed. Runoff from driveway ramp and subsoil drainage generated by the approved dwellings must be conveyed in a controlled manner by pump-out system to the same on-street gully pit. When a direct connection to the pit option is implemented then the pipeline within the footpath area shall have a minimum cover of 300mm.
- c) All civil and drainage works within the road reserve must be designed and built in accordance with Council's current "Infrastructure Specification". Prior to issue of the Construction Certificate the applicant must have engineering plans and specifications, prepared by a qualified civil drainage design engineer. Council must approve the plans and specifications, in writing, prior to issue of any Construction Certificate by the Certifying Authority. The documentation must provide engineering construction detail for the following public infrastructure works that must be completed as part of the approved development. Council reserve the right of keeping all bonds on infrastructure works for 12 month defects liability period.
- d) Video inspection must be carried out of completed drainage works that are to revert to council and a video tape forwarded to council's development engineer to support the certification. Bonds held by Council will be returned after receipt of satisfactory information.
- e) The stormwater drainage system shall be designed for an average recurrence interval (A.R.I.) of 1 in 20 years.
- f) All redundant stormwater pipelines within the footpath area shall be removed and the footpath and kerb reinstated.
- g) All sub-soil seepage drainage shall be discharged via a suitable silt arrester pit. Details of all plans certified as being adequate for their intended purpose and complaint with the provisions of AS3500.3.2 by an appropriately qualified and practising civil engineer, shall be submitted with the application for a Construction Certificate.
- h) The design and installation of the Rainwater Tanks shall comply with Basix and Sydney
  Water requirements. Overflow from tank shall be connected by gravity to the stormwater disposal system.
- i) Provide subsoil drainage to all necessary areas with pump out facilities as required.

Details demonstrating compliance are to be submitted with the Construction Certificate.

The Certifying Authority issuing the Construction Certificate must ensure that the approved drainage plan and specifications, satisfying the requirements of this condition, is referenced on and accompanies the Construction Certificate.

(Reason To ensure controlled stormwater management and disposal without nuisance)

#### **On-site Stormwater Detention**

C24. On site detention must be provided to ensure that the maximum discharge from the site does not exceed discharge which would occur during a 1 in 5 year storm for the time of concentration determined for the particular site, for the existing site conditions. All other stormwater run-off from the site for all storms up to the 1 in 100 year storm is to be retained on the site for gradual release to the kerb and gutter or drainage system. Provision is to be made for satisfactory overland flow should a storm in excess of the above parameters occur.

Determination of the required cumulative storage must be based on the mass curve technique as detailed in Technical Note 1, Chapter 14 of the Australian Rainfall and Runoff Volume 1, 1987 Edition.

Engineering calculations, design and certification complying with this condition must be provided by an appropriately qualified and practicing Civil Engineer and submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate.

(Reason: To ensure appropriate provision is made for the disposal and management of stormwater generated by the development, and to ensure that public infrastructure in Council's care and control is not overloaded)

# Bond for Damage and Completion of Infrastructure Works - Stormwater, Kerb and Gutter, Footpaths, Vehicular Crossing and Road Pavement

- C25. Prior to the issue of any Construction Certificate, security deposit or bank guarantee must be provided to Council to the sum of \$110,000.00 to be held by Council for the payment of cost for any/all of the following:
  - a) making good any damage caused to any property of the Council as a consequence of the doing of anything to which this consent relates,
  - completing any public work (such as road work, kerbing and guttering, footway construction, stormwater drainage and <u>environmental controls</u>) required in connection with this consent.
  - c) remedying any defects in any such public work that arise within one year for stormwater and 6 months for major road works and two months for vehicular crossing and small associated footpath works, after the work is completed

The security required by this condition and in the schedule contained later in these conditions must be provided by way of a deposit with the Council; or other such guarantee that is satisfactory to Council (such as a bank guarantee). Any guarantee provided as security must name North Sydney Council as the nominated beneficiary and must not be subject to an expiry date.

The security will be refundable following the expiration of six months from the issue of any final Occupation Certificate or completion of public work required to be completed (whichever is the latest) but only upon inspection and release by Council's Engineers.

Council shall have full authority to make use of the bond for such restoration works as deemed necessary by Council in circumstances including the following:

- where the damage constitutes a hazard in which case Council may make use of the security immediately;
- the applicant has not repaired or commenced repairing damage within 48 hours of the issue by Council in writing of instructions to undertake such repairs or works;
- works in the public road associated with the development are to an unacceptable quality; and
- the Certifying Authority must ensure that security is provided to North Sydney Council prior to issue of any Construction Certificate.

(Reason: To ensure appropriate security for works on public land and an appropriate quality for new public infrastructure)

# Upgrade of Existing Building - Fire Spread and Safe Egress

C26. Pursuant to Section 94 of the EP&A Regulation 2021, aspects of the existing building must be brought into conformity with the Building Code of Australia (BCA). Work must be carried out as part of the development so as to upgrade the building to bring it into compliance with Sections C, D & E of the NCC BCA 2019, Volume 1.

Plans and specifications showing the upgrading works which must be carried out under this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate.

Notes:

- 1) The Certifying Authority must be satisfied that the plans and specifications submitted prior to the issue of any Construction Certificate comply with the requirements of this condition.
- 2) The Certifying Authority issuing the Construction Certificate has no power to remove the requirements to upgrade the existing building as required by this condition.
- 3) Where this condition specifies compliance with the performance requirements of the BCA, the Certifying Authority, subject to their level of accreditation, may be satisfied as to such matters.

(Reason: Application of Regulations relating to Fire and Life Safety)

# Project Arborist to be Commissioned

C27. An experienced AQF Level 5 consulting arborist must be commissioned to assist the design development, contract documentation and overseeing of construction works on the site for their duration by undertaking regular inspections of the works in progress and providing advice in relation to tree matters.

Written details of the engagement of the experienced arborist must be submitted to the Certifying Authority prior to the issue of any Construction Certificate.

Note: This condition, and any advice given by the consulting arborist, should not be construed as authorising the carrying of development with/ otherwise than in accordance with the development consent.

(Reason: Tree protection measures)

#### **Tree Protection**

- C28. To ensure the protection of all trees to be retained, the following measures are to be undertaken:
  - a) All documentation for the Construction Certificate application must show the site trees to be retained, and retention of the adjoining trees, with their positions and diameters of trunks and crowns (canopies) to be clearly and accurately shown in relation to all levels of the proposed development.
  - b) All plans and documentation must refer to the required compliance with the approved Tree Protection and Management Plan, and clearly show the assigned number of each tree on the site and adjoining and Council land.
  - c) A Consulting Arboriculturist ("the project arboriculturist"), who holds a minimum Australian Qualification Framework Level 5 in Arboriculture, is a registered consulting member of a nationally recognised arboricultural organisation or association shall be engaged before work commences for the duration of site preparation, demolition, construction and landscaping.
  - d) The project arboriculturist shall inspect, monitor, supervise, provide recommendations and written reports and certification relating to protection of the trees and compliance with the conditions of consent.
  - e) The contact details of the project arboriculturist shall be advised to council before work commences and maintained up to date for the duration of works. If a new project arborist is appointed details of the new project arborist shall be notified to council within 7 days.
  - f) The project arboriculturist is to submit a list of critical stages where joint site inspections with Council's Landscape Development Officer may be required, with the adopted schedule to be complied with during the course of works, and include at minimum, the following hold points:
    - i. Prior to demolition of existing structures;
    - ii. At commencement of any excavation works within 7 metres of any tree to be retained.
    - iii. Prior to any tree crown or root pruning;
    - iv. At commencement of construction works within 7 metres of any tree to be retained.

(Reason: Tree protection measures)

#### **Tree Bond for Public Trees**

C29. Prior to the issue of any construction certificate, security in the sum of \$20,000.00 must be provided to Council for the protection of trees in public places, including the making good of any damage caused to such trees. The security is to be provided in accordance with the Schedule below.

The security required by this condition and in the schedule contained later in these conditions must be provided by way of a deposit with the Council; or other such guarantee that is satisfactory to Council (such as a bank guarantee). Any guarantee provided as security must name North Sydney Council as the nominated beneficiary and must not be subject to an expiry date.

The security will be refundable following the expiration of 6 months from the issue of any final Occupation Certificate but only upon inspection and release by Council's Landscape Development Officer.

If any tree is removed or damaged Council may deduct from this security the reasonable cost of replacement with a tree of the same species and to a similar stage of growth it would have attained at the completion of the work.

In the case of any tree, which cannot be replaced with a similar specimen, the security for that tree will be forfeited to Council and used to provide replacement street plantings.

#### SCHEDULE

Tree Species	Location	Bond
4 x Photinia sp.	Council verge in front of No. 13-15 Allister	4 x \$5,000
	Street,	Total \$20,000

(Reason: Protection of existing environment public infrastructure, community assets and significant trees)

#### Tree Protection Measures to be shown on Construction Drawings

- C30. The tree protection measures contained in the arborist report prepared by [Blues Brothers, Version 6, dated 17 April 2023, and as subsequently amended by conditions of this development consent shall be shown clearly on Construction Certificate drawings. Plans and specifications showing the said tree protection measures must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure the construction plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.
  - (Reason: To ensure that appropriate tree protection measures are shown on construction drawings)

#### Protection of Trees

C31. The following tree(s) are required to be protected and retained as part of the development consent in accordance with AS 4970-2009 - Protection of trees on development sites:

Tree	Location	Height
4 x Photinia sp.	Council verge in front of No. 13-15 Allister Street	4-5m
T4 Angophora costata	Southeastern corner of the site	11x8m
T8 Gordonia axillaris	Northwestern corner of the site	7x6m

Plans and specifications complying with this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

Any tree(s) shown as being retained on the approved plans (regardless of whether they are listed in the above schedule or not) must be protected and retained in accordance with this condition.

(Reason: Protection of existing environmental and community assets)

#### Approval for Removal of Trees

C32. The following tree(s) are approved for removal in accordance with the development consent:

Trees to be Removed	Location	Height
1 x Photinia sp.	Council verge in front of No. 13-15 Allister Street	4-5m
T2 Camellia sasanqua	Centre of the site	8x6m
T3 Viburnum tinus	Centre of the site	6x5m
T5 Glochidion ferdinandi	Front setback of the site	10x12m
T6 Glochidion ferdinandi	Northeastern corner of the site	8x6m
T7 Olea europa	Northeastern corner of the site	6x5m

Removal or pruning of any other tree on the site is not approved, excluding species exempt under Council's Tree Preservation Order.

Any tree(s) shown as being retained on the approved plans (regardless of whether they are listed in the above schedule or not) must be protected and retained in accordance with this condition.

(Reason: Protection of existing environmental and community assets)

#### **Pruning of Trees**

C33. All pruning works shall to the following tree(s) shall be undertaken under the guidance of an appropriately qualified arborist/tree surgeon in accordance with Australian Standard AS 4373-2007 - Pruning of Amenity Trees:

Tree	Location	Height
T4 Angophora costata)	Southeastern corner of the site	11x8m

Pruning to T4 is to be limited to a maximum of 5% of the tree canopy. The construction tree protection plan is also to address the erection of scaffolding or use of piling rigs, cranes etc within the vicinity of any tree required to be retained to ensure no additional pruning is required. Prior to undertaking any pruning, marked up pictures and accompanying statement form a suitable qualified arborist is to be provided to Council's Landscape Development Officer for

(Reason: Protection of existing environment public infrastructure, community assets and significant trees)

#### Garbage and Recycling Facilities

written approval.

- C34. An appropriate area must be provided within the premises for the storage of garbage bins and recycling containers and all waste and recyclable material generated by this premises. The following requirements must be met:
  - a) all internal walls of the storage area must be rendered to a smooth surface, coved at the floor/wall intersection, graded and appropriately drained with a tap in close proximity to facilitate cleaning;
  - b) provision for the separation and storage in appropriate categories of material suitable for recycling;
  - c) the storage area must be adequately screened from the street, with the entrance to the enclosures no more than 2 m from the street boundary of the property;
  - d) if a storage facility is to be provided at another suitable location within the building, a complementary garbage bin holding bay must be provided no more than 2 m from the street boundary of the property;
  - e) garbage enclosures serving residential units are not to be located within areas designated for non-residential uses; and
  - f) garbage enclosures serving non-residential uses are not to be located within areas designated for dining purposes.

Plans and specifications which comply with this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate.

The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

- Note: The applicant may wish to discuss bin storage requirements and location with Council's Environmental Services prior to finalisation of the required detail, and a copy of Council's Waste Handling Guide should be obtained for reference purposes before the design is finalised.
- (Reason: To ensure the provision of appropriate waste facilities for residents and protect community health, and to ensure efficient collection of waste by collection contractors)

# Asbestos Material Survey

C35. A report must be prepared by a suitably qualified person in relation to the existing building fabric to be demolished and/or disturbed identifying the presence or otherwise of asbestos contamination and, if asbestos contamination is present, making recommendations as to the work required to safely address the contamination.

Any demolition works or other works identified in the report as having to be carried out must be carried out in accordance with the recommendations of the report and the following:

- a) the removal of asbestos must be undertaken by a WorkCover licensed contractor;
- b) all removal must be in strict accordance with the requirements of the WorkCover Authority in relation to the removal, handling and disposal of material containing asbestos and any Work Safe Australia requirements.
- c) during the removal of any asbestos a sign stating "DANGER ASBESTOS REMOVAL IN PROGRESS" must be erected in a visible position at the boundary of the site; and
- d) Waste disposal receipts must be provided to the Certifying Authority as proof of correct disposal of asbestos laden waste.

The report must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the report, and other plans, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To ensure the long-term health of workers on site and occupants of the building is not put at risk unnecessarily)

#### Location of Plant

- C36. All plant and equipment (including but not limited to air conditioning equipment) is to be located within the basement of the building and is not to be located on balconies or the roof. Plans and specifications complying with this condition must be submitted to the Certifying Authority for Approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.
  - (Reason: Minimise impact on surrounding properties, improved visual appearance and amenity for locality)

#### Noise from Plant and Equipment

- C37. The use of all plant and equipment installed on the premises must not:
  - (a) Contribute an LAeq(15min) which will cause the total LAeq(15min) from all plant and equipment operating contemporaneously on the site or in the strata scheme or in the mixed strata schemes to exceed the RBL by more than 5dB when measured at the boundary of any affected receiver. The modifying factor adjustments in Section 4 of the EPA Industrial Noise Policy shall be applied.

(b) Cause "offensive noise" as defined in the *Protection of the Environment Operations Act* 1997.

"affected receiver" includes residential premises (including any lot in the strata scheme or another strata scheme), premises for short-term accommodation, schools, hospitals, places of worship, commercial premises and parks and such other affected receiver as may be notified by the Council in writing.

"boundary" includes any window or elevated window of an affected receiver.

Terms in this condition have the same meaning as in the Noise Guide for Local Government and the Industrial Noise Policy published by the NSW Environment Protection Authority.

(Reason: To maintain an appropriate level of amenity for adjoining land uses)

#### **Vibration from Plant and Equipment**

C38. The use of all plant and equipment to be installed on the premises must comply with the vibration limits specified in "Assessing Vibration: a technical guideline" issued by the NSW Environment Protection Authority, at the boundary of any affected receiver.

A certificate from an appropriately qualified acoustical consultant eligible for membership of the Association of Australian Acoustic Consultants must be submitted to the Certifying Authority, certifying that all plant and equipment on the site, together with the proposed plant and equipment, operating contemporaneously will comply with the requirements of this condition.

The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

"affected receiver" includes residential premises (including any lot in the strata scheme or another strata scheme), premises for short-term accommodation, schools, hospitals, places of worship and commercial premises and such other affected receiver as may be notified by the Council in writing.

"boundary" includes any window or elevated window of an affected residence.

"contemporaneously" means *existing at or occurring in the same period of time* (Macquarie Dictionary 3rd rev. ed. 2004).

(Reason: To maintain an appropriate level of amenity for adjoining land uses)

#### Air Conditioners in Residential Premises

- C39. The use of any air conditioner installed on the premises must comply with the requirements of the Protection of the Environment Operations (Noise Control) Regulations 2008 and State Environmental Planning Policy (Infrastructure) 2007 and must not:
  - (a) emit a noise that is audible within a habitable room in any affected residence (regardless of whether any door or window to that room is open);

- (i) before 8.00 am and after 10.00 pm on any Saturday, Sunday or Public Holiday; or
- (ii) before 7.00 am or after 10.00 pm on any other day
- (b) cause an LAeq(15min) which exceeds the RBL background noise level by more than 5dB when measured at the boundary of any affected residence. The modifying factor adjustments in Section 4 of the EPA Industrial Noise Policy will be applied.

"affected residence" includes residential premises (including any lot in the strata scheme or another strata scheme), premises for short-term accommodation and hospitals.

"boundary" includes any window or elevated window of an affected residence.

Terms in this condition have the same meaning as in the Noise Guide for Local Government and the Industrial Noise Policy published by the NSW Environment Protection Authority.

(Reason: To maintain residential amenity)

#### Acoustic Privacy (Residential Apartments)

C40. Noise levels in sole occupancy units of residential apartments must not exceed the following:

Location	Maximum
Habitable Rooms other than Sleeping Areas	40 LAeq (1hr)
Sleeping Areas	35 LAeq (1hr)

The "Maximum" limits are to apply in any hour of a 24-hour period with the windows of the sole occupancy unit closed.

"habitable room" has the same meaning as in the National Construction Code.

A floor separating sole occupancy units shall have a weighted standardised impact sound pressure level L'nT,w not more than 55dB when measured insitu in accordance with AS ISO 140.7-2006 "Field measurements of impact sound insulation of floors," and rated to AS ISO 717.2-2004 "Rating of sound insulation in buildings and of building elements. Part 2: Impact sound insulation." This clause shall not apply to the floor of a kitchen, bathroom, toilet or laundry in a residential sole occupancy unit.

Mechanical equipment such as lift plant, air conditioning plant servicing the building and pumps shall not be located immediately adjacent bedrooms.

A statement from an appropriately qualified acoustical consultant eligible for membership of the Association of Australian Acoustic Consultants, certifying that the acoustic mitigation measures outlined above have been satisfied, must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate.

(Reason: To comply with best practice standards for residential acoustic amenity)

# Noise and Vibration Compliance Certification Prior to Issue of Construction Certificate

C41. A certificate from an appropriately qualified acoustical consultant eligible for membership of the Association of Australian Acoustic Consultants, certifying that suitable measures have been incorporated into the development and that the noise criteria contained in the conditions herein have been satisfied, must be provided to the Certifying Authority for approval prior to the issue of any Construction Certificate.

The Principal Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To maintain an appropriate level of amenity for adjoining land uses)

# **Mechanical Exhaust Ventilation**

C42. A statement from an appropriately qualified and practising Mechanical Engineer is required detailing how the exhaust ventilation system will be installed in accordance with AS1668. The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

The mechanical exhaust ventilation ducting mounted on the roof of the building is to have a maximum RL of 88.3.

(Reason: To ensure compliance with acceptable standards for the construction and operation of mechanical plant)

# **Construction Noise Management Plan**

- C43. A Construction Noise Management Plan must be prepared by an appropriately qualified acoustical consultant eligible for membership of the Association of Australian Acoustic Consultants, and must include the following:
  - (a) Identification of noise affected receivers near to the site.
  - (b) A prediction as to the level of noise impact at noise affected receivers from the use and proposed number of high noise intrusive appliances intended to be operated onsite.
  - (c) Details of work schedules for all construction phases;
  - (d) A statement should also be submitted outlining whether or not predicted noise levels will comply with the noise criteria stated within the Environment Protection Authority's Interim Construction Noise Guideline ("ICNG").
  - (e) Representative background noise levels should be submitted in accordance with the ICNG.
  - (f) Confirmation of the level of community consultation that is to be undertaken by occupants at noise affected receivers likely to be most affected by site works and the operation of plant/machinery particularly during the demolition and excavation phases.

- (g) Confirmation of noise monitoring methodology that is to be undertaken during the noise intensive stages of work including details of monitoring to be undertaken at the boundary of any noise affected receiver.
- (h) What course of action will be undertaken following receipt of a complaint concerning offensive noise?
- (i) Details of any noise mitigation measures that have been outlined by an acoustic consultant or otherwise that will be deployed on site to reduce noise impacts on the occupants at noise affected receivers.
- (j) Details of selection criteria for any plant or equipment that is to be used on site, the level of sound mitigation measures to be undertaken in each case and the criteria adopted in their selection taking into account the likely noise impacts on occupants at noise affected receivers and other less intrusive technologies available; and
- (k) Details of site induction to be carried out for all employees and contractors undertaking work at the site.

"affected receiver" includes residential premises (including any lot in the strata scheme or another strata scheme), premises for short-term accommodation, schools, hospitals, places of worship, commercial premises and parks and such other affected receiver as may be notified by the Council in writing.

"boundary" includes any window or elevated window of an affected residence.

The Construction Noise Management Plan and must be submitted to the Principal Certifying Authority and a copy provided to Council prior to the issue of the Construction Certificate.

(Reason: To ensure noise generating activities are appropriately managed and nearby sensitive receivers protected)

#### Provision of Accessible Paths of Travel

C44. The building must be designed and constructed to provide access and facilities in accordance with the Building Code of Australia and Disability (Access to Premises - Buildings) Standards 2010. Plans and specifications complying with this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

Notes:

- 1. If, in complying with this condition, amendments to the development are required, the design changes must be submitted for the approval of Council prior to a Construction Certificate being issued. Approval of a modification application may be required.
- It is not within Council's power to set aside National legislation which requires the upgrade of buildings to meet modern access standards. Such decisions remain the jurisdiction of the Building Professionals Board Access Advisory Committee who may grant an exemption in certain exceptional circumstances.

- 3. Information on making an application for an "unjustifiable hardship exemption" under the accessibility standards can be found in the website of the NSW Building Professional Boards at <a href="http://www.bpb.nsw.gov.au/page/premises-standards">http://www.bpb.nsw.gov.au/page/premises-standards</a>.
- (Reason: To ensure the provision of equitable and dignified access for all people in accordance with disability discrimination legislation and relevant Australian Standards)

## Underground Electricity and Other Services

- C45. All overhead electricity and other lines (existing and proposed) must be undergrounded from the proposed building on the site to the appropriate power pole(s) or other connection point, in accordance with the requirements of Energy Australia. Plans and specifications complying with this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the building plans and specifications submitted fully satisfy the requirements of this condition.
  - (Reason: To provide infrastructure that facilitates the future improvement of the streetscape by relocation of overhead lines below ground)

## Screen Planting

C46. To maintain acceptable levels of privacy, screen planting must be installed and maintained adjacent to the southern side boundary of the site in locations shown clouded red on the stamped approved plans. The required screen planting must consist of suitable screening species capable of attaining a mature height of 2.5-3.0 metres above finished ground levels. Details of the screen planting required by this condition must be provided to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the details submitted fully satisfy the requirements of this condition.

(Reason: To preserve the privacy of adjoining properties)

# Adaptable Housing

- C47. Proposed apartments 3 are to be designed with accessible features for disabled persons and must incorporate level entries and wider doorways and corridors, slip resistant surfaces, reachable power points, disabled toilet, and lever door handles and taps. These features are to be designed generally in accordance with the relevant Australian Standard 4299-1995. Plans and specifications complying with this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.
  - (Reason: To ensure equity of access and availability of accommodation in the future for an ageing population)

## Section 7.11 Contributions

C48. A monetary contribution pursuant to the provisions of Section 7.11 of the Environmental Planning and Assessment Act 1979 is to be paid to Council, in accordance with the North Sydney Council's Contribution Plan, to provide for local infrastructure improvements.

Based on the cost of development at the date of determination, the total contribution payable to Council is **\$106,643.82**.

Α	В (\$)
Open Space and recreation facilities	\$58,722.84
Public domain	\$32,689.27
Active transport	\$1,865.78
Community Facilities	\$11,794.76
Plan Administration and Management	\$1,571.18
The total contribution is	\$106,643.82

#### Indexation

The monetary contribution required under this consent will be indexed at the time of payment in accordance with quarterly movements in the Consumer Price Index (All Groups Index) for Sydney as published by the Australian Bureau of Statistics.

#### **Timing of Payment**

The contribution must be paid to Council prior to issue of any Construction Certificate for any work approved by this consent.

A copy of the North Sydney Contribution Plan can be viewed at North Sydney Council's Customer Service Centre, 200 Miller Street, North Sydney or downloaded via Council's website at <u>www.northsydney.nsw.gov.au</u>.

(Reason: To provide for local infrastructure identified in the North Sydney Council Local Contributions Plan 2020)

#### Security Deposit/Guarantee Schedule

C49. All fees and security deposits/guarantees in accordance with the schedule below must be provided to Council prior to the issue of any Construction Certificate:

Security Deposit/Guarantee	Amount (\$)
Street Tree Bond (on Council Property)	\$20,000.00
Infrastructure Damage Bond	\$14,000.00
Drainage Engineering Bond	\$33,000.00
Engineering Construction Bond	\$63,000.00
TOTAL BONDS	\$130,500.00

Note: The following fees applicable

Fees	
Section 7.11 Contributions	\$106,643.82
TOTAL FEES	\$106,643.82

The security required by the above schedule must be provided by way of a deposit with the Council; or other such guarantee that is satisfactory to Council (such as a bank guarantee). Any guarantee provided as security must name North Sydney Council as the nominated beneficiary and must not be subject to an expiry date.

(Reason: Compliance with the development consent)

## **BASIX Certificate**

- C50. Under Section 75 of the Environmental Planning and Assessment Regulation 2021, it is a condition of this development consent that all the commitments listed in BASIX Certificate No. 1339223M\_02 dated 5 February 2023 and Certificate No. 1339489M\_02, dated 2 June 2023 (issued under the Alternative Assessment Pathway) for the development are fulfilled. Plans and specifications complying with this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.
  - (Reason: To ensure the proposed development will meet the Government's requirements for sustainability and statutory requirements)

## Outdoor Lighting

- C51. All outdoor lighting must comply with, where relevant AS/NZ1158.3:1999 Pedestrian Area (Category P) Lighting and AS4282:1997 Control of the Obtrusive Effects of Outdoor lighting. Details demonstrating compliance with these requirements must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the building plans and specifications submitted fully satisfy the requirements of this condition.
  - (Reason: To maintain the amenity of adjoining land uses)

#### Amendments to the Landscape Plan

- C52. The landscape plan must be amended as follows to provide an appropriate landscaped setting:
  - 1 x Jacaranda mimosifolia (100l) shown to be planted in the northeastern corner of the subject site shall be 400l min pot size.
  - 5x *Elaeocarpus reticulatus* (500mm) shown to be planted along the eastern boundary of the subject site shall be replaced with 5 x *Callicoma serratifolia* (500mm).
  - 10x Osmanthus fragrans (300mm) shown as feature planting within the southern setback planters shall be reduced in number to 5 x O. fragrans alternated with 5 x less sparsely foliaged plant of similar dimensions (300mm).
  - 3 x new replacement *Photinia sp* (75minl) shall be planted in the council verge in front of Nos. 13-15 Allister (1 to replace that removed, + 2 x additional).

- 20x Viburnum tinus (200mm) are considered too susceptible to pest infestation in this location and shall be replaced with a more reliable species (eg. *Murraya paniculata*) (300mm).
- 2x 400mm Pyrus *calleryana* 'Cleveland Select' feature trees shown to be planted on either side of the pedestrian entrance within the front setback of 13-15 Allister Street shall be replaced with 2 x Acer x *freemanii* 'Jeffersred' (200I).
- 1 x *Corymbia maculata* (100l) shown to be planted in the SW corner of the subject site shall be replaced with 3 x Corymbia maculata (100l) planted as a grove.
- 40 x *Syzigium* 'Cascade' (250mm) shall be replaced with 40 x *Syzigium* 'Cascade' (300mm)
- Stormwater and associated works (including 3 x pits as shown) shall be diverted outside the TPZ of T4.

An amended landscape plan complying with this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the amended landscape plan and other plans and specifications submitted fully satisfy the requirements of this condition.

(Reason: To ensure residential amenity)

## **Root Mapping**

C53. Non-invasive/non- destructive root mapping is to be undertaken within the tree protection zone (TPZ) (identified as per AS4970-2009) of the T4 located within the southeastern corner of the site to determine the size and depth of the tree roots prior to the design of any required piers/footings for any structures outside the footprint of the basement within the TPZ of this tree.

Root mapping is to be undertaken under the direct supervision of an AQF level 5 arborist. The said consulting/ project arborist is to prepare a written report, with images, addressing the following:

- a) describing the results of the root mapping;
- b) providing an assessment of potential tree impacts of the excavation; and
- c) making recommendations of protection measures to be implemented for the duration of excavation and construction activity to ensure the ongoing health and viability of the tree.

The report is to be provided to the Certifying Authority for approval (with a copy provided to Council) prior to the issue of any Construction Certificate. Plans and Specifications submitted to the Certifier for approval must comply with the recommendations of the arborist report referred to in this condition, and the development must be carried out in accordance with the said report.

(Reason: To ensure the protection of significant trees)

## D. Prior to the Commencement of any Works (and continuing where indicated)

## Photographic Survey (Heritage Items)

- D1. Prior to any works commencing a photographic survey recording, in accordance with the NSW Heritage Office Guidelines, "Photographic recording of Heritage Items using file or digital capture," is to be prepared for No. 15 Allister Street, Cremorne to the satisfaction of Council's Historian and Conservation Planner. Two (2) copies of the photographic survey must be provided to Council.
  - (Reason: To provide a historical record of heritage significant fabric on site for archival purposes)

## Protection of Trees

D2. All trees that are specifically nominated to be retained by notation on plans or by condition as a requirement of this consent must be maintained and protected during demolition, excavation and construction on the site in accordance with AS4970-2009 (Protection of trees on development sites). A report containing recommendations, and methods of tree protection prepared by an appropriately qualified person must be provided to the Certifying Authority for approval by an appropriately qualified person prior to commencement of any works on the site. Any recommendations must be undertaken for the duration of works on the site.

Sensitive construction techniques including hand excavation, pier & beam construction & flexible location of piers/footings shall be used within the TPZ of any protected tree. No roots greater than 40mm shall be cut. No excavation or construction shall be permitted beyond the proposed building line in the direction of T4. No canopy pruning other than that expressly permitted as per C34 shall be carried out. No stormwater or any other underground services shall be directed through the TPZ of any protected tree.

(Reason: To ensure compliance with the requirement to retain significant planting on the site)

#### Tree Protection Measures

- D3. The tree protection measures detailed in the approved Tree Protection and Management Plan prepared in accordance with condition C28, and as directed by the project arboriculturist shall be established before work commences.
  - (Reason: To ensure that the stability and ongoing viability of trees being retained are not compromised Tree protection measures)

## Project Arborist to be Engaged

 The project arboriculturist shall inspect tree protection measures and certify in writing to the Principal Certifying Authority the measures comply with the approved Tree Protection Plan as directed by the project arboriculturist before work commences.

- The project arboriculturist shall provide guidance and oversight of tree protection and management to ensure that the stability and ongoing viability of trees being retained is not compromised.
- The project arboriculturist must receive written approval from Council's Landscape Development Officer in accordance with Condition C48 for any tree pruning. Should a joint site meeting be required, the tree contractor and Council's Tree Management Officer or Landscape Development Officer (giving at least two working days' notice) are to arrange a joint site meeting, prior to commencing any pruning, to determine the exact location and extent of pruning that is permissible, with the tree pruning contractor to comply with any instructions issued by Council.
- Any pruning must be undertaken by a practicing arborist with a minimum Australian Qualification Framework Level 3 in arboriculture, in accordance with the principles of the Australian Standard AS 4373-2007 'Pruning of Amenity Trees,' and the NSW Work Cover Code of Practice for the Amenity Tree Industry (1998), as well as any instructions issued on site by Council, acting reasonably.
- The project arborist must keep a log of dates and times of when they attended the site, the type of works that were performed, and must form part of the Occupation Certificate.

(Reason: Tree protection measures)

## **Protection of Public Trees**

D5. The following tree(s) are required to be protected and retained as part of the development consent in accordance with AS 4970-2009 - Protection of trees on development sites:

Tree	Location	Protection
A x Photinia co	Council verge in front of No. 13-15	1.8 m high steel mesh tree protection
4 x Photinia sp.	Allister Street.	fencing, branch protection

Trunk protection to be installed by first wrapping the stem of the tree in hessian or like material then strapping timber battens over the top. It is recommended that timber battens with the dimensions of length 2000 mm, width 75 mm and depth 50 mm are used. The battens are not to be directly screwed or nailed into the tree.

Plans and specifications complying with this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: Protection of existing environmental and community assets)

## **Temporary Fences and Tree Protection**

- D6. All protected trees on-site that are specifically nominated as per Condition C32 to be retained by notation on plans or by condition as a requirement of this consent must be tagged with luminous tape or the like for purposes of identification prior to demolition, excavation or construction works and must remain so for the duration of works on the site. No materials or builders' waste are to be stored in the vicinity of the nominated tree/trees at any time.
  - (Reason: To protect the trees to be retained on the site during construction works)

## Public Liability Insurance - Works on Public Land

- D7. Any person or contractor undertaking works on public land must take out Public Risk Insurance with a minimum cover of \$20 million in relation to the occupation of public land and the undertaking of approved works within Council's road reserve or public land, as approved by this consent. The Policy is to note and provide protection/full indemnification for North Sydney Council, as an interested party. A copy of the Policy must be submitted to Council prior to commencement of any works. The Policy must be valid for the entire period that the works are being undertaken.
  - Note: Applications for hoarding permits, vehicular crossings etc will require evidence of insurance upon lodgement of the application.
  - (Reason: To ensure the community is protected from the cost of any claim for damages arising from works on public land)

#### Notification of New Addresses

D8. Prior to the commencement of any building works, an application must be made and written confirmation received from North Sydney Council of the allocated street address (house number) and/or unit numbers of the completed project.

To assist Council, a plan for unit numbering should be submitted for concurrence. These details will be recorded in Council records and must be displayed at the property in accordance with the provisions of the applicable Australian Standard relating to rural and urban addressing. A copy of the allocation confirmation must be submitted to the Certifying Authority with the application for a Construction Certificate.

(Reason: To ensure that Council records are accurate, and that house numbering complies with the requirements of Council's House Numbering Policy. Proper house numbering also assists emergency services in readily locating properties)

#### Sydney Water Approvals

D9. Prior to the commencement of any works, the approved plans must be submitted to Sydney Water to determine whether the development application will affect Sydney Water's sewer and water mains, stormwater drains and/or easements, and if further requirements need to be met. The Certifying Authority must ensure that Sydney Water has appropriately stamped the plans before the commencement of building works.

- Notes: **Sydney Water Building Plan Approvals** can be obtained from the Sydney Water Tap in<sup>™</sup> online service. Building plans must be submitted to the Tap in<sup>™</sup> to determine whether the development will affect any Sydney Water sewer or water main, stormwater drains and/or easement, and if further requirements need to be met. For further information visit <u>http://www.sydneywater.com.au/tapin/index.htm</u> or call 13 000 TAP IN (1300 082 746) for further information.
- (Reason: To ensure compliance with Sydney Water requirements)

## **Asbestos Material Survey**

- D10. Prior to the commencement of any works, a report must be prepared by a suitably qualified person in relation to the existing building fabric to be demolished and/or disturbed identifying the presence or otherwise of asbestos contamination and, if asbestos contamination is present, making recommendations as to the work required to safely address the contamination. Any demolition works or other works identified in the report as having to be carried out must be carried out in accordance with the recommendations of the report and the following:
  - i. the removal of asbestos must be undertaken by a WorkCover licensed contractor;
  - ii. all removal must be in strict accordance with the requirements of the WorkCover Authority in relation to the removal, handling and disposal of material containing asbestos and any Work Safe Australia requirements.
  - iii. during the removal of any asbestos a sign stating "DANGER ASBESTOS REMOVAL IN PROGRESS" must be erected in a visible position at the boundary of the site; and
  - iv. Waste disposal receipts must be provided to the Certifying Authority as proof of correct disposal of asbestos laden waste.

The report must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the report, and other plans, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To ensure the long-term health of workers on site and occupants of the building is not put at risk unnecessarily)

#### **Commencement of Works' Notice**

- D11. Building work, demolition or excavation in accordance with this development consent must not be commenced until the developer has given at least two days' notice to North Sydney Council of the person's intention to commence building work, demolition or excavation in accordance with this development consent.
  - (Reason: To ensure appropriate safeguarding measures are in place prior to the commencement of any building work, demolition or excavation)

#### *E.* During Demolition and Building Work

#### **Reuse of Sandstone**

- E1. Sandstone blocks (if any) removed from the site are to be either stored for re-use on site or offered to Council in the first instance.
  - Note: The provisions of the Heritage Act may also apply to altering any sandstone elements on any site.
  - (Reason: To allow for preservation of cultural resources within the North Sydney Council area)

#### Parking Restrictions

- E2. Existing public parking provisions in the vicinity of the site must be maintained at all times during works. The placement of any barriers, traffic cones, obstructions or other device in the road shoulder or kerbside lane is prohibited without the prior written consent of Council. Changes to existing public parking facilities/restrictions must be approved by the North Sydney Local Traffic Committee. The Developer will be held responsible for any breaches of this condition and will incur any fines associated with enforcement by Council regulatory officers.
  - (Reason: To ensure that existing kerbside parking provisions are not compromised during works)

#### Road Reserve Safety

E3. All public footways and roadways fronting and adjacent to the site must be maintained in a safe condition at all times during the course of the development works, with no obstructions caused to the said footways and roadways. Construction materials and plant must not be stored in the road reserve without approval of Council. A safe pedestrian circulation route and a pavement/route free of trip hazards must be maintained at all times on or adjacent to any public access ways fronting the construction site.

Where public infrastructure is damaged, repair works must be carried out in when and as directed by Council officers (at full Developer cost). Where pedestrian circulation is diverted on to the roadway or verge areas, clear directional signage and protective barricades must be installed in accordance with AS1742-3 (1996) "Traffic Control Devices for Work on Roads". If pedestrian circulation is not satisfactorily maintained across the site frontage, and action is not taken promptly to rectify the defects, Council may undertake proceedings to stop work.

(Reason: Public Safety)

## Service Adjustments

- E4. Where required, the adjustment or inclusion of any new utility service facilities must be carried out by the person acting on the consent and in accordance with the requirements of the relevant utility authority. These works shall be at no cost to Council. It is the Applicants full responsibility to make contact with the relevant utility authorities to ascertain the impacts of the proposal upon utility services at the appropriate stage of the development (including water, phone, gas and the like). Council accepts no responsibility whatsoever for any matter arising from its approval of this application involving any influence upon utility services provided by another authority.
  - (Reason: To ensure the service requirements are met)

## **Temporary Disposal of Stormwater Runoff**

- E5. During construction, stormwater runoff must be disposed in a controlled manner that is compatible with the erosion and sediment controls on the site. Immediately upon completion of any impervious areas on the site (including roofs, driveways, paving) and where the final drainage system is incomplete, the necessary temporary drainage systems must be installed to reasonably manage and control runoff as far as the approved point of stormwater discharge. Such ongoing measures must be to the satisfaction of the Certifying Authority.
  - (Reason: Stormwater control during construction)

## Structural and Geotechnical Stability during Works

E6. A contractor with specialist excavation experience must undertake the excavations for the development and a suitably qualified and consulting geotechnical engineer must oversee the excavation procedure.

Geotechnical aspects of the development work, namely appropriate excavation method and vibration control, support and retention of excavated faces, and hydrogeological considerations must be undertaken in accordance with the recommendations of the reports prepared to satisfy **condition AA1** and all subsequent geotechnical inspections carried out during the excavation and construction phase.

Approval must be obtained from all affected property owners, including North Sydney Council where rock anchors (both temporary and permanent) are proposed below adjacent private or public property.

(Reason: Ensure appropriate professional are engaged at appropriate stages during construction)

#### **Council Inspection of Public Infrastructure Works**

- E7. During the works on public infrastructure reverting to Council's care and control, Council's development engineer may undertake inspections of the works at the following hold points:
  - a) Vehicular access; and associated road civil works
  - b) Stormwater connection to Council's system.

All works must proceed in accordance with Roads Act 1993 approvals or other permits relating to roads issued by Council. A minimum of 48 hours' notice must be given to Council to book an inspection. Work must not proceed until the works or activity covered by the inspection is approved.

(Reason: To ensure quality of construction joints and connections in the drainage system)

#### Progress Survey

- E8. In order to ensure compliance with approved plans, a Survey Certificate, prepared to Australian Height Datum, must be prepared by a Registered Surveyor showing the following:
  - a) at the completion of excavation, prior to the placement of any footings, showing the completed level of the excavation and its relationship to the boundaries;
  - b) prior to placement of concrete at the ground floor level, showing the level of the form work and its relationship to boundaries including relevant footpath and roadway levels;
  - c) prior to placement of concrete at each fifth-floor level showing the principal level of the formwork and the intended relationship of the completed works to the boundary;
  - d) prior to roofing, or completion of the highest point of the building showing the anticipated level of the completed work and it relationship to the boundary; and
  - e) at completion, works showing the relationship of the building to the boundary and showing the maximum height of the overall works and the height of the principal roof elements.

Progress certifications in response to points (a) through to (e) must be provided to the Certifying Authority for approval at the time of carrying out relevant progress inspections. In the event that such survey information is not provided or reveals discrepancies between the approved plans and the proposed works, all works, save for works necessary to bring the development into compliance with the approved plans, must cease. Works may only continue upon notification by the Certifying Authority to the Applicant that survey information (included updated survey information following the carrying out of works to comply with the approved plans) complies with this condition.

(Reason: To ensure compliance with approved plans)

#### **Removal of Extra Fabric**

E9. Should any portion of the existing building, trees, or curtilage of the site which is indicated on the approved plans to be retained be damaged for whatever reason, all the works in the area of the damaged portion are to cease and written notification of the damage is to be given to Council forthwith. No work is to resume until the written approval of Council to do so is obtained. Failure to comply with the provisions of this condition may result in the Council taking further action including legal proceedings if necessary.

(Reason: To ensure compliance with the terms of this development consent)

#### **Dust Emission and Air Quality**

- E10. The following must be complied with at all times:
  - (a) Materials must not be burnt on the site.
  - (b) Vehicles entering and leaving the site with soil or fill material must be covered.
  - (c) Dust suppression measures must be carried out to minimise wind-borne emissions in accordance with the NSW Department of Housing's 1998 guidelines Managing Urban Stormwater: Soils and Construction.
  - (d) Odour suppression measures must also be carried out where appropriate so as to prevent nuisance occurring at adjoining properties.
  - (Reason: To ensure residential amenity is maintained in the immediate vicinity)

#### Noise and Vibration

- E11. The works must be undertaken in accordance with the "Interim Construction Noise Guideline," published by the NSW Environment Protection Authority, to ensure excessive levels of noise and vibration do not occur so as to minimise adverse effects experienced on any adjoining land.
  - (Reason: To ensure residential amenity is maintained in the immediate vicinity)

#### Compliance with Construction Noise Management Plan

- E12. All works conducted on site which form part of this development must be carried out in accordance with the submitted Construction Noise Management Plan submitted with the Construction Certificate and all conditions of consent.
  - (Reason: To ensure noise generating activities are appropriately managed and nearby sensitive receivers protected)

#### No Work on Public Open Space

- E13. No work can be undertaken within adjoining public lands (i.e., Parks, Reserves, Roads etc) without the prior written consent of Council. In this regard the developer is to liaise with Council prior to the commencement of any design works or preparation of a Construction and Traffic Management Plan.
  - (Reason: Protection of existing public infrastructure and land and to ensure public safety and proper management of public land)

#### Applicant's Cost of Work on Council Property

E14. The applicant must bear the cost of all works associated with the development that occurs on Council's property, including the restoration of damaged areas.

(Reason: To ensure the proper management of public land and funds)

#### No Removal of Trees on Public Property

- E15. No trees on public property (footpaths, roads, reserves, etc.) unless specifically approved by this consent shall be removed or damaged during construction including for the erection of any fences, hoardings or other temporary works.
  - (Reason: Protection of existing environmental infrastructure and community assets)

#### **Protection of Trees**

E16. All trees required to be retained, as part of this consent must be protected from any damage during construction works in accordance with AS4970-2009. All recommendations contained within the tree report prepared by Blues Brothers, version 6, dated 17 April 2023 and as subsequently amended by conditions of this development consent must be implemented for the duration of the works.

In the event that any tree required to be retained is damaged during works on the site, notice of the damage must be given to Council forthwith.

Notes:

- a. If the nominated tree is damaged to a significant degree or removed from the site without prior written approval being obtained from Council, the issuing of fines or legal proceedings may be commenced for failure to comply with the conditions of this consent.
- b. An application to modify this consent pursuant to Section 4.55 of *the Environmental Planning and Assessment Act 1979* will be required to address the non-compliance with any of the conditions of consent relating to the retention of nominated trees, and Council may require tree replenishment.
- (Reason: Protection of existing environmental infrastructure and community assets)

## Benchmarks

E17. All permanent survey markers must be retained, undamaged, and not relocated.

(Reason: Protection of existing environmental infrastructure and community assets)

#### **Special Permits**

E18. Unless otherwise specifically approved in writing by Council, all works, processes, storage of materials, loading and unloading associated with the development must occur entirely on the property.

The developer, owner or builder may apply for specific permits available from Council's Customer Service Centre for the undermentioned activities on Council's property. In the event that a permit is granted by Council for the carrying out of works, processes, storage of materials, loading and unloading associated with the development on Council's property, the development must be carried out in accordance with the requirements of the permit. A minimum of forty-eight (48) hours' notice is required for any permit:

## 1) **On-street mobile plant**

E.g., cranes, concrete pumps, cherry-pickers, etc. - restrictions apply to the hours of operation, the area of operation, etc. Separate permits are required for each occasion and each piece of equipment. It is the developer's, owner's and builder's responsibilities to take whatever steps are necessary to ensure that the use of any equipment does not violate adjoining property owner's rights.

(Reason: Proper management of public land)

## 2) Hoardings

Permits are required to erect Class A and Class B hoardings. If an 'A' Class hoarding is to alienate a section of Council's property, that section will require a permit for the occupation of Council's property.

(Reason: Proper management of public land)

## 3) Storage of building materials and building waste containers (skips) on Council's property

Permits to utilise Council property for the storage of building materials and building waste containers (skips) are required for each location. Failure to obtain the relevant permits will result in the building materials or building waste containers (skips) being impounded by Council with no additional notice being given. Storage of building materials and waste containers on open space reserves and parks is prohibited.

(Reason: Proper management of public land)

## 4) Kerbside restrictions, construction zones

Attention is drawn to the existing kerbside restrictions adjacent to the development. Should alteration of existing kerbside restrictions be required, or the provision of a construction zone, the appropriate application must be made and the fee paid to Council. Alternatives to such restrictions may require referral to Council's Traffic Committee and may take considerable time to be resolved. An earlier application is suggested to avoid delays in construction programs.

(Reason: Proper management of public land)

## **Construction Hours**

E19. Construction activities and works approved under this consent must be carried out only within the hours stipulated in the following table:

Standard Construction Hours		
Location	Day	Hours
	Monday - Friday	7.00 am - 5.00 pm
Residential zones	Saturday	8.00 am - 1.00 pm
	Sunday, Public holiday	No work permitted

Construction activities for development approved under this consent must be carried out in accordance with the standard construction hours above and any Construction Noise Management Plan required under this consent.

In the event of breach to the approved hours of construction Council take may take enforcement action under Part 9 of the EP&A Act 1979 and in accordance with Council's adopted Compliance and Enforcement Policy.

(Reason: To ensure that works do not interfere with reasonable amenity expectations of residents and the community)

#### Installation and Maintenance of Sediment Control

E20. Erosion and sediment controls must be installed and maintained at all times in accordance with the Sediment and erosion control plan submitted and approved with the Construction Certificate.

Erosion and sediment measures must be maintained in accordance with the publication Managing Urban Stormwater: Soils and Construction (4th edition, Landcom, 2004), commonly referred to as the "Blue Book" and can only be removed when development activities have been completed and the site fully stabilised.

(Reason: To protect the environment from the effects of sedimentation and erosion from development sites)

#### Sediment and Erosion Control Signage

- E21. A durable sign must be erected during building works in a prominent location on site, warning of penalties should appropriate erosion and sedimentation control devices not be maintained. A sign of the type referred to in this condition is available from Council.
  - (Reason: To protect the environment from the effects of sedimentation and erosion from development sites)

#### **Site Amenities and Facilities**

E22. Where work involved in the erection and demolition of a building is being carried out, amenities which satisfy applicable occupational health and safety and construction safety regulations, including any WorkCover Authority requirements, must be provided and maintained at all times. The type of workplace determines the type of amenities required.

Further information and details can be obtained from the Internet at www.workcover.nsw.gov.au.

(Reason: To ensure the health and safety of the community and workers on the site)

## Health and Safety

E23. All work undertaken must satisfy applicable occupational health and safety and construction safety regulations, including any WorkCover Authority requirements to prepare a health and safety plan. Site fencing must be installed sufficient to exclude the public from the site. Safety signs must be erected that warn the public to keep out of the site and provide a contact telephone number for enquiries.

Further information and details regarding occupational health and safety requirements for construction sites can be obtained from the internet at <u>www.workcover.nsw.gov.au</u>.

(Reason: To ensure the health and safety of the community and workers on the site)

#### **Community Information**

- E24. Reasonable measures must be undertaken at all times to keep nearby residents informed about the proposed work, such as by way of signs, leaflets, public meetings and telephone contact numbers, to ensure that adjoining residents are aware of the likely duration of the construction works on the site.
  - (Reason: To ensure that residents are kept informed of activities that may affect their amenity)

#### Prohibition on Use of Pavements

- E25. Building materials must not be placed on Council's footpaths, roadways, parks or grass verges, (unless a permit is obtained from Council beforehand). A suitable sign to this effect must be erected adjacent to the street alignment.
  - (Reason: To ensure public safety and amenity on public land)

#### Plant and Equipment Kept Within Site

E26. All plant and equipment used in the undertaking of the development/ works, including concrete pumps, wagons, lifts, mobile cranes, hoardings etc, must be situated within the boundaries of the site (unless a permit is obtained from Council beforehand) and so placed that all concrete slurry, water, debris and the like must be discharged onto the building site, and is to be contained within the site boundaries.

Details of Council requirements for permits on public land for standing plant, hoardings, storage of materials and construction zones and the like are available on Council's website at <u>www.northsydney.nsw.gov.au</u>.

(Reason: To ensure public safety and amenity on public land)

## Waste Disposal

- E27. All records demonstrating the lawful disposal of waste must be retained and kept readily accessible for inspection by regulatory authorities such as North Sydney Council and the Environmental Protection Authority.
  - (Reason: To ensure the lawful disposal of construction and demolition waste)

#### Asbestos Removal

- E28. All demolition works involving the removal and disposal of asbestos cement must only be undertaken by contractors who hold a current WorkCover Asbestos or "Demolition Licence" and a current WorkCover "Class 2 (Restricted) Asbestos Licence and removal must be carried out in accordance with National Occupational Health and Safety Commission.
  - (Reason: To ensure works are carried out in accordance with relevant WorkCover requirements)

## F. Prescribed Conditions imposed under EP&A Act and Regulations and other relevant Legislation

## National Construction Code

- F1. All building work must be carried out in accordance with the provisions of the National Construction Code.
  - (Reason: Prescribed Statutory)

#### **Home Building Act**

- F2. 1) Building work that involves residential building work (within the meaning and exemptions provided in the Home Building Act 1989) for which the *Home Building Act* 1989 requires there to be a contract of insurance under Part 6 of that Act must not be carried out unless the Principal Certifying Authority for the development to which the work relates has given North Sydney Council written notice of the contract of insurance being issued and of the following:
  - a) in the case of work for which a principal contractor is required to be appointed:
    - i) the name and licence number of the principal contractor, and
    - ii) the name of the insurer by which the work is insured under Part 6 of that Act, or
  - (b) in the case of work to be done by an owner-builder:
    - (i) the name of the owner-builder, and
    - (ii) if the owner-builder is required to hold an owner-builder permit under that Act, the number of the owner-builder permit.

- 2) If arrangements for doing residential building work are changed while the work is in progress such that the information submitted to Council in accordance with this conditions is out of date, work must cease and no further work may be carried out unless the Principal Certifying Authority for the development to which the work relates (not being the Council), has given the Council written notice of the updated information.
- Note: A certificate purporting to be issued by an approved insurer under Part 6 of the Home Building Act 1989 that states that a person is the holder of an insurance policy issued for the purposes of that Part is, for the purposes of this clause, sufficient evidence that the person has complied with the requirements of that Part.

(Reason: Prescribed - Statutory)

## Appointment of a Principal Certifying Authority (PCA)

- F3. Building work, demolition or excavation in accordance with the development consent must not be commenced until the developer has appointed a Principal Certifying Authority for the building work in accordance with the provisions of the EP&A Act and its Regulations.
  - (Reason: Statutory: To ensure appropriate safeguarding measures are in place prior to the commencement of any building work, demolition or excavation)

#### **Construction Certificate**

- F4. Building work, demolition or excavation in accordance with the development consent must not be commenced until a Construction Certificate for the relevant part of the building work has been issued in accordance with the provisions of the EP&A Act and its Regulations.
  - (Reason: Statutory: To ensure appropriate safeguarding measures are in place prior to the commencement of any building work, demolition or excavation)

#### **Occupation Certificate**

F5. A person must not commence occupation or use of the whole or any part of a new building (*new building* includes an altered portion of, or an extension to, an existing building) unless an Occupation Certificate has been issued in relation to the building or part. Only the Principal Certifying Authority appointed for the building work can issue an Occupation Certificate.

(Reason: Statutory)

## Mandatory Critical Stage Inspections

F6. Building work must be inspected by the Principal Certifying Authority on the critical stage occasions prescribed by the EP&A Act and its Regulations, and as directed by the appointed Principal Certifying Authority.

(Reason: Statutory)

#### Page **55** of **64**

## Excavation/Demolition

- F7. 1) All excavations and backfilling associated with the erection or demolition of a building must be executed safely and in accordance with appropriate professional standards.
  - 2) All excavations associated with the erection or demolition of a building must be properly guarded and protected to prevent them from being dangerous to life or property.
  - 3) Demolition work must be undertaken in accordance with the provisions of AS2601-Demolition of Structures.
  - (Reason: To ensure that work is undertaken in a professional and responsible manner and protect adjoining property and persons from potential damage)

#### **Protection of Public Places**

- F8. 1) A hoarding and site fencing must be erected between the work site and adjoining public place.
  - 2) If necessary, an awning is to be erected, sufficient to prevent any substance from, or in connection with, the work falling into the public place.
  - 3) The work site must be kept lit between sunset and sunrise if it is likely to be hazardous to persons in the public place.
  - 4) Any such hoarding, fence or awning is to be removed when the work has been completed.
  - 5) No access across public reserves or parks is permitted.
  - Note: Prior to the erection of any temporary fence or hoarding over property owned or managed by Council, written approval must be obtained. Any application needs to be accompanied by plans indicating the type of hoarding and its layout. Fees are assessed and will form part of any approval given. These fees must be paid prior to the approval being given. Approval for hoardings will generally only be given in association with approved building works, maintenance or to ensure protection of the public. An application form for a Hoarding Permit can be downloaded from Council's website.
  - (Reason: To ensure public safety and the proper management of public land)

#### Site Sign

- F9. 1) A sign must be erected in a prominent position on the site
  - a) stating that unauthorised entry to the work site is prohibited;
  - b) showing the name of the principal contractor (or person in charge of the work site), and a telephone number at which that person may be contacted at any time for business purposes and outside working hours; and

- c) showing the name, address and telephone number of the Principal Certifying Authority for the work.
- 2) Any such sign must be maintained while to building work or demolition work is being carried out but must be removed when the work has been completed.

(Reason: Prescribed - Statutory)

## G. Prior to the Issue of an Occupation Certificate

#### Infrastructure Repair and Completion of Works

- G1. Prior to the issue of any Occupation Certificate any and all works relating to the development:
  - a. in the road reserve must be fully completed; and
  - b. to repair and make good any damaged public infrastructure caused as a result of any works relating to the development (including damage caused by, but not limited to, delivery vehicles, waste collection, contractors, sub-contractors, concrete vehicles) must be fully repaired;

to the satisfaction of Council Engineers at no cost to Council.

(Reason: Maintain quality of public assets)

#### Line Marking

- G2. A certificate prepared by an appropriately qualified and practising Civil Engineer certifying the construction, paving, line marking and signposting of 19 off-street carparking spaces, together with access driveways, in accordance with the approved development plans, appropriate Australian Standards and industry best practice as appropriate must be submitted to, and approved by, the Certifying Authority prior to issue of any Occupation Certificate.
  - (Reason: To ensure ongoing compliance with this development consent and Australian Standards relating to manoeuvring and access of vehicles)

#### Noise Certification

G3. Prior to issue of the any Occupation Certificate a certificate from an appropriately qualified acoustical consultant eligible for membership of the Association of Australian Acoustic Consultants is to be submitted to, and approved by, the Certifying Authority certifying that the noise and vibration from use of the development complies with the conditions of consent herein.

(Reason: To ensure acoustic amenity)

## **Certification - Civil Works**

- G4. a) An appropriately qualified and practising Civil Engineer must certify to the Certifying Authority that the stormwater drainage system is constructed in accordance with this consent and the provisions of the applicable Australian Standard. A copy of the certificate must be submitted to Council (if it is not the Certifying Authority) upon completion of the development works and prior to the issue of an Occupation Certificate.
  - b) An appropriately qualified and practicing Civil Engineer must certify to the Certifying Authority that the vehicular crossing and associated works and road works were constructed in accordance with this consent and any approval for works in the road reserve issued by the Council. A copy of the certificate must be submitted to Council (if it is not the Certifying Authority), upon completion of the development works and prior to the issue of an Occupation Certificate.
  - (Reason: Compliance with the Consent)

## Works as Executed Drawings and Video

G5. A works-as-executed survey drawing (W.A.E.) of the completed stormwater drainage system must be obtained. The W.A.E. survey drawing must show the alignment, depth and grade of the stormwater drainage pipelines, pits and ancillary plumbing. The W.A.E. survey drawing must be reviewed by a qualified and practising civil engineer and certification provided to the Certifying Authority that the as-built system achieves the design intent of the plans approved with the Construction Certificate. Certification must be provided with the W.A.E. survey drawing to the Certifying Authority prior to the issue of an Occupation Certificate.

A copy of the W.A.E. survey drawing and certification must be submitted to the Council if it is not the Certifying Authority.

(Reason: Compliance with the Consent)

#### **Certification for Mechanical Exhaust Ventilation**

- G6. Prior to issue of an Occupation Certificate and following the completion, installation, and testing of all the mechanical ventilation systems, a Mechanical Ventilation Certificate of Completion and Performance in accordance with Clause A2.2(a)(iii) of the Building Code of Australia, must be submitted to, and approved by, the Certifying Authority.
  - (Reason: To ensure compliance with acceptable standards for the construction and operation of mechanical plant)

#### **Utility Services**

G7. All utility services shall be adjusted to the correct levels and/or location/s required by this consent, prior to issue of an occupation certificate. This shall be at no cost to Council.

(Reason: To ensure compliance with the terms of this consent)

#### **Basement Pump-out Maintenance**

G8. Prior to issue of an Occupation Certificate a Maintenance Regime must be prepared for the basement stormwater pump-out system and submitted to the Principal Certifying Authority for approval with the Occupation Certificate documentation. The regime must specify that the system is to be regularly inspected and checked by qualified practitioners.

The basement stormwater pump-out system must be maintained in accordance with the approved Maintenance Regime at all times.

(Reason: To ensure future provision for maintenance of the drainage system)

## Notification of New Address Developments

- G9. Prior to any Occupation Certificate being issued, the person acting upon this consent must comply with the following:
  - (a) Notify Australia Post of the address(es) as issued by Council and the location in plan form of any secondary, internal addresses, in relation to built public roads. Check Australia Post Website (<u>www.auspost.com.au</u>) to find your nearest Australia Post Delivery Facility.
  - (Reason: To ensure that Council records are accurate, and that house numbering complies with the requirements of Council's House Numbering Policy. Proper house numbering also assists emergency services in readily locating properties)

#### **Asbestos Clearance Certificate**

- G10. For building works where asbestos based products have been removed or altered, an asbestos clearance certificate signed by an appropriately qualified person (being an Occupational Hygienist or Environmental Consultant) must be submitted to and approved by the Certifying Authority (and a copy forwarded to Council if it is not the Certifying Authority) for the building work prior to the issue of any Occupation Certificate, the asbestos clearance certificate must certify the following:
  - a) the building/land is free of asbestos; or
  - b) the building/land has asbestos that is presently deemed safe.

The certificate must also be accompanied by tipping receipts, which detail that all asbestos waste has been disposed of at an approved asbestos waste disposal depot. If asbestos is retained on site the certificate must identify the type, location, use, condition and amount of such material.

- Note: Further details of licensed asbestos waste disposal facilities can be obtained from <u>www.epa.nsw.gov.au</u>.
- (Reason: To ensure that building works involving asbestos-based products are safe for occupation and will pose no health risks to occupants)

#### Page **59** of **64**

## **Certification of Tree Condition**

G11. Prior to the issue of an Occupation Certificate, a report prepared by an appropriately qualified person (being an arborist or the like) must be submitted to the Certifying Authority, describing the health of the tree(s) specifically nominated below:

Tree	Location	Height
4 x Photinia sp.	Council verge in front of No. 13-15 Allister Street	4-5m
3 x (new) Photinia sp.	Council verge in front of No. 13-15 Allister St	751
T4 Angophra costata	Southeastern corner of the site	11x8m
T8 Gordonia axillaris	Northwestern corner of the site	7x6m
1 x (new) Jacaranda mimosifolia	Northeastern corner of the site	4001
3 x (new) Corymbia maculata	Southwestern corner of the site	100
2 x (new) Acer x freemanii 'Jeffersred'	Front setback area of the site	2001

The report must detail the condition and health of the nominated tree(s) upon completion of the works and shall certify that the tree(s) has/have not been significantly damaged during the works on the site and has/have reasonable prospects for survival.

(Reason: To ensure compliance with the terms of this consent)

#### Signal System

G12. Prior to the issue of an Occupation Certificate, a signal system must be installed at the street alignment and within the building to indicate traffic movement on the single lane ramp, and so designed that the signal indication at the point of ingress shall remain green except when an exiting vehicle is detected upon the ramp or driveway.

(Reason: To properly manage vehicle entry to, and exit from, the subject site)

#### **Disposal Information**

- G13. Upon completion of works and prior to occupation, a report including the following information must be provided to Council's Open Space and Environmental Services Department:
  - (a) the total tonnage of all waste and excavated material disposed of from the site (including any tipping dockets); and
  - (b) the disposal points and methods used.
    - (Reason: To ensure appropriate disposal methods are undertaken for auditing and inspection purposes)

#### Sydney Water

G14. A Section 73 Compliance Certificate under the Sydney Water Act 1994 must be obtained.

The final Section 73 Certificate must be submitted to the Certifying Authority prior to release of any linen plan for subdivision or prior to occupation of the development, whichever is the earlier.

Notes: Application must be made through an authorised Water Servicing Co-ordinator, for details see the Sydney Water web site <u>www.sydneywater.com.au\customer\urban\index</u>, or telephone 13 20 92.

Following application, a 'Notice of Requirements' will be forwarded detailing water and sewer extensions to be built and charges to be paid. Please make early contact with the Coordinator since building of water/sewer extensions can be time consuming and may impact on other services and building, driveway or landscape design.

(Reason: To ensure compliance with the statutory requirements of Sydney Water)

## **BASIX Completion Certificate**

G15. In accordance with Section 45 of the Environmental Planning and Assessment (Development Certification and Fire Safety) Regulation 2021, prior to issuing a final occupation certificate, the Principal Certifier must provide a BASIX completion receipt.

(Reason: To ensure compliance with the Regulations)

## House Numbering (Dwellings)

- G16. Prior to any Occupation Certificate being issued an application must be made to North Sydney Council for written confirmation, or allocation, of the street address(es) or apartment number(s) for the completed project in accordance with Council's Property Addressing Policy. These are the numbers that will be recorded in Council records and must be displayed at the property in accordance with the provisions of AS/NZS 4819:2011.
  - Note: If apartments are to be sold off the plan, the applicant must have written confirmation from Council of the address and apartment numbering if the apartment number is to be identified on the contract.
  - (Reason: To ensure that Council records are accurate, and that house numbering complies with the requirements of Council's House Numbering Policy. Proper house numbering also assists emergency services in readily locating properties.)

#### Landscaping

G17. The landscaping shown in the approved landscape plans 1 and 2/2 prepared by Andrew Davies, dated 24 January 2023, as modified by Condition C53.

(Reason: To ensure compliance)

#### Damage to Adjoining Properties

G18. On completion of the development the subject of this consent and prior to the issue of the Occupation Certificate, a report is to be prepared by an appropriately qualified consultant and is to be provided to the Certifying Authority (and a copy to Council if it is not the Certifying Authority) certifying:

- a) whether any damage to adjoining properties has occurred as a result of the development;
- b) the nature and extent of any damage caused to the adjoining property as a result of the development;
- c) the nature and extent of works required to rectify any damage caused to the adjoining property as a result of the proposed development;
- d) the nature and extent of works carried out to rectify any damage caused to the adjoining property as a result of the development; and
- e) the nature and extent of any agreements entered into for rectification of any damage caused to the adjoining property as a result of the development.

The report and certification must reference the dilapidation survey and reports required to be provided to the Certifying Authority in accordance with this consent.

Where works required to rectify any damage caused to adjoining property as a result of the development identified in the report and certification have not been carried out, a satisfactory agreement for rectification of the damage is to be made with the affected person/s as soon as possible prior to the issue of an Occupation Certificate.

All costs incurred in achieving compliance with this condition shall be borne by the developer.

(Reason: To ensure adjoining owner's property rights are protected in so far as possible)

## Verification Statement (External Finishes and Materials)

G19. Prior to the issue of any Occupation Certificate, a verification statement from a qualified designer or architect (preferably the original designer), must be submitted to Council and the Certifying Authority certifying that the external finishes and materials are in accordance with the approved schedule of finishes and materials identified in this consent.

"qualified designer" means a person registered as an architect in accordance with the Architects Act 2003 cf 50(1A) EP&A Regs 2000.

(Reason: To ensure the design quality and finishes for residential flat development)

#### **Required Tree Planting**

G20. On completion of works and prior to the issue of an Occupation Certificate trees in accordance with the schedule hereunder must be planted in Council's nature strip/footpath:

#### Schedule

Tree	Location	Height
3 x (new) Photinia sp.	Council verge in front of No. 13-15 Allister St	751

The installation of such trees, their current health and their prospects for future survival must be certified upon completion by an appropriately qualified horticulturalist.

Upon completion of installation and prior to the issue of an Occupation Certificate an appropriately qualified horticulturalist must certify that any trees planted in accordance with this condition are healthy and have good prospects of future survival. The certification must be submitted with any application for an Occupation Certificate.

(Reason: To ensure that replacement plantings are provided to enhance community landscaped amenity and cultural assets)

#### **Unpaved Verge**

- G21. The unpaved verge area must be constructed/reconstructed with an appropriate species of grass prior to completion of the works at no cost to Council.
  - (Reason: To ensure that community assets are presented in accordance with reasonable community expectations)

#### Intercom

G22. An intercom system must be provided in a convenient location adjacent to the visitor parking entry to enable easier and safe access to visitor parking prior to issue of any occupation Certificate.

(Reason: To ensure convenient access is available for visitors to the building)

#### Allocation of Spaces

G23. Car parking spaces must be provided and maintained at all times on the subject site. The spaces shall be allocated to uses within the building in accordance the following table:

Residential	Parking Spaces
One Bedroom Apartments (1 space per apartment)	3
Two Bedroom Apartments (1 space per apartment)	4
Three Bedroom Apartments (Including 3 Accessible Parking Spaces) (1	9
or 2 spaces per apartment)	
Visitor	3
Total	19

The car parking spaces are to be identified on-site by line-marking and numbering upon the completion of the works and prior to issue of Occupation Certificate. Car parking spaces provided must only be used in conjunction with the approved uses contained within the development.

In the case of Strata subdivision any car parking for strata lots for residential purposes must be individually allocated to its corresponding residential strata lot as part of each lots' unit entitlement.

Visitor parking facilities must be designated as common property on the strata plan. Visitor parking facilities must not at any time be allocated, sold, licensed or leased for the exclusive use of any occupier or owner and must be retained as common property by the Owners Corporation for use by building visitors.

(Reason: To ensure that adequate parking facilities to service the development are provided on site)

#### **Compliance with Certain Conditions**

- G24. Prior to the issue of any Occupation Certificate, Conditions C1 Heritage and C46 Screen Planting must be certified as having been implemented on site and complied with.
  - (Reason: To ensure the development is completed in accordance with the requirements of this consent)

## **Covenant and Restriction (Use of Communal Areas)**

- G25. An Instrument pursuant to Sections 88B and 88E of the Conveyancing Act 1919 and one copy must be submitted to Council in registrable form, providing for:
  - a restriction as to user and positive covenant in favour of North Sydney Council burdening Nos. 13-15 Allister Street, Cremorne, restricting the use of the communal areas for residents and guest to be maintained as such and shall only be varied with approval of Council; and
  - 2) North Sydney Council being nominated in the Instrument as the only party authorised to release, vary or modify the Instrument.

Upon Council being satisfied as to the terms of the Instrument, North Sydney Council's official seal will be affixed to these documents, prior to submission to the Land & Property Information Office for registration.

The Instrument creating the restriction and/or covenant under ss 88B and 88E required by this condition of consent must be registered on the Title of the development site prior to the issue of an Occupation Certificate or commencement of use of the site, whichever is the earlier.

Evidence of the registration of the instrument referred to in this condition is to be provided to Council prior to the issue of an Occupation Certificate.

All costs associated with the preparation, approval and registration of the Instrument required by this condition of consent must be borne by the person acting on this consent including the reasonable costs of Council in obtaining advice, negotiating the terms or otherwise facilitating the execution and registration of the required Instrument.

(Reason: Compliance and maintain communal use of the communal area)

## I. Ongoing/Operational Conditions

#### Maintenance of Approved Landscaping

11. The owner of the premises at 13-15 Allister Street is to maintain the landscaping approved by this consent generally in accordance with Landscape Plans 1 and 2/2 prepared by Andrew Davies, dated 24 January 2023, as modified by Condition C52.

Any replacement plants required shall be advanced in growth and be selected to maintain the anticipated mature height, canopy density and nature of those plant species as originally approved.

(Reason: To ensure maintenance of the amenity of the site)