

### NORTH SYDNEY COUNCIL

200 Miller Street, North Sydney, NSW 2060 | ABN 32 353 260 317 All correspondence PO Box 12, North Sydney, NSW 2059 P (02) 9936 8100 | E council@northsydney.nsw.gov.au W www.northsydney.nsw.gov.au

Kaisey Lea Hulsboch C/- Clare Carter, Contemporary Architecture Suite 203/10-12 Clarke Street CROWS NEST NSW 2065

> D4/23 AB7 (CIS)

#### ENVIRONMENTAL PLANNING AND ASSESSMENT ACT, 1979 AS AMENDED NOTICE OF DETERMINATION - Approval

Development Application Number:	4/23
Land to which this applies:	16A Benelong Road, Cremorne Lot No.: B, DP: 449837
Applicant:	Kaisey Lea Hulsboch C/- Contemporary Architecture
Proposal:	Alterations and additions to dwelling house.
Determination of Development Application:	Subject to the provisions of Section 4.17 of <i>the Environmental Planning and Assessment Act 1979</i> , approval has been granted subject to conditions in the notice of determination.
Date of Determination:	28 September 2023
Reasons for Approval	The development application has been assessed against the relevant planning instruments and policies, in particular the <i>North Sydney Local Environmental Plan 2013</i> and the North Sydney Development Control Plan 2013, and generally found to be satisfactory. There would be no unreasonable overshadowing, view loss, privacy loss and/or excessive bulk and scale as a result of the proposal given that the majority of the works are not highly visible from the public domain, and are compliant with Council's height, setbacks and bulk and scale controls. The overall development is considered to be generally sympathetic with the existing building on the site and nearby development within the Benelong Neighbourhood, while also ensuring that an appropriate landscaped context for the site is maintained and is visible from the streetscape. As a result, the overall proposed works will provide additional residential amenity without significantly impacting upon adjoining dwellings or the character of the neighbourhood.

	The application is considered to be acceptable in the circumstances and it is recommended for <b>approval</b> subject to standard and site-specific conditions.
Consent to operate from:	5 October 2023
Consent will lapse on:	5 October 2028
Period of Consent	Subject to Section 4.20 of the Act, this consent becomes effective and operates from the date listed above. The consent lapses five years after the date of consent in accordance with Section 4.53 of the Act and cannot be extended. To activate this consent, works must physically commence onsite 5 October 2028.
How community views were taken into account:	The subject application was notified to surrounding properties and the Brightmore Precinct Committee seeking comment and two submissions were received raising various concerns. Nevertheless, it is considered that the proposal will not have any significant impact upon the general amenity of adjoining properties or the neighbourhood, subject to appropriate conditions of consent to maintain residential amenity and an appropriate landscaped context for the site.
Review of determination and right of appeal:	Within six months after the date of notification of the decision, a review of this determination can be requested under Division 8.2 of the Act or an appeal to the Land and Environment Court made pursuant to the provisions of Section 8.7 of the Act. A review of determination should be lodged as soon as possible, and preferably no later two months after the date of notification of the decision to enable the review to be completed within the six-month period.

Plans endorsed by the consent authority - please refer to condition A1.

Endorsed for and on behalf of North Sydney Council

5 October 2023

DATE

Signature on behalf of consent authority ISOBELLA LUCIC TEAM LEADER ASSESSMENTS

#### (i) Conditions

Consent is granted subject to the following conditions imposed pursuant to Section 4.17 of the *Environmental Planning and Assessment Act 1979* ("the *Act*") and the provisions of the *Environmental Planning and Assessment Regulation 2021* ("the *Regulation*") such conditions being reasonable and relevant to the development as assessed pursuant to Section 4.17 of the Act.

#### (ii) Definitions

Unless specified otherwise, words have the same meaning as defined by the *Act*, the *Regulation* and the *Interpretation Act 1987* as in force at the date of consent.

Applicant means the applicant for this consent.

*Approved Plans* means the plans endorsed by Council referenced by this consent as amended by conditions of this consent.

**AS** or **AS/NZS** means Australian Standard<sup>®</sup> or Australian/New Zealand Standard<sup>®</sup>, respectively, published by Standards Australia International Limited.

**NCC** means the National Construction Code as published by the Australian Building Codes Board as in force at the date of issue of any *Construction Certificate*.

*Council* means North Sydney Council.

*Court* means the Land and Environment Court.

Local Native Plants means species of native plant endemic to North Sydney LGA.

*Stormwater Drainage System* means all works, facilities and documentation relating to:

- The collection of stormwater,
- The retention of stormwater,
- The reuse of stormwater,
- The detention of stormwater,
- The controlled release of stormwater; and
- Connections to easements and public stormwater systems.

*Owner* means the owner of the *site* and successors in title to the *site*.

*Owner Builder* has the same meaning as in the *Home Building Act* 1989.

**Principal Certifier** for building or subdivision work means the certifier appointed as the principal certifier for the building work under section 6.6 (1) or for the subdivision work under section 6.12 (1). **Principal Contractor** for building work means the person responsible for the overall coordination and control of the carrying out of the building work.

Note: If any residential building work is involved, the principal contractor must be the holder of a contractor licence under the *Home Building Act 1989*.

Professional Engineer has the same meaning as in the NCC.

Public Place has the same meaning as in the Local Government Act 1993.

Road has the same meaning as in the Roads Act 1993.

SEE means the final version of the Statement of Environmental Effects lodged by the Applicant.

*Site* means the land being developed subject to this consent.

**NSLEP 2013** means North Sydney Local Environmental Plan 2013

NSDCP 2013 means North Sydney Development Control Plan 2013

*Work* for the purposes of this consent means:

- the use of land in connection with development,
- the subdivision of land,
- the erection of a building,
- the carrying out of any work,
- the use of any site crane, machine, article, material, or thing,
- the storage of any waste, materials, site crane, machine, article, material, or thing,
- the demolition of a building,
- the piling, piercing, cutting, boring, drilling, rock breaking, rock sawing or excavation of land,
- the delivery to or removal from the site of any machine, article, material, or thing, or
- the occupation of the site by any person unless authorised by an occupation certificate.
- Note: **Interpretation of Conditions** Where there is any need to obtain an interpretation of the intent of any condition this must be done in writing to Council and confirmed in writing by Council.

# RE: 16A BENELONG ROAD, CREMORNE DEVELOPMENT CONSENT NO. 4/23

	NDEX OF CONDITIONS	
А.	Conditions that Identify Approved Plans	Page No.
A1.	Development in Accordance with Plans/Documentation	7
A1. A2.	Plans on Site	7
A3.	No Demolition of Extra Fabric	7
A3. A4.	External Finishes and Materials	8
С.	Prior to the Issue of a Construction Certificate (and ongoing, where indicated)	
C1.	Dilapidation Report Damage to Public Infrastructure	8
C2.	Dilapidation Report Private Property (Excavation)	8
C3.	Structural Adequacy of Existing Building	9
C4.	Structural Adequacy of Adjoining Properties – Excavation Works	9
C5.	Waste Management Plan	10
C6.	Sediment Control	10
C7.	External Colours and Finishes	10
C8.	Work Zone	11
C9.	Obtain Driveway Crossing Permit under S.138 Roads Act 1993	11
C10.	Porous Paving	12
C11.	Bond for Damage and Completion of Infrastructure Works - Stormwater,	
	Kerb and Gutter, Footpaths, Vehicular Crossing and Road Pavement	13
C12.	Arborist to be Commissioned	14
C13.	Tree Bond for Public Trees	14
C14.	Tree Protection Measures	15
C15.	Protection of Trees	15
C16.	Approval for Removal of Trees	16
C17.	Garbage and Recycling Facilities	16
C18.	Asbestos Material Survey	16
C19.	Air Conditioners in Residential Premises	17
C20.	Section 7.12 Development Contributions	17
C21.	Security Deposit/Guarantee and Fee Schedule	18
C22.	BASIX Certificate	18
C23.	Landscape Amendments	19
C24.	Root Mapping	19
D.	Prior to the Commencement of any Works (and continuing where indicated)	
D1.	Protection of Public Trees	19
D2.	Protection of Trees	20
D3.	Project Arborist Engaged	20
D4.	Temporary Fences and Tree Protection	21
D5.	Public Liability Insurance - Works on Public Land	21
D6.	Commencement of Works' Notice	21
Е.	During Demolition and Building Work	
E1.	Parking Restrictions	22
E2.	Road Reserve Safety	22
E3.	Temporary Disposal of Stormwater Runoff	22
E4.	Service Adjustments	22

## RE: 16A BENELONG ROAD, CREMORNE DEVELOPMENT CONSENT NO. 4/23

E5.	Council Inspection of Public Infrastructure Works	23
E6.	Removal of Extra Fabric	23
E7.	Dust Emission and Air Quality	23
E8.	Noise and Vibration	23
E9.	Developer's Cost of Work on Council Property	24
E10.	No Removal of Trees on Public Property	24
E11.	Protection of Tree	24
E12.	Trees to be Removed	24
E13.	Special Permits	24
E14.	Construction Hours	25
E15.	Installation and Maintenance of Sediment Control	26
E16.	Sediment and Erosion Control Signage	26
E17.	Site Amenities and Facilities	26
E18.	Health and Safety	27
E19.	Archaeological discovery during works	27
E20.	Prohibition on Use of Pavements	27
E21.	Plant and Equipment Kept Within Site	27
E22.	Waste Disposal	27
E23.	Asbestos Removal	28

#### F. Prescribed Conditions imposed under EP&A Act and Regulations and other relevant Legislation

F1.	National Construction Code	28
F2.	Home Building Act	28
F3.	Appointment of a Principal Certifying Authority (PCA)	29
F4.	Construction Certificate	29
F5.	Occupation Certificate	29
F6.	Excavation/Demolition	29
F7.	Protection of Public Places	29
F8.	Site Sign	30

#### G. Prior to the Issue of an Occupation Certificate

G1.	Infrastructure Repair and Completion of Works	30
G2.	Certification – Civil Works	31
G3.	Damage to Adjoining Properties	31
G4.	Utility Services	31
G5.	Asbestos Clearance Certificate	31
G6.	Certification of Tree Condition	31
G7.	BASIX Completion Receipt	32
G8.	Landscaping	32
G9.	Unpaved Verge	32
G10.	Compliance with Certain Conditions	32
Ι.	Ongoing/Operational Conditions	

11.	Single Occupancy	33
12.	Maintenance of Approved Landscaping	33

#### A. Conditions that Identify Approved Plans

#### **Development in Accordance with Plans/Documentation**

A1. The development must be carried out in accordance with the following drawings endorsed with Council's approval stamp and other documentation listed in the table to this clause, or cited by other conditions, and as amended by other conditions of this consent.

Plan	Revision	Title	Drawn by	Dated	Received
No.					
DA01	D	Cover & Site Plan	Contemporary Architecture	05/09/2023	06/09/2023
DA07	E	Basement	Contemporary Architecture	05/09/2023	06/09/2023
DA08	С	Ground Floor – Part 1	Contemporary Architecture	05/05/2023	08/05/2023
DA09	D	Ground Floor – Part 2	Contemporary Architecture	05/09/2023	06/09/2023
DA10	С	Level 1 Plan	Contemporary Architecture	05/05/2023	08/05/2023
DA11	С	Roof Plan	Contemporary Architecture	05/05/2023	08/05/2023
DA12	С	Elevation 1, 3 & Street	Contemporary Architecture	05/05/2023	08/05/2023
		Elevation 1 & 2			
DA13	С	Elevation 2	Contemporary Architecture	05/05/2023	08/05/2023
DA14	С	Elevation 4	Contemporary Architecture	05/05/2023	08/05/2023
DA15	С	Section A	Contemporary Architecture	05/05/2023	08/05/2023
DA16	С	Section B	Contemporary Architecture	05/05/2023	08/05/2023
DA17	D	Section C	Contemporary Architecture	05/09/2023	06/09/2023
DA18	С	Section D, E & F	Contemporary Architecture	05/05/2023	08/05/2023
FS01	С	Finishes Schedule	Contemporary Architecture	19/12/2022	04/01/2023
101	В	Master Landscape Plan	Jamie King Landscape Architect	05/05/2023	08/05/2023
102	В	Detail Plan	Jamie King Landscape Architect	05/05/2023	08/05/2023
103	В	Planting Plan	Jamie King Landscape Architect	05/05/2023	08/05/2023

(Reason: To ensure that the form of the development undertaken is in accordance with the determination of Council, Public Information)

#### Plans on Site

A2. A copy of all plans endorsed with Council's approval stamp, specifications and documents (including the plans, specifications and documents submitted and approved with the Construction Certificate) must be kept on site at all times so as to be readily available for perusal by any officer of Council or the Principal Certifier.

All documents kept on site in accordance with this condition must be provided to any officer of the Council or the Principal Certifier upon their request.

(Reason: To ensure that the form of the development undertaken is in accordance with the determination of Council, Public Information and to ensure ongoing compliance)

#### No Demolition of Extra Fabric

A3. Alterations to, and demolition of the existing building shall be limited to that documented on the approved plans.

(Reason: To ensure compliance with the approved development)

#### **External Finishes and Materials**

- A4. The submitted Finishes Schedule numbered FS01, dated 19 December 2022, prepared by Contemporary Architecture, and received by Council on 4 January 2023, must be amended and updated as follows:
  - a) to reflect the amendments to the driveway materials made in the architectural plans (Numbered DA01 revision D, DA07 revision E, and DA17 revision D) prepared by Contemporary Architecture, dated 5 September 2023, and received by Council on 6 September 2023.
  - b) The colours for the approved additions shall be sympathetic to the nearby reserve and bushland areas, using muted colours. Vivid or bright colours, or very dark tones, shall not be used.

External finishes and materials must be in accordance with the above schedule (as modified), unless otherwise modified by Council in writing.

(Reason: To ensure that the form of the development undertaken is in accordance with the determination of Council, Public Information)

#### C. Prior to the Issue of a Construction Certificate (and ongoing, where indicated)

#### **Dilapidation Report Damage to Public Infrastructure**

C1. A dilapidation survey and report (including photographic record) must be prepared by a suitably qualified consultant which details the pre-developed condition of the existing public infrastructure in the vicinity of the development site. Particular attention must be paid to accurately recording any pre-developed damaged areas so that Council is fully informed when assessing any damage to public infrastructure caused as a result of the development. A copy of the dilapidation survey and report is to be submitted to the Principal Certifier for approval prior to the issue of any Construction Certificate.

The developer may be held liable for all damage to public infrastructure in the vicinity of the site, where such damage is not accurately recorded and demonstrated as pre-existing under the requirements of this condition.

The developer shall bear the cost of carrying out works to restore all public infrastructure damaged as a result of the carrying out of the development, and no occupation of the development shall occur until damage caused as a result of the carrying out of the development is rectified.

A copy of the dilapidation survey and report must be lodged with North Sydney Council by the Principal Certifier with submission of the Construction Certificate documentation.

(Reason: To record the condition of public infrastructure prior to the commencement of construction)

#### Dilapidation Report Private Property (Excavation) C2

C2. A full dilapidation survey and report on the visible and structural condition of all neighbouring structures within the 'zone of influence' of the required excavations must be submitted to the Principal Certifier for approval prior to the issue of any Construction Certificate. The zone of influence is to be defined as the horizontal distance from the edge of the excavation face to twice the excavation depth.

The dilapidation report and survey are to be prepared by a consulting structural/geotechnical engineer and a copy to be given to the owner of any affected adjoining property.

All costs incurred in achieving compliance with this condition shall be borne by the person entitled to act on this Consent.

In the event that access for undertaking the dilapidation survey is denied by an adjoining owner, the applicant MUST DEMONSTRATE, in writing, to the satisfaction of Council that all reasonable steps have been taken to obtain access and advise the affected property owner of the reason for the survey and that these steps have failed. Written concurrence must be obtained from Council in such circumstances.

- Note: This documentation is for record keeping purposes only, and may be used by the developer or affected property owners to assist in any action required to resolve dispute(s) over damage to adjoining properties arising from the works. It is in the applicant's and adjoining owner's interest for it to be as full and detailed as possible.
- (Reason: To record the condition of property/ies prior to the commencement of construction)

#### Dilapidation Survey Private Property (Neighbouring Buildings) C3

C3. A photographic survey and dilapidation report of the rear setbacks of the adjoining properties at No's. 16 and 18 Benelong Road, Cremorne, detailing the physical condition of those properties, MUST BE submitted to the Principal Certifier for approval prior to the issue of any Construction Certificate. The survey and report are to be prepared by an appropriately qualified person and a copy to be given to the owner of the adjoining property. A copy of the report is to be provided to Council, if Council is not the Principal Certifier, prior to the issue of any Construction Certificate.

All costs incurred in achieving compliance with this condition shall be borne by the person entitled to act on this Consent.

In the event that access for undertaking the photographic survey and dilapidation report is denied by an adjoining owner, the applicant MUST DEMONSTRATE, in writing, to the satisfaction of Council that all reasonable steps have been taken to obtain access and advise the affected property owner of the reason for the survey and that these steps have failed. Written concurrence must be obtained from Council in such circumstances.

Note: This documentation is for record keeping purposes only and may be used by an applicant or affected property owner to assist in any action required to resolve any dispute over damage to adjoining properties arising from the works. It is in the applicant's and adjoining owner's interest for it to be as full and detailed as possible.

(Reason: Proper management of records)

#### Structural Adequacy of Adjoining Properties – Excavation Works C5

C4. A report prepared by an appropriately qualified and practising structural engineer detailing the structural adequacy of adjoining properties No's. **16** and **18 Benelong Road**, **Cremorne**, which certifies their ability to withstand the proposed excavation and outlines any measures required to be implemented to ensure that no damage will occur to adjoining properties during the course of the works, must be submitted to the Principal Certifier for approval prior to the issue of any Construction

Certificate. The measures outlined in the certified report must be complied with at all times.

(Reason: To ensure the protection and structural integrity of adjoining properties in close proximity during excavation works)

#### Structural Adequacy of Existing Building C7

C5. A report prepared by an appropriately qualified and practising structural engineer, certifying the structural adequacy of the property and its ability to withstand the proposed additional, or altered structural loads during all stages of construction shall be submitted to the Principal Certifier for approval prior to issue of any Construction Certificate. The certified report must also include all details of the methodology to be employed in construction phases to achieve the above requirements. The methodology in the certified report must be complied with at all times.

#### Sediment Control C10

C6. Where construction or excavation activity requires the disturbance of the soil surface or existing vegetation, erosion, and sediment control techniques, as a minimum, are to be in accordance with the publication Managing Urban Stormwater: Soils and Construction (4th Edition, Landcom, 2004) commonly referred to as the "Blue Book" or a suitable and effective alternative method.

An Erosion and Sediment Control Plan must be prepared and submitted to the Principal Certifier for approval prior to the issue of any Construction Certificate and prior to any works commencing. The Erosion and Sediment Control Plan must be consistent with the Blue Book and disclose:

- a) All details of drainage to protect and drain the site during the construction processes;
- b) All sediment control devices, barriers and the like;
- c) Sedimentation tanks, ponds or the like;
- d) Covering materials and methods; and
- e) A schedule and programme of the sequence of the sediment and erosion control works or devices to be installed and maintained.
- f) Methods for the temporary and controlled disposal of stormwater during construction.

All works must be undertaken in accordance with the approved Sediment Control plan.

The Principal Certifier must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To protect the environment from the effects of sedimentation and erosion from development sites)

#### Waste Management Plan

C7. A Waste Management Plan is to be submitted for approval by the Principal Certifier prior to the issue of any Construction Certificate. The plan must include, but not be limited to:

<sup>(</sup>Reason: To ensure the structural integrity of the building is maintained)

- a) The estimated volume of waste and method of disposal for the construction and operation phases of the development;
- b) The design of the on-site waste storage and recycling area; and
- c) Administrative arrangements for waste and recycling management during the construction process.

The approved Waste Management Plan must be complied with at all times in the carrying out of the development.

(Reason: To encourage the minimisation of waste and recycling of building waste)

#### Work Zone C23

C8. If a Work Zone is required a Work Zone permit is to be obtained from Council prior to the issue of any Construction Certificate.

*Note:* For major development an application for work zone permit must be considered by the North Sydney Local Traffic Committee.

Work Zones are provided specifically for the set down and pick up of materials and not for the parking of private vehicles associated with the site. Works Zones will generally not be approved where there is sufficient space on-site for the setting down and picking up of goods being taken to or from a construction site. If the Works Zone is approved by the Committee, the Applicant must obtain a written copy of the related resolution from the North Sydney Local Traffic Committee and submit a copy of this to the Principal Certifier to enable issue of the Construction Certificate.

Where approval of the 'Work Zone' is given by the Committee, the requirements of the Committee, including installation of the necessary 'Work Zone' signage and payment of any fees, must occur prior to commencement of any works on the site. Further, at the expiration of the Work Zone approval, the developer is required to remove the Work Zone signs and reinstate any previous signs, all at the developer's cost. The requirements imposed by the Committee on the Work Zone permit (or permits) must be complied with at all times.

(Reason: Amenity and convenience during construction)

#### Obtain Driveway Crossing Permit under S.138 Roads Act 1993 C32

C9. A driveway crossing and roads infrastructure works permit to suit the approved off-street parking facilities must be granted by the Council prior to the issue of any Construction Certificate. In order to obtain a permit under S.138 of the Roads Act 1993, an application must be made to Council on the 'Vehicular Access Application' form with payment of the adopted assessment/inspection fees. Council will require civil design construction drawings and certification from the applicant's Civil Engineer to verify design details and enable issue of the permit. The requirements of the permit must be complied with at all times.

The civil design drawings must include the following at a minimum: -

a) the vehicular access way must comply with AS 2890.1 and Council's current Vehicular Access Application Guidelines and Specification (gutter bridges not permitted) to ensure that a B85 vehicle will not scrape/strike the surface of the carriageway, layback, vehicular crossing, or parking floor,

- b) the redundant parts of the layback crossing on Benelong Lane must be reinstated as upright kerb gutter and concrete footpath,
- c) the width of the vehicular layback must be 4.0 metres (including the wings),
- d) the vehicular laybacks must be set square to the kerb,
- e) The boundary footpath levels and street gutter invert levels must match the existing levels and shall not be altered unless agreed to by Council.
- f) The kerb gutter, and 600 mm road shoulder wide- strip, adjacent to all new layback and gutter works, on Benelong Lane must be reconstructed, to ensure uniformity in the road reserve.
- g) All inspection openings and utility services must be adjusted to match the proposed driveway levels and location.
- h) The design detail has to be provided with vehicular access application and must include sections along the centerline and extremities of the crossing at a scale of 1:25. Sections are to be taken from the centre of the roadway through to the parking area itself and shall include all changes of grade and levels, both existing and proposed.
- i) A longitudinal section along the street gutter line at a scale of 1:50 showing how it is intended to transition the layback with the existing gutter levels and shall include all changes of grade and levels, both existing and proposed.
- j) A longitudinal section along the footpath property boundary at a scale of 1:50 is required and shall include all changes of grade and levels, both existing and proposed.
- Any stormwater pipelines within the footpath area must be hot dipped galvanized rectangular steel hollow section with a minimum wall thickness of 4.0 millimetres and a section height of 100 millimetres.
- I) Any footpath panel on Benelong Lane that is disturbed for the purpose of stormwater connection must be reconstructed as a whole panel.

All driveway and infrastructure works on the road reserve must be undertaken in accordance with the terms of the permit issued by Council. Inspections by Council will be required as specified. The Certifying Authority issuing the Construction Certificate must ensure that the permit issued by Council is obtained and referenced on and accompanies the Construction Certificate issued.

(Reason: To facilitate appropriate vehicular access to private sites, without disruption to pedestrian and vehicular traffic)

#### Porous Paving C33

C10. The proposed off street car parking space(s), driveway, and/or paving may be paved with materials to allow stormwater infiltration to the substrate. Plans and specifications which comply with this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate.

The Certifying Authority must ensure that the building plans and specifications submitted, referenced on, and accompanying the issued Construction Certificate fully satisfy the requirements of this condition.

(Reason: To improve the capacity of the site to absorb water runoff)

### Bond for Damage and Completion of Infrastructure Works - Stormwater, Kerb and Gutter, Footpaths, Vehicular Crossing and Road Pavement

- C11. Prior to the issue of any Construction Certificate, security deposit or bank guarantee must be provided to Council to the sum of **\$3,500.00** to be held by Council for the payment of cost for any/all of the following:
  - a) making good any damage caused to any property of the Council as a consequence of the doing of anything to which this consent relates,
  - b) completing any public work (such as road work, kerbing and guttering, footway construction, stormwater drainage and environmental controls) required in connection with this consent
  - c) remedying any defects in any such public work that arise within 6 months after the work is completed.
  - d) Council reserves the right to retain all bonds on infrastructure works relating to the completion of required Infrastructure work for a 12-month defect liability period. Council may elect to provide a lesser period for minor residential work.

The security required by this condition and in the schedule contained later in these conditions must be provided by way of a deposit with the Council; or other such guarantee that is satisfactory to Council (such as a bank guarantee). Any guarantee provided as security must name North Sydney Council as the nominated beneficiary and must not be subject to an expiry date.

The security will be refundable following the expiration of six months from the issue of any final Occupation Certificate or completion of public work required to be completed (whichever is the latest) but only upon inspection and release by Council's Development Engineers or Manager of Development Services.

Council shall have full authority to make use of the bond for such restoration works as deemed necessary by Council in circumstances including the following:

- where the damage constitutes a hazard in which case Council may make use of the security immediately;
- the applicant has not repaired or commenced repairing damage within 48 hours of the issue by Council in writing of instructions to undertake such repairs or works;
- works in the public road associated with the development are to an unacceptable quality; and
- the Principal Certifier must ensure that security is provided to North Sydney Council prior to issue of any Construction Certificate.
- (Reason: To ensure appropriate security for works on public land and an appropriate quality for new public infrastructure)

#### Arborist to be Commissioned

C12. An experienced AQF Level 5 consulting arborist must be commissioned to assist the design development, contract documentation and overseeing of construction works on the site for their duration by undertaking regular inspections of the works in progress and providing advice in relation to tree matters.

Written details of the engagement of the experienced arborist must be submitted to the Certifying Authority prior to the issue of any Construction Certificate.

- Note: This condition, and any advice given by the consulting arborist, should not be construed as authorising the carrying of development with/ otherwise than in accordance with the development consent.
- (Reason: To ensure that all matters relating to trees are resolved and recorded using best practice)

#### Tree Bond for Public Trees

C13. Prior to the issue of any construction certificate, security in the sum of **\$21,500.00** must be provided to Council for the protection of trees in public places, including the making good of any damage caused to such trees. The security is to be provided in accordance with the Schedule below.

The security required by this condition and in the schedule contained later in these conditions must be provided by way of a deposit with the Council; or other such guarantee that is satisfactory to Council (such as a bank guarantee). Any guarantee provided as security must name North Sydney Council as the nominated beneficiary and must not be subject to an expiry date.

The security will be refundable following the expiration of 6 months from the issue of any final Occupation Certificate but only upon inspection and release by Council's Landscape Development Officer.

If any tree is removed or damaged Council may deduct from this security the reasonable cost of replacement with a tree of the same species and to a similar stage of growth it would have attained at the completion of the work.

In the case of any tree, which cannot be replaced with a similar specimen, the security for that tree will be forfeited to Council and used to provide replacement street plantings.

#### SCHEDULE

Tree Species	Location	Bond
T1 Cinnamomum camphora (22x22m)	Council verge adjacent to north- western side boundary of 16A Benelong Road.	\$20,000
1 x Callistemon viminalis (1.5m)	Council verge in front of 16A Benelong Road.	\$1,500

(Reason: Protection of existing environment public infrastructure, community assets and significant trees)

#### **Tree Protection Measures**

- C14. To ensure the protection of all trees to be retained, the following measures are to be undertaken:
  - a) All documentation for the Construction Certificate application must show the site trees to be retained, and retention of the adjoining trees, with their positions and diameters of trunks and crowns (canopies) to be clearly and accurately shown in relation to all levels of the proposed development.
  - b) The tree protection measures contained in the arborist report prepared by Hugh The Arborist dated 25/10/2022, shall be shown clearly on the Construction Certificate drawings.
  - c) All plans and correspondences must refer to the required compliance with the approved Tree Protection and Management Plan, and clearly show the assigned number of each tree on site, adjoining and Council land.
  - d) A Consulting Arboriculturist ("the project arboriculturist"), who holds a minimum Australian Qualification Framework Level 5 in Arboriculture, is a registered consulting member of a nationally recognised arboricultural organisation or association, and who does not remove or prune trees in the North Sydney local government area, shall be engaged before work commences for the duration of site preparation, demolition, construction and landscaping.
  - e) The project arboriculturist shall inspect, monitor, supervise, provide recommendations and written reports and certification relating to protection of the trees and compliance with the conditions of consent.
  - f) The contact details of the project arboriculturist shall be advised to council before work commences and maintained up to date for the duration of works. If a new project arborist is appointed details of the new project arborist shall be notified to council within 7 days.

Plans and specifications showing the said tree protection measures must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure the construction plans and specifications submitted, referenced on, and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To ensure the protection of significant trees, and that appropriate tree protection measures are shown on construction drawings)

#### Protection of Trees

C15. The following tree(s) are required to be protected and retained as part of the development consent in accordance with AS 4970-2009 – Protection of trees on development sites:

Tree	Location	Height
T1 Cinnamomum camphora	Council verge adjacent to north- western side boundary of 16A Benelong Road.	22x22m
1 x Callistemon viminalis	Council verge in front of 16A Benelong Road.	1.5m
Section of <i>Viburnum</i> hedge (Not expressly shown for	Rear boundary of 16A Benelong Road	5m

Removal)		
1 x Camelia sasanqua hedge	Front boundary16A Benelong Road	1.5m
1 x existing tree	North-eastern corner of the front setback – 16A Benelong Road	5x5m

Plans and specifications complying with this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the building plans and specifications submitted, referenced on, and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

Any tree(s) shown as being retained on the approved plans (regardless of whether they are listed in the above schedule or not) must be protected and retained in accordance with this condition and AS4970.

(Reason: Protection of existing environmental and community assets)

#### **Approval for Removal of Trees**

C16. The following tree(s) are approved for removal in accordance with the development consent:

Trees that are acceptable to remove	Location	Height
Northern end of Viburnum hedge	Rear boundary 16A Benelong Road	5m

Removal of any other tree on the site is not approved, excluding species exempt under Council's Tree Preservation Order.

Any tree(s) shown as being retained on the approved plans (regardless of whether they are listed in the above schedule or not) must be protected and retained in accordance with this condition.

(Reason: Protection of existing environmental and community assets)

#### Garbage and Recycling Facilities

- C17. Adequate provision must be made for the storage of waste and recyclable material generated by the premises. Plans and specifications which comply with this condition must be submitted to the Principal Certifier for approval prior to the issue of any Construction Certificate. The Principal Certifier must ensure that the building plans and specifications submitted, referenced on, and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.
  - (Reason: To ensure the provision of appropriate waste facilities and to ensure efficient collection of waste by collection contractors)

#### **Asbestos Material Survey**

C18. A report must be prepared by a suitably qualified person in relation to the existing building fabric to be demolished and/or disturbed identifying the presence or otherwise of asbestos contamination and, if asbestos contamination is present, making recommendations as to the work required to safely address the contamination.

Any demolition works or other works identified in the report as having to be carried out must be carried out in accordance with the recommendations of the report and the following:

a) the removal of asbestos must be undertaken by a WorkCover licensed contractor;

- all removal must be in strict accordance with the requirements of the WorkCover Authority in relation to the removal, handling and disposal of material containing asbestos and any Work Safe Australia requirements.
- c) during the removal of any asbestos a sign stating "DANGER ASBESTOS REMOVAL IN PROGRESS" must be erected in a visible position at the boundary of the site; and
- d) Waste disposal receipts must be provided to the Principal Certifier as proof of correct disposal of asbestos laden waste.

The report must be submitted to the Principal Certifier for approval prior to the issue of any Construction Certificate. The Principal Certifier must ensure that the report, and other plans, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To ensure the long term health of workers on site and occupants of the building is not put at risk unnecessarily)

#### Air Conditioners in Residential Premises

- C19. The use of any air conditioner installed on the premises must comply with the requirements of the Protection of the Environment Operations (Noise Control) Regulations 2017 and State Environmental Planning Policy (Infrastructure) 2007 and must not:
  - (a) emit a noise that is audible within a habitable room in any affected residence (regardless of whether any door or window to that room is open);
    - (i) before 8.00am and after 10.00pm on any Saturday, Sunday or Public Holiday; or
    - (ii) before 7.00am or after 10.00pm on any other day
  - (b) cause an LAeq(15min) which exceeds the RBL background noise level by more than 5dB when measured at the boundary of any affected residence. The modifying factor adjustments in Section 4 of the EPA Noise Policy for Industry 2017 will be applied.

"affected residence" includes residential premises (including any lot in the strata scheme or another strata scheme), premises for short-term accommodation and hospitals.

"boundary" includes any window or elevated window of an affected residence.

Terms in this condition have the same meaning as in the Noise Guide for Local Government and the Noise Policy for Industry published by the NSW Environment Protection Authority.

(Reason: To maintain residential amenity)

#### Section 7.12 Development Contributions

C20. A monetary contribution pursuant to the provisions of Section 7.12 of the *Environmental Planning and Assessment Act 1979* is to be paid to Council, in accordance with the North Sydney Council's Contribution Plan, to provide for local infrastructure improvements.

Based on the cost of development at the date of determination, the total contribution payable to Council is **\$8,000.00**.

#### **Indexation**

The monetary contribution required under this consent will be indexed between the date of the grant of the consent and the date on which the contribution is paid the time of payment in accordance with quarterly movements in the Consumer Price Index (All Groups Index) for Sydney as published by the Australian Bureau of Statistics.

#### **Timing of payment**

The contribution must be paid to Council prior to issue of any Construction Certificate for any work approved by this consent.

A copy of the North Sydney Contribution Plan can be viewed at North Sydney Council's Customer Service Centre, 200 Miller Street, North Sydney or downloaded via Council's website at www.northsydney.nsw.gov.au

(Reason: to provide for local infrastructure identified in the North Sydney Council Local Contributions Plan 2020)

#### Security Deposit/Guarantee and Free Schedule

C21. All fees and security deposits/ guarantees in accordance with the schedule below must be provided to Council prior to the issue of any Construction Certificate:

Security Deposit/Guarantee	Amount (\$)
Footpath Damage Bond	\$3,500.00
Tree Protection Bond (on Council's property)	\$21,500.00
TOTAL BONDS	\$25,000.00

The security required by the above schedule must be provided by way of a deposit with the Council; or other such guarantee that is satisfactory to Council (such as a bank guarantee). Any guarantee provided as security must name North Sydney Council as the nominated beneficiary and must not be subject to an expiry date.

Note: The following fees are applicable as per Condition C20.

Fees	Amount (\$)
Section 7.12 Development Contributions	\$8,000.00
TOTAL FEES	\$8,000.00

(Reason: Compliance with the development consent)

#### **BASIX Certificate**

C22. Under clause 75 of the Environmental Planning & Assessment Regulation 2021, it is a condition of this development consent that all the commitments listed in BASIX Certificate No. A477786 (dated 21 December 2022) for the development are fulfilled. Plans and specifications complying with this condition must be submitted to the Principal Certifier for approval prior to the issue of the relevant Construction Certificate. The Principal Certifier must ensure that the building plans and specifications submitted, referenced on, and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To ensure the proposed development will meet the Government's requirements for

#### sustainability and statutory requirements)

#### Landscape Amendments

- C23. The landscape plans approved as per Condition A1 of this consent, must be amended as follows:
  - 1) The landscape plans numbered 101-103, prepared by Jamie King Landscape Architect, dated 5 May 2023, received by Council on 8 May 2023, must be amended and updated to reflect the amendments made in the architectural plans (Numbered DA01 revision D, DA07 revision E, and DA17 revision D) prepared by Contemporary Architecture, dated 5 September 2023, and received by Council on 6 September 2023.
  - 2) 1 x replacement *Viburnum odoratissimum* (minimum 25-litre pot size) is to be planted in the north-western corner of the site to line with the existing rear hedge.
  - 3) The proposed *Hymenosporum flavum* and *Tristaniopsis* 'Luscious' shown shall be a minimum of 75-litre in pot size.

Amended plans complying with this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the amended plans and specifications submitted fully satisfy the requirements of this condition.

(Reason: To ensure an appropriate landscaped context and to demonstrate compliance with Council's controls)

#### **Root Mapping**

C24. Non-invasive/non- destructive root mapping is to be undertaken within the tree protection zone (TPZ) (identified as per AS4970-2009) of the [specify tree/location] to determine the size and depth of the tree roots prior to the design of the required footings for [specify structure].

Root mapping is to be undertaken under the direct supervision of an AQF level 5 arborist. The said consulting/ project arborist is to prepare a written report, with images, addressing the following:

- a) describing the results of the root mapping;
- b) providing an assessment of potential tree impacts of the excavation; and
- c) making recommendations of protection measures to be implemented for the duration of excavation and construction activity to ensure the ongoing health and viability of the tree.

The report is to be provided to the Principal Certifier for approval (with a copy provided to Council) prior to the issue of the relevant Construction Certificate. Plans and Specifications submitted to the Certifier for approval must comply with the recommendations of the arborist report referred to in this condition, and the development must be carried out in accordance with the said report.

(Reason: To ensure the protection of significant trees)

#### D. Prior to the Commencement of any Works (and continuing where indicated)

#### **Protection of Public Trees**

D1. The following tree(s) are required to be protected and retained as part of the development consent in accordance with AS 4970-2009 – Protection of trees on development sites:

Tree	Location	Protection
T1 Cinnamomum camphora (22x22m)	• •	1.8m-high steel mesh tree protection fencing. Trunk, branch, and root protection.
1 x Callistemon viminalis (1.5m)	Council verge in front of 16A Benelong Road.	1.8m-high steel mesh tree protection fencing.

Trunk protection is to be installed by first wrapping the stem of the tree in hessian or like material then strapping timber battens over the top. It is recommended that timber battens with the dimensions of length 2000mm, width 75mm and depth 50mm are used. The battens are not to be directly screwed or nailed into the tree.

Plans and specifications complying with this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the building plans and specifications submitted, referenced on, and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: Protection of existing environmental and community assets)

#### **Protection of Trees**

D2. All trees that are specifically nominated to be retained by notation on plans or by condition as a requirement of this consent must be maintained and protected during demolition, excavation, and construction on the site in accordance with AS4970-2009 (Protection of trees on development sites). A report containing recommendations, and methods of tree protection prepared by an appropriately qualified person must be provided to the Certifying Authority for approval by an appropriately qualified person prior to commencement of any works on the site. Any recommendations must be undertaken for the duration of works on the site.

Sensitive construction techniques including hand excavation, pier and beam construction, and the flexible location of piers/footings shall be used within the Tree Protection Zone (TPZ) of any protected tree. No roots greater than 50mm shall be cut. No stormwater or any other underground services shall be directed through the TPZ of any protected tree.

(Reason: To ensure that the stability and ongoing viability of trees being retained are not compromised. Tree protection measures.)

#### **Project Arborist Engaged**

D3. The project arboriculturist shall inspect tree protection measures and certify in writing to the Principal Certifying Authority the measures comply with the approved Tree Protection Plan and as directed by the project arboriculturist before work commences.

The project arboriculturist shall provide guidance and oversight of tree protection and management to ensure that the stability and ongoing viability of trees being retained is not compromised.

The project arboriculturist must contact the tree pruning contractor and Council's Tree Management Officer (giving at least 2 working days' notice) to arrange a joint site meeting, prior to commencing any

pruning, to determine the exact location and extent of pruning that is permissible, with the tree pruning contractor to comply with any instructions issued by Council, acting reasonably.

Any pruning must be undertaken by a practicing arborist with a minimum Australian Qualification Framework Level 3 in arboriculture, in accordance with the principles of the Australian Standard AS 4373-2007 'Pruning of Amenity Trees,' and the NSW Work Cover Code of Practice for the Amenity Tree Industry (1998), as well as any instructions issued on site by Council, acting reasonably.

The practicing arborist must keep a log of dates and times of when they attended the site, the type of works that were performed, and must form part of the certification required prior to Occupation.

(Reason: Tree protection measures)

#### **Temporary Fences and Tree Protection**

D4. All protected trees on-site that are specifically nominated as per condition C46 to be retained by notation on plans or by condition as a requirement of this consent must be tagged with luminous tape or the like for purposes of identification prior to demolition, excavation or construction works and must remain so for the duration of works on the site. No materials or builder's waste are to be stored in the vicinity of the nominated tree/trees at any time.

Appropriate fencing or barricades in accordance with AS4970-2009 (Protection of trees on development sites) must be installed to the satisfaction of the Certifying Authority prior to demolition or commencement of any works and must be maintained for the duration of the works: -

(Reason: To protect the trees to be retained on the site during construction works)

#### Public Liability Insurance - Works on Public Land

- D5. Any person or contractor undertaking works on public land must take out Public Risk Insurance with a minimum cover of \$20 million in relation to the occupation of public land and the undertaking of approved works within Council's road reserve or public land, as approved by this consent. The Policy is to note and provide protection/full indemnification for North Sydney Council, as an interested party. A copy of the Policy must be submitted to Council prior to commencement of any works. The Policy must be valid for the entire period that the works are being undertaken.
  - (Note: Applications for hoarding permits, vehicular crossings etc will require evidence of insurance upon lodgement of the application.)
  - (Reason: To ensure the community is protected from the cost of any claim for damages arising from works on public land)

#### Commencement of Works' Notice D11

- D6. Building work, demolition or excavation in accordance with this development consent must not be commenced until the developer has given at least two days' notice to North Sydney Council of the person's intention to commence building work, demolition or excavation in accordance with this development consent.
  - (Reason: To ensure appropriate safeguarding measures are in place prior to the commencement of any building work, demolition or excavation)

#### E. During Demolition and Building Work

#### Parking Restrictions

E1. Existing public parking provisions in the vicinity of the site must be maintained at all times during works. The placement of any barriers, traffic cones, obstructions or other device in the road shoulder or kerbside lane is prohibited without the prior written consent of Council. Changes to existing public parking facilities/restrictions must be approved by the North Sydney Local Traffic Committee. The Developer will be held responsible for any breaches of this condition and will incur any fines associated with enforcement by Council regulatory officers.

(Reason: To ensure that existing kerbside parking provisions are not compromised during works)

#### Road Reserve Safety

E2. All public footways and roadways fronting and adjacent to the site must be maintained in a safe condition at all times during the course of the development works, with no obstructions caused to the said footways and roadways. Construction materials and plant must not be stored in the road reserve without approval of Council.. A safe pedestrian circulation route and a pavement/route free of trip hazards must be maintained at all times on or adjacent to any public access ways fronting the construction site.

Where public infrastructure is damaged, repair works must be carried out in when and as directed by Council officers (at full Developer cost). Where pedestrian circulation is diverted on to the roadway or verge areas, clear directional signage and protective barricades must be installed in accordance with AS1742-3 (1996) "Traffic Control Devices for Work on Roads". If pedestrian circulation is not satisfactorily maintained across the site frontage, and action is not taken promptly to rectify the defects, Council may undertake proceedings to stop work.

(Reason: Public Safety)

#### **Temporary Disposal of Stormwater Runoff**

E3. During construction, stormwater runoff must be disposed in a controlled manner that is compatible with the erosion and sediment controls on the site. Immediately upon completion of any impervious areas on the site (including roofs, driveways, paving) and where the final drainage system is incomplete, the necessary temporary drainage systems must be installed to reasonably manage and control runoff as far as the approved point of stormwater discharge. Such ongoing measures must be to the satisfaction of the Principal Certifier.

(Reason: Stormwater control during construction)

#### Service Adjustments

E4. Where required, the adjustment or inclusion of any new utility service facilities must be carried out by the person acting on the consent and in accordance with the requirements of the relevant utility authority. These works shall be at no cost to Council. It is the Applicant's full responsibility to make contact with the relevant utility authorities to ascertain the impacts of the proposal upon utility services at the appropriate stage of the development (including water, phone, gas and the like).

Council accepts no responsibility whatsoever for any matter arising from its approval of this application involving any influence upon utility services provided by another authority.

(Reason: To ensure the service requirements are met)

#### **Council Inspection of Public Infrastructure Works**

- E5. During the works on public infrastructure reverting to Council's care and control, Council's development engineer may undertake inspections of the works at the following hold points: -
  - Vehicular access; and associated road civil works.

All works must proceed in accordance with Roads Act 1993 approvals or other permits relating to roads issued by Council. A minimum of 48 hours' notice must be given to Council to book an inspection. Work must not proceed until the works or activity covered by the inspection is approved.

(Reason: To ensure quality of construction joints and connections in the drainage system)

#### **Removal of Extra Fabric**

E6. Should any portion of the existing building, trees, or curtilage of the site which is indicated on the approved plans to be retained be damaged for whatever reason, all the works in the area of the damaged portion are to cease and written notification of the damage is to be given to Council forthwith. No work is to resume until the written approval of Council to do so is obtained. Failure to comply with the provisions of this condition may result in the Council taking further action including legal proceedings if necessary.

(Reason: To ensure compliance with the terms of this development consent)

#### **Dust Emission and Air Quality**

- E7. The following must be complied with at all times:
  - (a) Materials must not be burnt on the site.
  - (b) Vehicles entering and leaving the site with soil or fill material must be covered.
  - (c) Dust suppression measures must be carried out to minimise wind-borne emissions in accordance with the NSW Department of Housing's 1998 guidelines Managing Urban Stormwater: Soils and Construction.
  - (d) Odour suppression measures must also be carried out where appropriate so as to prevent nuisance occurring at adjoining properties.
  - (Reason: To ensure residential amenity is maintained in the immediate vicinity)

#### Noise and Vibration

E8. The works must be undertaken in accordance with the "Interim Construction Noise Guideline" published by the NSW Environment Protection Authority, to ensure excessive levels of noise and vibration do not occur so as to minimise adverse effects experienced on any adjoining land.

(Reason: To ensure residential amenity is maintained in the immediate vicinity)

#### **Developer's Cost of Work on Council Property**

- E9. The developer or the person, company or other entity that is acting upon this consent, must bear the cost of all works associated with the development that occurs on Council's property, including the restoration of damaged areas.
  - (Reason: To ensure the proper management of public land and funds)

#### No Removal of Trees on Public Property

- E10. No trees on public property (footpaths, roads, reserves, etc.) unless specifically approved by this consent shall be removed or damaged during construction including for the erection of any fences, hoardings, or other temporary works.
  - (Reason: Protection of existing environmental infrastructure and community assets)

#### **Protection of Trees**

E11. All trees required to be retained, as part of this consent must be protected from any damage during construction works in accordance with AS4970-2009. All recommendations contained within the tree report prepared by Hugh The Arborist dated 25/10/2022 must be implemented for the duration of the works.

In the event that any tree required to be retained is damaged during works on the site, notice of the damage must be given to Council forthwith.

Notes:

- 1) If the nominated tree is damaged to a significant degree or removed from the site without prior written approval being obtained from Council, the issuing of fines or legal proceedings may be commenced for failure to comply with the conditions of this consent.
- 2) An application to modify this consent pursuant to Section 96 of the *Environmental Planning and Assessment Act 1979* will be required to address the non-compliance with any of the conditions of consent relating to the retention of nominated trees, and Council may require tree replenishment.

(Reason: Protection of existing environmental infrastructure and community assets)

#### Trees to be Removed

E12. All trees on the site must be protected and retained save for those expressly identified below as being approved for removal: -

Trees that are acceptable to remove	Location	Height
Northern end of Viburnum hedge	Rear boundary of 16A Benelong Road	5m

(Reason: To ensure compliance with the terms of this development consent)

#### **Special Permits**

E13. Unless otherwise specifically approved in writing by Council, all works, processes, storage of materials, loading and unloading associated with the development must occur entirely on the property.

The developer, owner or builder may apply for specific permits available from Council's Customer Service Centre for the undermentioned activities on Council's property. In the event that a permit is granted by Council for the carrying out of works, processes, storage of materials, loading and unloading associated with the development on Council's property, the development must be carried out in accordance with the requirements of the permit. A minimum of forty-eight (48) hours' notice is required for any permit:

#### 1) **On-street mobile plant**

E.g., cranes, concrete pumps, cherry-pickers, etc., - restrictions apply to the hours of operation, the area of operation, etc. Separate permits are required for each occasion and each piece of equipment. It is the developer's, owner's and builder's responsibilities to take whatever steps are necessary to ensure that the use of any equipment does not violate adjoining property owner's rights.

(Reason: Proper management of public land)

#### 2) Hoardings

Permits are required to erect Class A and Class B hoardings. If an 'A' Class hoarding is to alienate a section of Council's property, that section will require a permit for the occupation of Council's property.

(Reason: Proper management of public land)

#### 3) Storage of building materials and building waste containers (skips) on Council's property

Permits to utilise Council property for the storage of building materials and building waste containers (skips) are required for each location. Failure to obtain the relevant permits will result in the building materials or building waste containers (skips) being impounded by Council with no additional notice being given. Storage of building materials and waste containers on open space reserves and parks is prohibited.

(Reason: Proper management of public land)

#### 4) Kerbside restrictions, construction zones

Attention is drawn to the existing kerbside restrictions adjacent to the development. Should alteration of existing kerbside restrictions be required, or the provision of a construction zone, the appropriate application must be made and the fee paid to Council. Alternatives to such restrictions may require referral to Council's Traffic Committee and may take considerable time to be resolved. An earlier application is suggested to avoid delays in construction programs.

(Reason: Proper management of public land)

#### **Construction Hours**

E14. Construction activities and works approved under this consent must be restricted to within the hours stipulated in the following table:

Standard Construction Hours			
Location	Day	Hours	
All zones	Monday - Friday	7.00 am - 5.00 pm	
(Excl. E2 Commercial Centre &	Saturday	8.00 am - 1.00 pm	
MU1 Mixed-use Zone)	Sunday, Public holiday	No work permitted	

Construction activities for development approved under this consent must be carried out in accordance with the standard construction hours above, the EPA Noise Policy for Industry 2017 and any Construction Noise Management Plan required under this consent.

In the event of breach to the approved hours of construction Council take may take enforcement action under Part 9 of the EP&A Act 1979 and in accordance with Council's adopted Compliance and Enforcement Policy.

(Reason: To ensure that works do not interfere with reasonable amenity expectations of residents and the community)

#### Installation and Maintenance of Sediment Control

E15. Erosion and sediment controls must be installed and maintained at all times in accordance with the Sediment and erosion control plan submitted and approved with the Construction Certificate.

Erosion and sediment measures must be maintained in accordance with the publication Managing Urban Stormwater: Soils and Construction (4th Edition, Landcom, 2004), commonly referred to as the "Blue Book" and can only be removed when development activities have been completed and the site fully stabilised.

(Reason: To protect the environment from the effects of sedimentation and erosion from development sites)

#### Sediment and Erosion Control Signage

- E16. A durable sign must be erected during building works in a prominent location on site, warning of penalties should appropriate erosion and sedimentation control devices not be maintained. A sign of the type referred to in this condition is available from Council.
  - (Reason: To protect the environment from the effects of sedimentation and erosion from development sites)

#### Site Amenities and Facilities

E17. Where work involved in the erection and demolition of a building is being carried out, amenities which satisfy applicable occupational health and safety and construction safety regulations, including any WorkCover Authority requirements, must be provided and maintained at all times. The type of work-place determines the type of amenities required.

Further information and details can be obtained from the Internet at <u>www.workcover.nsw. gov.au</u>.

(Reason: To ensure the health and safety of the community and workers on the site)

#### Health and Safety

E18. All work undertaken must satisfy applicable occupational health and safety and construction safety regulations, including any WorkCover Authority requirements to prepare a health and safety plan. Site fencing must be installed sufficient to exclude the public from the site. Safety signs must be erected that warn the public to keep out of the site and provide a contact telephone number for enquiries.

Further information and details regarding occupational health and safety requirements for construction sites can be obtained from the internet at <u>www.workcover.nsw.gov.au</u>.

(Reason: To ensure the health and safety of the community and workers on the site)

#### Archaeological Discovery During Works

- E19. Should any historical or Aboriginal relic be discovered on the site during demolition, excavation or site preparatory works, all excavation or disturbance to the area is to stop immediately and the Heritage Council of NSW must be informed in accordance with the provisions of the Heritage Act 1977 and/or National Parks and Wildlife Act, 1974. Works must not recommence until such time as approval to recommence is given in writing by Council or a permit from the Director of the NPWS is issued.
  - (Reason: To prevent the unnecessary destruction or removal of unrecorded historical or Aboriginal relics)

#### Prohibition on Use of Pavements

- E20. Building materials must not be placed on Council's footpaths, roadways, parks, or grass verges, (unless a permit is obtained from Council beforehand). A suitable sign to this effect must be erected adjacent to the street alignment.
  - (Reason: To ensure public safety and amenity on public land)

#### Plant and Equipment Kept Within Site

E21. All plant and equipment used in the undertaking of the development/ works, including concrete pumps, wagons, lifts, mobile cranes, hoardings etc, must be situated within the boundaries of the site (unless a permit is obtained from Council beforehand) and so placed that all concrete slurry, water, debris and the like must be discharged onto the building site, and is to be contained within the site boundaries.

Details of Council requirements for permits on public land for standing plant, hoardings, storage of materials and construction zones and the like are available on Council's website at <u>www.north</u> <u>sydney.nsw.gov.au</u>.

(Reason: To ensure public safety and amenity on public land)

#### Waste Disposal

E22. All records demonstrating the lawful disposal of waste must be retained and kept readily accessible for inspection by regulatory authorities such as North Sydney Council and the Environmental Protection Authority.

(Reason: To ensure the lawful disposal of construction and demolition waste)

#### Asbestos Removal

E23. All demolition works involving the removal and disposal of asbestos cement must only be undertaken by contractors who hold a current WorkCover Asbestos or "Demolition Licence" and a current WorkCover "Class 2 (Restricted) Asbestos Licence and removal must be carried out in accordance with National Occupational Health and Safety Commission.

(Reason: To ensure works are carried out in accordance with relevant WorkCover requirements)

#### F. Prescribed Conditions imposed under EP&A Act and Regulations and other relevant Legislation

#### **National Construction Code**

F1. All building work must be carried out in accordance with the provisions of the National Construction Code.

(Reason: Prescribed - Statutory)

#### **Home Building Act**

- F2. 1) Building work that involves residential building work (within the meaning and exemptions provided in the Home Building Act 1989) for which the *Home Building Act* 1989 requires there to be a contract of insurance under Part 6 of that Act must not be carried out unless the Principal Certifier for the development to which the work relates has given North Sydney Council written notice of the contract of insurance being issued and of the following:
  - a) in the case of work for which a principal contractor is required to be appointed:
    - i) the name and licence number of the principal contractor, and
    - ii) the name of the insurer by which the work is insured under Part 6 of that Act, or
  - (b) in the case of work to be done by an owner-builder:
    - (i) the name of the owner-builder, and
    - (ii) if the owner-builder is required to hold an owner-builder permit under that Act, the number of the owner-builder permit.
  - 2) If arrangements for doing residential building work are changed while the work is in progress such that the information submitted to Council in accordance with this condition is out of date, work must cease, and no further work may be carried out unless the Principal Certifier for the development to which the work relates (not being the Council), has given the Council written notice of the updated information.
  - Note: A certificate purporting to be issued by an approved insurer under Part 6 of the Home Building Act 1989 that states that a person is the holder of an insurance policy issued for the purposes of that Part is, for the purposes of this clause, sufficient evidence that the person has complied with the requirements of that Part.

(Reason: Prescribed - Statutory)

#### Appointment of Principal Certifier (PC)

- F3. Building work, **demolition** or excavation in accordance with the development consent must not be commenced until the developer has appointed a Principal Certifier for the building work in accordance with the provisions of the EP&A Act and its Regulations.
  - (Reason: Statutory; To ensure appropriate safeguarding measures are in place prior to the commencement of any building work, demolition or excavation)

#### **Construction Certificate**

- F4. Building work, demolition or excavation in accordance with the development consent must not be commenced until a Construction Certificate for the relevant part of the building work has been issued in accordance with the provisions of the EP&A Act and its Regulations.
  - (Reason: Statutory; To ensure appropriate safeguarding measures are in place prior to the commencement of any building work, demolition or excavation)

#### **Occupation Certificate**

- F5. A person must not commence occupation or use of the whole or any part of a new building (new building includes an altered portion of, or an extension to, an existing building) unless an Occupation Certificate has been issued in relation to the building or part. Only the Principal Certifier appointed for the building work can issue an Occupation Certificate.
  - (Reason: Statutory)

#### **Excavation/Demolition**

- F6. 1) All excavations and backfilling associated with the erection or demolition of a building must be executed safely and in accordance with appropriate professional standards.
  - 2) All excavations associated with the erection or demolition of a building must be properly guarded and protected to prevent them from being dangerous to life or property.
  - 3) Demolition work must be undertaken in accordance with the provisions of AS2601- Demolition of Structures.
  - (Reason: To ensure that work is undertaken in a professional and responsible manner and protect adjoining property and persons from potential damage)

#### **Protection of Public Places**

- F7. 1) A hoarding and site fencing must be erected between the work site and adjoining public place.
  - 2) If necessary, an awning is to be erected, sufficient to prevent any substance from, or in connection with, the work falling into the public place.

- 3) The work site must be kept lit between sunset and sunrise if it is likely to be hazardous to persons in the public place.
- 4) Any such hoarding, fence or awning is to be removed when the work has been completed.
- 5) No access across public reserves or parks is permitted.
- Note: Prior to the erection of any temporary fence or hoarding over property owned or managed by Council, written approval must be obtained. Any application needs to be accompanied by plans indicating the type of hoarding and its layout. Fees are assessed and will form part of any approval given. These fees must be paid prior to the approval being given. Approval for hoardings will generally only be given in association with approved building works, maintenance or to ensure protection of the public. An application form for a Hoarding Permit can be downloaded from Council's website.
- (Reason: To ensure public safety and the proper management of public land)

#### Site Sign

- F8. 1) A sign must be erected in a prominent position on the site
  - a) stating that unauthorised entry to the work site is prohibited;
  - b) showing the name of the principal contractor (or person in charge of the work site), and a telephone number at which that person may be contacted at any time for business purposes and outside working hours; and
  - c) showing the name, address and telephone number of the Principal Certifier for the work.
  - 2) Any such sign must be maintained while to building work or demolition work is being carried out but must be removed when the work has been completed.

(Reason: Prescribed - Statutory)

#### G. Prior to the Issue of an Occupation Certificate

#### Infrastructure Repair and Completion of Works

- G1. Prior to the issue of any Occupation Certificate any and all works relating to the development:
  - a. in the road reserve must be fully completed; and
  - to repair and make good any damaged public infrastructure caused as a result of any works relating to the development (including damage caused by, but not limited to, delivery vehicles, waste collection, contractors, sub-contractors, concrete vehicles) must be fully repaired;

to the satisfaction of Council Engineers at no cost to Council. Council's development engineer must be contacted to arrange inspections of the completed works in the Public Domain.

(Reason: Maintain quality of Public assets)

#### **Certification – Civil Works**

- G2. An appropriately qualified and practicing Civil Engineer must certify to the Certifying Authority that the vehicular crossing and associated works and road works were constructed in accordance with this consent and any approval for works in the road reserve issued by the Council. A copy of the certificate must be submitted to Council (if it is not the Certifying Authority), upon completion of the development works and prior to the issue of an Occupation Certificate.
  - (Reason: Compliance with the Consent)

#### **Damage to Adjoining Properties**

- G3. All precautions must be taken to prevent any damage likely to be sustained to adjoining properties. Adjoining owner property rights and the need for owner's permission must be observed at all times, including the entering onto land for the purpose of undertaking works.
  - (Reason: To ensure adjoining owner's property rights are protected)

#### **Utility Services**

G4. All utility services shall be adjusted to the correct levels and/or location/s required by this consent, prior to issue of an occupation certificate. This shall be at no cost to Council.

(Reason: To ensure compliance with the terms of this consent)

#### Asbestos Clearance Certificate

- G5. For building works where asbestos based products have been removed or altered, an asbestos clearance certificate signed by an appropriately qualified person (being an Occupational Hygienist or Environmental Consultant) must be submitted to and approved by the Principal Certifier (and a copy forwarded to Council if it is not the Principal Certifier) for the building work prior to the issue of any Occupation Certificate, the asbestos clearance certificate must certify the following:
  - a) the building/ land is free of asbestos; or
  - b) the building/ land has asbestos that is presently deemed safe.

The certificate must also be accompanied by tipping receipts, which detail that all asbestos waste has been disposed of at an approved asbestos waste disposal depot. If asbestos is retained on site the certificate must identify the type, location, use, condition and amount of such material.

- Note: Further details of licensed asbestos waste disposal facilities can be obtained from www.epa.nsw.gov.au
- (Reason: To ensure that building works involving asbestos based products are safe for occupation and will pose no health risks to occupants)

#### **Certification of Tree Condition**

G6. Prior to the issue of an Occupation Certificate, a report prepared by an appropriately qualified person (AQ5 Arborist) must be submitted to the Certifying Authority, describing the health of the tree(s) specifically nominated below: -

### RE: 16A BENELONG ROAD, CREMORNE DEVELOPMENT CONSENT NO. 4/23

Tree	Location	Height
T1 Cinnamomum camphora	Council verge adjacent to north-western side	22x22m
	boundary of 16A Benelong Road.	
1 x Callistemon viminalis	Council verge in front of 16A Benelong Road.	1.5m
Section of Viburnum hedge	Rear boundary of 16A Benelong Road	5m
(Not expressly shown for		
Removal)		
1 x Camelia sasanqua hedge	Front boundary16A Benelong Road	1.5m
1 x existing tree	North-eastern corner of the front setback -	5x5m
	16A Benelong Road	

The report must detail the condition and health of the nominated trees upon completion of the works and shall certify that the trees have not been significantly damaged during the works on the site and have reasonable prospects for survival.

(Reason: To ensure compliance with the terms of this consent)

#### **BASIX Completion Receipt**

G7. In accordance with Section 45 of the Environmental Planning and Assessment (Development Certification and Fire Safety) Regulation 2021, prior to issuing a final occupation certificate the Principal Certifier must provide a BASIX completion receipt.

(Reason: To ensure compliance with the Regulations)

#### Landscaping

G8. The landscaping shown in the approved plans numbered 101-103, prepared by Jamie King Landscape Architect, dated 5 May 2023, received by Council on 8 May 2023, and as amended by **Condition C23** of this consent, must be completed prior to the issue of any Occupation Certificate.

(Reason: To ensure compliance)

#### **Unpaved Verge**

- G9. The unpaved verge area must be constructed or reconstructed and planted with an appropriate species of grass prior to completion of the works at no cost to Council.
  - (Reason: To ensure that community assets are presented in accordance with reasonable community expectations)

#### **Compliance with Certain Conditions**

- G10. Prior to the issue of any Occupation Certificate **Condition 23 (Landscape Amendments)** must be certified as having been implemented on site and complied with.
  - (Reason: To ensure the development is completed in accordance with the requirements of this consent)

#### I. Ongoing/Operational Conditions

#### Single Occupancy

11. Nothing in this consent authorises the use of the premises other than for a single occupancy.

(Reason: To ensure compliance with the terms of this consent)

#### Maintenance of Approved Landscaping

12. The owner(s) of 16A Benelong Road, Cremorne, is/are to maintain the landscaping approved by this consent generally in accordance with the landscaping shown on plans numbered 101-103, prepared by Jamie King Landscape Architect, dated 5 May 2023, received by Council on 8 May 2023, and as amended by **Condition C23** of this consent.

Any replacement plants required shall be advanced in growth and be selected to maintain the anticipated mature height, canopy density and nature of those plant species as originally approved.

(Reason: To ensure maintenance of the amenity, solar access, and views of adjoining properties)