

200 Miller Street, North Sydney, NSW 2060 | ABN 32 353 260 317
All correspondence PO Box 12, North Sydney, NSW 2059
P (02) 9936 8100 | E council@northsydney.nsw.gov.au
W www.northsydney.nsw.gov.au

Mr Levi Fletcher, The City Geeks Pty Ltd 401/661 George Street HAYMARKET NSW 2000

> D15/23 DWH (CPE)

# ENVIRONMENTAL PLANNING AND ASSESSMENT ACT, 1979 AS AMENDED NOTICE OF DETERMINATION - Approval

Development Application Number:	15/23
Land to which this applies:	48 Emmett Street, Crows Nest Lot No.: B, DP 356451
Applicant:	L Fletcher, The City Geeks Pty Ltd
Proposal:	Construction of garage with studio above
Determination of Development Application:	Subject to the provisions of Section 4.17 of the Environmental Planning and Assessment Act 1979, approval has been granted subject to conditions in the notice of determination.
Date of Determination:	15 December 2023
	The development application has been assessed against the North Sydney Environmental Plan 2013 and the North Sydney Development Control Plan 2013 and generally found to be satisfactory.
Reasons for Approval	Subject to conditions requiring amendment of the development, the proposal is not considered to cause unreasonable impacts on the Holtermann Estate C Conservation Area or adjoining properties. The reduction of the garage by 400mm overall and amendment to the width of the dormer windows is considered sufficient to preserve adequate solar access and privacy for adjoining properties. Conditions are also required to provide for additional soft landscaping within the site.
	Having regard to the provisions of Section 4.15 (1) of the Environmental Planning and Assessment Act 1979, the proposed development will not result in any unreasonable amenity or environmental impacts. The application is considered satisfactory and is recommended for approval.

Consent to operate from:	15 December 2023
Consent will lapse on:	15 December 2028
Period of Consent	Subject to Section 4.20 of the Act, this consent becomes effective and operates from the date listed above. The consent lapses five years after the date of consent in accordance with Section 4.53 of the Act and cannot be extended. To activate this consent, works must physically commence onsite 15 December 2028.
How community views were taken into account:	The subject application was notified to adjoining properties and the Hayberry for 14 days where a number of issues were raised that have been addressed in this report where appropriate conditions of consent have been recommended to maintain the amenity of adjoining properties and/or the character of the streetscape/conservation area.
Review of determination and right of appeal:	Within six months after the date of notification of the decision, a review of this determination can be requested under Division 8.2 of the Act or an appeal to the Land and Environment Court made pursuant to the provisions of Section 8.7 of the Act. A review of determination should be lodged as soon as possible, and preferably no later two months after the date of notification of the decision to enable the review to be completed within the six-month period.

Plans endorsed by the consent authority - please refer to condition A1.

**Endorsed for and on behalf of North Sydney Council** 

15 December 2023	
DATE	

Signature on sebalf of consent authority
DAVID HOY

**TEAM LEADER (ASSESSMENTS)** 

## (i) Conditions

Consent is granted subject to the following conditions imposed pursuant to Section 4.17 of the Environmental Planning and Assessment Act 1979 ("the Act") and the provisions of the Environmental Planning and Assessment Regulation 2021 ("the Regulation") such conditions being reasonable and relevant to the development as assessed pursuant to Section 4.17 of the Act.

#### (ii) Definitions

Unless specified otherwise, words have the same meaning as defined by the *Act*, the *Regulation* and the *Interpretation Act* 1987 as in force at the date of consent.

**Applicant** means the applicant for this consent.

**Approved Plans** means the plans endorsed by Council referenced by this consent as amended by conditions of this consent.

**AS** or **AS/NZS** means Australian Standard® or Australian/New Zealand Standard®, respectively, published by Standards Australia International Limited.

**NCC** means the National Construction Code as published by the Australian Building Codes Board as in force at the date of issue of any *Construction Certificate*.

Council means North Sydney Council.

**Court** means the Land and Environment Court.

Local Native Plants means species of native plant endemic to North Sydney LGA.

Stormwater Drainage System means all works, facilities and documentation relating to:

- The collection of stormwater,
- The retention of stormwater,
- The reuse of stormwater,
- The detention of stormwater,
- The controlled release of stormwater; and
- Connections to easements and public stormwater systems.

**Owner** means the owner of the *site* and successors in title to the *site*.

Owner Builder has the same meaning as in the Home Building Act 1989.

**Principal Certifier** for building or subdivision work means the certifier appointed as the principal certifier for the building work under section 6.6 (1) or for the subdivision work under section 6.12 (1). **Principal Contractor** for building work means the person responsible for the overall coordination and control of the carrying out of the building work.

Note: If any residential building work is involved, the principal contractor must be the holder of a contractor licence under the *Home Building Act 1989*.

**Professional Engineer** has the same meaning as in the NCC.

Public Place has the same meaning as in the Local Government Act 1993.

**Road** has the same meaning as in the Roads Act 1993.

SEE means the final version of the Statement of Environmental Effects lodged by the Applicant.

Site means the land being developed subject to this consent.

NSLEP 2013 means North Sydney Local Environmental Plan 2013

**NSDCP 2013** means North Sydney Development Control Plan 2013

**Work** for the purposes of this consent means:

- the use of land in connection with development,
- the subdivision of land,
- the erection of a building,
- the carrying out of any work,
- the use of any site crane, machine, article, material, or thing,
- the storage of any waste, materials, site crane, machine, article, material, or thing,
- the demolition of a building,
- the piling, piercing, cutting, boring, drilling, rock breaking, rock sawing or excavation of land,
- the delivery to or removal from the site of any machine, article, material, or thing, or
- the occupation of the site by any person unless authorised by an occupation certificate.

Note: **Interpretation of Conditions** - Where there is any need to obtain an interpretation of the intent of any condition this must be done in writing to Council and confirmed in writing by Council.

## **INDEX OF CONDITIONS**

		Page No.
A.	Conditions that Identify Approved Plans	
A1.	Development in Accordance with Plans/Documentation	7
A2.	Plans on Site	7
A3.	No Demolition of Extra Fabric	7
С.	Prior to the Issue of a Construction Certificate (and ongoing, where indicated)	
C1.	Design Changes	7
C2.	Soft Landscaping and Removal of Hard Paving	8
C3.	Dilapidation Report Damage to Public Infrastructure	8
C4.	Sediment Control	9
C5.	Waste Management Plan	9
C6.	Colours, Finishes and Materials (Conservation Areas)	10
C7.	Roofing Materials - Reflectivity	10
C8.	Work Zone	10
C9.	Maintain Property Boundary Alignment Levels	11
C10.	Obtain Driveway Crossing Permit under S.138 Roads Act 1993	11
C11.	Stormwater Disposal - Drainage Plan	12
C12.	Bond for Damage and Completion of Infrastructure Works - Stormwater,	42
C12	Kerb and Gutter, Footpaths, Vehicular Crossing and Road Pavement	13
C13.	Asbestos and Hazardous Material Survey Air Conditioners in Residential Premises	13
C14. C15.	Section 7.12 Contributions	14 14
C15.		15
C10.	Security Deposit/Guarantee Schedule BASIX Certificate	15
D.	Prior to the Commencement of any Works (and continuing where indicated)	
D1.	Public Liability Insurance - Works on Public Land	16
D2.	Commencement of Works' Notice	16
E.	During Demolition and Building Work	
E1.	Parking Restrictions	16
E2.	Road Reserve Safety	16
E3.	Temporary Disposal of Stormwater Runoff	17
E4.	Council Inspection of Public Infrastructure Works	17
E5.	Applicant's Cost of Work on Council Property	17
E6.	Benchmarks	17
E7.	Special Permits	18
E8.	Construction Hours	19
E9.	Out-of-hours' Work Permits	19
E10.	Installation and Maintenance of Sediment Control	20
E11.	Sediment and Erosion Control Signage	20
E12.	Site Amenities and Facilities	20
E13.	Prohibition on Use of Pavements	20
E14.	Plant and Equipment Kept Within Site	20
E15.	Asbestos Removal	21

F.	Prescribed Conditions imposed under EP&A Act and Regulations and other	er relevant Legislation
F1.	National Construction Code	21
F2.	Home Building Act	21
F3.	Appointment of a Principal Certifying Authority (PCA)	22
F4.	Construction Certificate	22
F5.	Occupation Certificate	22
F6.	Critical Stage Inspections	22
F7.	Commencement of Works	22
F8.	Excavation/Demolition	23
F9.	Protection of Public Places	23
F10.	Site Sign	23
G.	Prior to the Issue of an Occupation Certificate	
G1.	Infrastructure Repair and Completion of Works	24
G2.	Damage to Adjoining Properties	24
G3.	Utility Services	24
G4.	BASIX Completion Certificate	24
G5.	Landscaping	24
I.	Ongoing/Operational Conditions	
l1.	Single Occupancy	25

## A. Conditions that Identify Approved Plans

## **Development in Accordance with Plans/Documentation**

A1. The development must be carried out in accordance with the following drawings endorsed with Council's approval stamp and other documentation listed in the table to this clause, or cited by other conditions, and as amended by other conditions of this consent.

Plan No.	Rev.	Description	Prepared by	Dated
DA01	В	Site Plan	City Geeks	28 Sept 2023
DA03	В	Materials and colours	City Geeks	28 Sept 2023
DA04	В	Demolition Plan	City Geeks	28 Sept 2023
DA05	В	Proposed Plans	City Geeks	28 Sept 2023
DA06	В	Roof Plan and Drainage	City Geeks	28 Sept 2023
DA08	В	East Elevation	City Geeks	28 Sept 2023
DA09	В	North/South Elevations & Short Sections	City Geeks	28 Sept 2023
DA11	В	Landscape Plan	City Geeks	28 Sept 2023

(Reason:

To ensure that the form of the development undertaken is in accordance with the determination of Council, Public Information)

#### Plans on Site

A2. A copy of all plans endorsed with Council's approval stamp, specifications and documents (including the plans, specifications and documents submitted and approved with the Construction Certificate) must be kept on site at all times so as to be readily available for perusal by any officer of Council or the Principal Certifier.

All documents kept on site in accordance with this condition must be provided to any officer of the Council or the Principal Certifier upon their request.

(Reason:

To ensure that the form of the development undertaken is in accordance with the determination of Council, Public Information and to ensure ongoing compliance)

## No Demolition of Extra Fabric

A3. Alterations to, and demolition of the existing building shall be limited to that documented on the approved plans.

(Reason: To ensure compliance with the approved development)

C. Prior to the Issue of a Construction Certificate (and ongoing, where indicated)

#### **Design Changes**

- C1. The plans referred to in Condition A1 are to be amended to incorporate the following design changes:
  - The height of the garage is to be reduced by 400mm overall to achieve a maximum RL 95.35 to the ridge. This is to be achieved through reduction of the floor to ceiling heights and ridge height. The proposed roof pitch is to be retained;

- The width of the southern dormer to the garage is to be reduced by 2.0metres and amended to enable the adjusted stair riser heights and floor levels required above;
- The width of the northern dormer to Hayberry Lane is to be reduced to have a maximum width of 3.6 metres and minimum inset from the eastern and western edges of the roof by 1.2 metres.
- A landscape planter bed with minimum dimensions 400mm x 1.2m is to be provided on the eastern and western sides of the driveway crossing.

The Certifying Authority is to be satisfied that the amendments required by this condition are incorporated in the Construction Certificate Drawings.

(Reason:

(Reason:

To reduce overshadowing and reduce the impact of oversized dormer to Hayberry Lane and the overall bulk of the structure)

## Soft Landscaping and Removal of Hard Paving

C2. A minimum of 5 square metres of paving within the rear courtyard area is to be removed from the site and additional soft landscaping provided within planter beds. Landscaping is to be provided within these planter beds consisting of a minimum of 3 screening plant species capable of attaining a mature height of 3 metres within a minimum pot size of 45 litres.

The Certifying Authority is to be satisfied that landscaping capable of complying with this condition is shown on the Construction Certificate Plans and is installed prior to the issue of the Occupation Certificate.

To reduce hard paving and provide additional soft landscaping within the site)

## **Dilapidation Report Damage to Public Infrastructure**

C3. A dilapidation survey and report (including photographic record) must be prepared by a suitably qualified consultant which details the predeveloped condition of the existing public infrastructure in the vicinity of the development site. Particular attention must be paid to accurately recording any predeveloped damaged areas so that Council is fully informed when assessing any damage to public infrastructure caused as a result of the development. A copy of the dilapidation survey and report is to be submitted to the Principal Certifier for approval prior to the issue of any Construction Certificate.

The developer may be held liable for all damage to public infrastructure in the vicinity of the site, where such damage is not accurately recorded and demonstrated as pre-existing under the requirements of this condition.

The developer shall bear the cost of carrying out works to restore all public infrastructure damaged as a result of the carrying out of the development, and no occupation of the development shall occur until damage caused as a result of the carrying out of the development is rectified.

A copy of the dilapidation survey and report must be lodged with North Sydney Council by the Principal Certifier with submission of the Construction Certificate documentation.

(Reason: To record the condition of public infrastructure prior to the commencement of construction)

#### **Sediment Control**

C4. Where construction or excavation activity requires the disturbance of the soil surface or existing vegetation, erosion and sediment control techniques, as a minimum, are to be in accordance with the publication *Managing Urban Stormwater: Soils and Construction* (4th Edition, Landcom, 2004) commonly referred to as the "Blue Book" or a suitable and effective alternative method.

An Erosion and Sediment Control Plan must be prepared and submitted to the Principal Certifier for approval prior to the issue of any Construction Certificate and prior to any works commencing. The Erosion and Sediment Control Plan must be consistent with the Blue Book and disclose:

- a) All details of drainage to protect and drain the site during the construction processes;
- b) All sediment control devices, barriers and the like;
- c) Sedimentation tanks, ponds or the like;
- d) Covering materials and methods; and
- e) A schedule and programme of the sequence of the sediment and erosion control works or devices to be installed and maintained.
- f) Methods for the temporary and controlled disposal of stormwater during construction.

All works must be undertaken in accordance with the approved Sediment Control plan.

The Principal Certifier must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To protect the environment from the effects of sedimentation and erosion from development sites)

## **Waste Management Plan**

- C5. A Waste Management Plan is to be submitted for approval by the Principal Certifier prior to the issue of any Construction Certificate. The plan must include, but not be limited to:
  - a) The estimated volume of waste and method of disposal for the construction and operation phases of the development;
  - b) The design of the on-site waste storage and recycling area; and
  - c) Administrative arrangements for waste and recycling management during the construction process.

The approved Waste Management Plan must be complied with at all times in the carrying out of the development.

(Reason: To encourage the minimisation of waste and recycling of building waste)

## **Colours, Finishes and Materials (Conservation Areas)**

C6. The finishes, materials and exterior colours shall be complementary to the architectural style of the original building and sympathetic to the character of the Conservation Area. A schedule of finishes, materials and external colours shall be submitted to the Principal Certifier for approval prior to the issue of any Construction Certificate. The Principal Certifier must ensure that the building plans and specifications submitted fully satisfy the requirements of this condition prior to the release of the Construction Certificate.

(Reason: To ensure that the completed colours, finishes and materials are complementary to

the Conservation Area.)

#### **Roofing Materials - Reflectivity**

C7. Roofing materials must be factory pre-finished with low glare and reflectivity properties to be compatible with the colours of neighbouring buildings. The selected roofing material must not cause a glare nuisance or excessive reflectivity to adjoining or nearby properties. Plans and specifications which comply with this condition must be submitted to the Principal Certifier for approval prior to the issue of any Construction Certificate. The Principal Certifier must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To ensure that excessive glare or reflectivity nuisance from roofing materials does not

occur as a result of the development)

## **Work Zone**

C8. If a Work Zone is required a Work Zone permit is to be obtained from Council prior to the issue of any Construction Certificate.

Note: For major development an application for work zone permit must be considered by the North Sydney Local Traffic Committee.

Work Zones are provided specifically for the set down and pick up of materials and not for the parking of private vehicles associated with the site. Works Zones will generally not be approved where there is sufficient space on-site for the setting down and picking up of goods being taken to or from a construction site. If the Works Zone is approved by the Committee, the Applicant must obtain a written copy of the related resolution from the North Sydney Local Traffic Committee and submit a copy of this to the Principal Certifier to enable issue of the Construction Certificate.

Where approval of the 'Work Zone' is given by the Committee, the requirements of the Committee, including installation of the necessary 'Work Zone' signage and payment of any fees, must occur prior to commencement of any works on the site. Further, at the expiration of the Work Zone approval, the developer is required to remove the Work Zone signs and reinstate any previous signs, all at the developer's cost. The requirements imposed by the Committee on the Work Zone permit (or permits) must be complied with at all times.

(Reason: Amenity and convenience during construction)

## **Maintain Property Boundary Alignment Levels**

C9. Except where otherwise approved by Council, the property boundary alignment levels must match the levels which existed prior to the commencement of works. Plans and specifications which document existing and proposed levels adjacent to the site boundaries and which comply with the requirements of this condition must be submitted to the Principal Certifier for approval prior to the issue of any Construction Certificate.

The Principal Certifier must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To ensure interface between property and public land remains uniform)

## Obtain Driveway Crossing Permit under S.138 Roads Act 1993

C10. A driveway crossing and roads infrastructure works permit to suit the approved off-street parking facilities must be granted by the Council prior to the issue of any Construction Certificate. In order to obtain a permit under S.138 of the Roads Act 1993, an application must be made to Council on the 'Vehicular Access Application' form with payment of the adopted assessment/inspection fees. Council will require civil design construction drawings and certification from the applicant's Civil Engineer to verify design details and enable issue of the permit. The requirements of the permit must be complied with at all times.

The civil design drawings must include the following at a minimum:

- a) the vehicular access way must comply with AS 2890.1 and Council's current Vehicular Access Application Guidelines and Specification (gutter bridges not permitted) to ensure that a B85 vehicle will not scrape/strike the surface of the carriageway, layback, vehicular crossing or parking floor;
- b) the width of the vehicular layback must be full property frontage on Emmett Lane frontage i.e., 6.13 meters (including wings),
- c) the wings of the driveway crossing must marry smoothly with the adjacent kerb and no trip hazards are to be present in the footpath area.
- d) the vehicular crossover must be set square to the kerb,
- e) the crossing (between the layback and the property boundary) must be placed on a single straight grade of approximately 4.5%, falling to the back of the layback,
- f) the gutter levels and boundary footpath levels must match the existing levels and shall not be altered,
- g) new footpath, kerb gutter and road shoulder 0.60 m wide strip adjacent to all new gutter works) works are required for the full property frontage,
- h) the works will require reconstruction of the carriageway shoulder extending out 600mm from the gutter lip in AC10 50mm thick, adjacent to all new gutter works, layback, kerb/gutter,
- i) any twisting of driveway access must occur entirely within the subject property,

- j) all inspection openings and utility services must be adjusted to match the proposed driveway levels,
- k) sections along the centreline and extremities are required at a scale of 1:50 to be taken from the centreline of the roadway through to the parking area itself and must include all changes of grade and levels both existing and proposed,
- a longitudinal section along the gutter line at a scale of 1:50 showing how it is intended to blend the vehicular crossing with the existing kerb and gutter,
- m) a longitudinal section along the footpath property boundary at a scale of 1:50 is required,
- n) the sections must show the calculated clearance to the underside of any overhead structure,

The permit must be granted by Council prior to the issue of any Construction Certificate.

All driveway and infrastructure works on the road reserve must be undertaken in accordance with the terms of the permit issued by Council. Inspections by Council will be required as specified. The Principal Certifier issuing the Construction Certificate must ensure that the permit issued by Council is obtained and referenced on and accompanies the Construction Certificate issued.

(Reason: To facilitate appropriate vehicular access to private sites, without disruption to pedestrian and vehicular traffic)

## Stormwater Disposal - Drainage Plan

- C11. Prior to the issue of any Construction Certificate, site drainage plans must be prepared by a licensed plumber or drainage engineer. The site drainage plans must —be designed in accordance with the following criteria:
  - a) compliance with NCC drainage requirements and current Australian Standards and guidelines;
  - b) stormwater runoff and subsoil drainage generated by the approved development must be conveyed in a controlled manner by gravity to [INSERT];
  - c) new pipelines within council land shall be hot dipped galvanised steel hollow section with a minimum wall thickness of 4.0 millimetres and a section height of 100 millimetres;
  - d) the design and installation of the Rainwater Tanks shall comply with BASIX and Sydney Water requirements. Overflow from tank shall be connected by gravity to the stormwater disposal system; and
  - e) prevent any stormwater egress into adjacent properties by creating physical barriers and surface drainage interception.

Drainage plans and specifications which comply with this condition must be submitted to the Principal Certifier for approval prior to the issue of any Construction Certificate. The Principal Certifier must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: Proper disposal of stormwater)

Bond for Damage and Completion of Infrastructure Works - Stormwater, Kerb and Gutter, Footpaths, Vehicular Crossing and Road Pavement

- C12. Prior to the issue of any Construction Certificate, security deposit or bank guarantee must be provided to Council to the sum of \$5,000.00 to be held by Council for the payment of cost for any/all of the following:
  - a) making good any damage caused to any property of the Council as a consequence of the doing of anything to which this consent relates,
  - b) completing any public work (such as road work, kerbing and guttering, footway construction, stormwater drainage and environmental controls) required in connection with this consent
  - c) remedying any defects in any such public work that arise within 6 months after the work is completed.
  - d) Council reserves the right to retain all bonds on infrastructure works relating to the completion of required Infrastructure work for a 12-month defect liability period. Council may elect to provide a lesser period for minor residential work.

The security required by this condition and in the schedule contained later in these conditions must be provided by way of a deposit with the Council; or other such guarantee that is satisfactory to Council (such as a bank guarantee). Any guarantee provided as security must name North Sydney Council as the nominated beneficiary and must not be subject to an expiry date.

The security will be refundable following the expiration of six months from the issue of any final Occupation Certificate or completion of public work required to be completed (whichever is the latest) but only upon inspection and release by Council's Development Engineers or Manager of Development Services.

Council shall have full authority to make use of the bond for such restoration works as deemed necessary by Council in circumstances including the following:

- where the damage constitutes a hazard in which case Council may make use of the security immediately;
- the applicant has not repaired or commenced repairing damage within 48 hours of the issue by Council in writing of instructions to undertake such repairs or works;
- works in the public road associated with the development are to an unacceptable quality; and
- the Principal Certifier must ensure that security is provided to North Sydney Council prior to issue of any Construction Certificate.

(Reason: To ensure appropriate security for works on public land and an appropriate quality for new public infrastructure)

## **Asbestos and Hazardous Material Survey**

C13. A report must be prepared by a suitably qualified person in relation to the existing building fabric to be demolished and/or disturbed identifying the presence or otherwise of asbestos contamination and, if asbestos contamination is present, making recommendations as to the work required to safely address the contamination. Any demolition works or other works identified in the report as having to be carried out must be carried out in accordance with the recommendations of the report and the following:

- a) the removal of asbestos must be undertaken by a WorkCover licensed contractor;
- b) all removal must be in strict accordance with the requirements of the WorkCover Authority in relation to the removal, handling and disposal of material containing asbestos and any Work Safe Australia requirements.
- c) during the removal of any asbestos a sign stating "DANGER ASBESTOS REMOVAL IN PROGRESS" must be erected in a visible position at the boundary of the site; and
- d) Waste disposal receipts must be provided to the Principal Certifier as proof of correct disposal of asbestos laden waste.

The report must be submitted to the Principal Certifier for approval prior to the issue of any Construction Certificate. The Principal Certifier must ensure that the report, and other plans, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To ensure the long-term health of workers on site and occupants of the building is not put at risk unnecessarily)

#### Air Conditioners in Residential Premises

- C14. The use of any air conditioner installed on the premises must comply with the requirements of the Protection of the Environment Operations (Noise Control) Regulations 2017 and State Environmental Planning Policy (Infrastructure) 2007 and must not:
  - (a) emit a noise that is audible within a habitable room in any affected residence (regardless of whether any door or window to that room is open);
    - (i) before 8.00am and after 10.00pm on any Saturday, Sunday or Public Holiday; or
    - (ii) before 7.00am or after 10.00pm on any other day
  - (b) cause an LAeq(15min) which exceeds the RBL background noise level by more than 5dB when measured at the boundary of any affected residence. The modifying factor adjustments in Section 4 of the EPA Noise Policy for Industry 2017 will be applied.

"affected residence" includes residential premises (including any lot in the strata scheme or another strata scheme), premises for short-term accommodation and hospitals.

"boundary" includes any window or elevated window of an affected residence.

Terms in this condition have the same meaning as in the Noise Guide for Local Government and the Noise Policy for Industry published by the NSW Environment Protection Authority.

(Reason: To maintain residential amenity)

## **Section 7.12 Development Contributions**

C15. A monetary contribution pursuant to the provisions of Section 7.12 of *the Environmental Planning and Assessment Act 1979* is to be paid to Council, in accordance with the North Sydney Council's Contribution Plan, to provide for local infrastructure improvements.

Based on the cost of development at the date of determination, the total contribution payable to Council is \$\$2,750.00.

#### Indexation

The monetary contribution required under this consent will be indexed between the date of the grant of the consent and the date on which the contribution is paid the time of payment in accordance with quarterly movements in the Consumer Price Index (All Groups Index) for Sydney as published by the Australian Bureau of Statistics.

#### **Timing of Payment**

The contribution must be paid to Council prior to issue of any Construction Certificate for any work approved by this consent.

A copy of the North Sydney Contribution Plan can be viewed at North Sydney Council's Customer Service Centre, 200 Miller Street, North Sydney or downloaded via Council's website at www.north sydney.nsw.gov.au.

To provide for local infrastructure identified in the North Sydney Council Local (Reason:

Contributions Plan 2020)

## Security Deposit/Guarantee Schedule

C16. All fees and security deposits/ guarantees in accordance with the schedule below must be provided to Council prior to the issue of any Construction Certificate:

Security Deposit/Guarantee	Amount (\$)
Infrastructure Damage Bond	\$5,000.00
TOTAL BONDS	\$5,000.00

Note: The following fees applicable

Fees	
Local Infrastructure Contributions:	\$2,750.00
TOTAL FEES	\$2,750.00

The security required by the above schedule must be provided by way of a deposit with the Council; or other such guarantee that is satisfactory to Council (such as a bank guarantee). Any guarantee provided as security must name North Sydney Council as the nominated beneficiary and must not be subject to an expiry date.

(Reason: Compliance with the development consent)

## **BASIX Certificate**

C17. Under clause 75 of the Environmental Planning and Assessment Regulation 2021, it is a condition of this development consent that all the commitments listed in BASIX Certificate No. A474623 02 for the development are fulfilled. Plans and specifications complying with this condition must be submitted to the Principal Certifier for approval prior to the issue of the relevant Construction Certificate. The Principal Certifier must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To ensure the proposed development will meet the Government's requirements for

sustainability and statutory requirements)

## D. Prior to the Commencement of any Works (and continuing where indicated)

## **Public Liability Insurance - Works on Public Land**

D1. Any person or contractor undertaking works on public land must take out Public Risk Insurance with a minimum cover of \$20 million in relation to the occupation of public land and the undertaking of approved works within Council's road reserve or public land, as approved by this consent. The Policy is to note and provide protection/full indemnification for North Sydney Council, as an interested party. A copy of the Policy must be submitted to Council prior to commencement of any works. The Policy must be valid for the entire period that the works are being undertaken.

(Note: Applications for hoarding permits, vehicular crossings etc will require evidence of insurance upon lodgement of the application.)

(Reason: To ensure the community is protected from the cost of any claim for damages arising from works on public land)

# Commencement of Works' Notice

D2. Building work, demolition or excavation in accordance with this development consent must not be commenced until the developer has given at least two days' notice to North Sydney Council of the person's intention to commence building work, demolition or excavation in accordance with this development consent.

(Reason: To ensure appropriate safeguarding measures are in place prior to the commencement of any building work, demolition or excavation)

E. During Demolition and Building Work

## **Parking Restrictions**

E1. Existing public parking provisions in the vicinity of the site must be maintained at all times during works. The placement of any barriers, traffic cones, obstructions or other device in the road shoulder or kerbside lane is prohibited without the prior written consent of Council. Changes to existing public parking facilities/restrictions must be approved by the North Sydney Local Traffic Committee. The Developer will be held responsible for any breaches of this condition and will incur any fines associated with enforcement by Council regulatory officers.

(Reason: To ensure that existing kerbside parking provisions are not compromised during works)

#### **Road Reserve Safety**

E2. All public footways and roadways fronting and adjacent to the site must be maintained in a safe condition at all times during the course of the development works, with no obstructions caused to the said footways and roadways. Construction materials and plant must not be stored in the road reserve without approval of Council. A safe pedestrian circulation route and a pavement/route free of trip hazards must be maintained at all times on or adjacent to any public access ways fronting the construction site.

Where public infrastructure is damaged, repair works must be carried out in when and as directed by Council officers (at full Developer cost). Where pedestrian circulation is diverted on to the roadway or verge areas, clear directional signage and protective barricades must be installed in accordance with AS1742-3 (1996) "Traffic Control Devices for Work on Roads". If pedestrian circulation is not satisfactorily maintained across the site frontage, and action is not taken promptly to rectify the defects, Council may undertake proceedings to stop work.

(Reason: Public Safety)

## **Temporary Disposal of Stormwater Runoff**

E3. During construction, stormwater runoff must be disposed in a controlled manner that is compatible with the erosion and sediment controls on the site. Immediately upon completion of any impervious areas on the site (including roofs, driveways, paving) and where the final drainage system is incomplete, the necessary temporary drainage systems must be installed to reasonably manage and control runoff as far as the approved point of stormwater discharge. Such ongoing measures must be to the satisfaction of the Principal Certifier.

(Reason: Stormwater control during construction)

## **Council Inspection of Public Infrastructure Works**

- E4. During the works on public infrastructure reverting to Council's care and control, Council's development engineer may undertake inspections of the works at the following hold points:
  - a) Formwork for layback, kerb/gutter, footpath, etc.

All works must proceed in accordance with Roads Act 1993 approvals or other permits relating to roads issued by Council. A minimum of 48 hours' notice must be given to Council to book an inspection. Work must not proceed until the works or activity covered by the inspection is approved.

(Reason: To ensure quality of construction joints and connections in the drainage system)

#### **Applicant's Cost of Work on Council Property**

E5. The applicant or the person, company or other entity that is acting upon this consent, must bear the cost of all works associated with the development that occurs on Council's property, including the restoration of damaged areas.

(Reason: To ensure the proper management of public land and funds)

#### **Benchmarks**

E6. All permanent survey markers must be retained, undamaged, and not relocated.

(Reason: Protection of existing environmental infrastructure and community assets)

## **Special Permits**

E7. Unless otherwise specifically approved in writing by Council, all works, processes, storage of materials, loading and unloading associated with the development must occur entirely on the property.

The developer, owner or builder may apply for specific permits available from Council's Customer Service Centre for the undermentioned activities on Council's property. In the event that a permit is granted by Council for the carrying out of works, processes, storage of materials, loading and unloading associated with the development on Council's property, the development must be carried out in accordance with the requirements of the permit. A minimum of forty-eight (48) hours' notice is required for any permit:

#### 1) On-street mobile plant

E.g., cranes, concrete pumps, cherry-pickers, etc., - restrictions apply to the hours of operation, the area of operation, etc. Separate permits are required for each occasion and each piece of equipment. It is the developer's, owner's and builder's responsibilities to take whatever steps are necessary to ensure that the use of any equipment does not violate adjoining property owner's rights.

(Reason: Proper management of public land)

## 2) Hoardings

Permits are required to erect Class A and Class B hoardings. If an 'A' Class hoarding is to alienate a section of Council's property, that section will require a permit for the occupation of Council's property.

(Reason: Proper management of public land)

## 3) Storage of building materials and building waste containers (skips) on Council's property

Permits to utilise Council property for the storage of building materials and building waste containers (skips) are required for each location. Failure to obtain the relevant permits will result in the building materials or building waste containers (skips) being impounded by Council with no additional notice being given. Storage of building materials and waste containers on open space reserves and parks is prohibited.

(Reason: Proper management of public land)

#### 4) Kerbside restrictions, construction zones

Attention is drawn to the existing kerbside restrictions adjacent to the development. Should alteration of existing kerbside restrictions be required, or the provision of a construction zone, the appropriate application must be made and the fee paid to Council. Alternatives to such restrictions may require referral to Council's Traffic Committee and may take considerable time to be resolved. An earlier application is suggested to avoid delays in construction programs.

(Reason: Proper management of public land)

#### **Construction Hours**

E8. Construction activities and works approved under this consent must be restricted to within the hours stipulated in the following table:

Standard Construction Hours				
Location Day Hours				
All zones	Monday - Friday	7.00 am - 5.00 pm		
(Excl. E2 Commercial Centre	Saturday	8.00 am - 1.00 pm		
MU1 Mixed-use	Sunday, Public holiday	No work permitted		

Construction activities for development approved under this consent must be carried out in accordance with the standard construction hours above, the EPA Noise Policy for Industry 2017 and any Construction Noise Management Plan required under this consent.

In the event of breach to the approved hours of construction Council take may take enforcement action under Part 9 of the EP&A Act 1979 and in accordance with Council's adopted Compliance and Enforcement Policy.

(Reason:

To ensure that works do not interfere with reasonable amenity expectations of residents and the community)

#### **Out-of-hours' Work Permits**

E9. Where it is necessary for works to occur outside those hours allowed by these conditions, an application may be made to Council's Customer Services Centre for a permit to carry out works outside of the approved hours. If a permit is issued the works approved must be carried out in accordance with any requirements specified in the permit. Permits will only be approved if **public safety is at risk**. Applications which seek a variation to construction hours solely to benefit the developer will require the lodgement and favourable determination of a modification application pursuant to the provisions of Section 4.55 of the Environmental Planning and Assessment Act 1979.

## Notes:

- 1) Failure to obtain a permit for work outside of the approved hours will result in on the spot fines being issued, or Council pursuing any action required (including legal proceedings) to have the out of hours work cease, without prior warning.
- 2) Applications for out of hour's works should be lodged with Council no later than seven (7) calendar days prior to the date of the intended works.
- 3) Examples of activities for which permits may be granted include:
  - the erection of awnings,
  - footpath, road and other infrastructure works which cannot be carried out for public convenience reasons within normal hours,
  - the erection and removal of hoardings and site cranes, and
  - craneage of materials which cannot be done for public convenience reasons within normal working hours.
- 4) Examples of activities for which permits WILL NOT be granted include:
  - extended concrete pours
  - works which are solely to convenience the developer or client, and
  - catch up works required to maintain or catch up with a construction schedule.

5) Further information on permits can be obtained from the Council website at <a href="https://www.north.sydney.nsw.gov.au">www.north.sydney.nsw.gov.au</a>.

(Reason: To ensure that works do not interfere with reasonable amenity expectations of

residents and the community)

#### Installation and Maintenance of Sediment Control

E10. Erosion and sediment controls must be installed and maintained at all times in accordance with the Sediment and erosion control plan submitted and approved with the Construction Certificate.

Erosion and sediment measures must be maintained in accordance with the publication *Managing Urban Stormwater: Soils and Construction* (4th Edition, Landcom, 2004), commonly referred to as the "Blue Book" and can only be removed when development activities have been completed and the site fully stabilised.

(Reason: To protect the environment from the effects of sedimentation and erosion from

development sites)

## **Sediment and Erosion Control Signage**

E11. A durable sign must be erected during building works in a prominent location on site, warning of penalties should appropriate erosion and sedimentation control devices not be maintained. A sign of the type referred to in this condition is available from Council.

(Reason: To protect the environment from the effects of sedimentation and erosion from

development sites)

## **Site Amenities and Facilities**

E12. Where work involved in the erection and demolition of a building is being carried out, amenities which satisfy applicable occupational health and safety and construction safety regulations, including any WorkCover Authority requirements, must be provided and maintained at all times. The type of workplace determines the type of amenities required.

Further information and details can be obtained from the Internet at www.workcover.nsw. gov.au.

(Reason: To ensure the health and safety of the community and workers on the site)

## **Prohibition on Use of Pavements**

E13. Building materials must not be placed on Council's footpaths, roadways, parks or grass verges, (unless a permit is obtained from Council beforehand). A suitable sign to this effect must be erected adjacent to the street alignment.

(Reason: To ensure public safety and amenity on public land)

## **Plant and Equipment Kept Within Site**

E14. All plant and equipment used in the undertaking of the development/ works, including concrete pumps, wagons, lifts, mobile cranes, hoardings etc, must be situated within the boundaries of the site (unless a permit is obtained from Council beforehand) and so placed that all concrete slurry, water, debris and the like must be discharged onto the building site, and is to be contained within the site boundaries.

Details of Council requirements for permits on public land for standing plant, hoardings, storage of materials and construction zones and the like are available on Council's website at <a href="www.northsydney.nsw.gov.au">www.northsydney.nsw.gov.au</a>.

(Reason: To ensure public safety and amenity on public land)

#### **Asbestos Removal**

E15. All demolition works involving the removal and disposal of asbestos cement must only be undertaken by contractors who hold a current WorkCover Asbestos or "Demolition Licence" and a current WorkCover "Class 2 (Restricted) Asbestos Licence and removal must be carried out in accordance with National Occupational Health and Safety Commission.

(Reason: To ensure works are carried out in accordance with relevant WorkCover requirements)

F. Prescribed Conditions imposed under EP&A Act and Regulations and other relevant Legislation

## **National Construction Code**

F1. All building work must be carried out in accordance with the provisions of the National Construction Code.

(Reason: Prescribed - Statutory)

## **Home Building Act**

- F2. 1) Building work that involves residential building work (within the meaning and exemptions provided in the Home Building Act 1989) for which the *Home Building Act* 1989 requires there to be a contract of insurance under Part 6 of that Act must not be carried out unless the Principal Certifier for the development to which the work relates has given North Sydney Council written notice of the contract of insurance being issued and of the following:
  - a) in the case of work for which a principal contractor is required to be appointed:
    - i) the name and licence number of the principal contractor, and
    - ii) the name of the insurer by which the work is insured under Part 6 of that Act, or
  - (b) in the case of work to be done by an owner-builder:
    - (i) the name of the owner-builder, and
    - (ii) if the owner-builder is required to hold an owner-builder permit under that Act, the number of the owner-builder permit.
  - If arrangements for doing residential building work are changed while the work is in progress such that the information submitted to Council in accordance with this condition is out of date, work must cease, and no further work may be carried out unless the Principal Certifier for the development to which the work relates (not being the Council), has given the Council written notice of the updated information.

Note: A certificate purporting to be issued by an approved insurer under Part 6 of the Home Building Act 1989 that states that a person is the holder of an insurance policy issued for the purposes of that Part is, for the purposes of this clause, sufficient evidence that the person has complied with the requirements of that Part.

(Reason: Prescribed - Statutory)

## Appointment of Principal Certifier (PC)

F3. Building work, **demolition** or excavation in accordance with the development consent must not be commenced until the developer has appointed a Principal Certifier for the building work in accordance with the provisions of the EP&A Act and its Regulations.

(Reason: Statutory; To ensure appropriate safeguarding measures are in place prior to the

commencement of any building work, demolition or excavation)

#### **Construction Certificate**

F4. Building work, demolition or excavation in accordance with the development consent must not be commenced until a Construction Certificate for the relevant part of the building work has been issued in accordance with the provisions of the EP&A Act and its Regulations.

(Reason: Statutory; To ensure appropriate safeguarding measures are in place prior to the

commencement of any building work, demolition or excavation)

## **Occupation Certificate**

F5. A person must not commence occupation or use of the whole or any part of a new building (new building includes an altered portion of, or an extension to, an existing building) unless an Occupation Certificate has been issued in relation to the building or part. Only the Principal Certifier appointed for the building work can issue an Occupation Certificate.

(Reason: Statutory)

## **Critical Stage Inspections**

F6. Building work must be inspected by the Principal Certifier on the critical stage occasions prescribed by the EP&A Act and its Regulations, and as directed by the appointed Principal Certifier.

(Reason: Statutory)

#### **Commencement of Works' Notice**

F7. Building work, demolition or excavation in accordance with this development consent must not be commenced until the developer has given at least two days' notice to North Sydney Council of the person's intention to commence the erection of the building.

(Reason: Statutory; To ensure appropriate safeguarding measures are in place prior to the

commencement of any building work, demolition or excavation)

#### **Excavation/Demolition**

- F8. 1) All excavations and backfilling associated with the erection or demolition of a building must be executed safely and in accordance with appropriate professional standards.
  - 2) All excavations associated with the erection or demolition of a building must be properly guarded and protected to prevent them from being dangerous to life or property.
  - 3) Demolition work must be undertaken in accordance with the provisions of AS2601- Demolition of Structures.

(Reason: To ensure that work is undertaken in a professional and responsible manner and protect adjoining property and persons from potential damage)

## **Protection of Public Places**

- F9. 1) A hoarding and site fencing must be erected between the work site and adjoining public place.
  - 2) If necessary, an awning is to be erected, sufficient to prevent any substance from, or in connection with, the work falling into the public place.
  - 3) The work site must be kept lit between sunset and sunrise if it is likely to be hazardous to persons in the public place.
  - 4) Any such hoarding, fence or awning is to be removed when the work has been completed.
  - 5) No access across public reserves or parks is permitted.

Note: Prior to the erection of any temporary fence or hoarding over property owned or managed by Council, written approval must be obtained. Any application needs to be accompanied by plans indicating the type of hoarding and its layout. Fees are assessed and will form part of any approval given. These fees must be paid prior to the approval being given. Approval for hoardings will generally only be given in association with approved building works, maintenance or to ensure protection of the public. An application form for a Hoarding Permit can be downloaded from Council's website.

(Reason: To ensure public safety and the proper management of public land)

## Site Sign

- F10. 1) A sign must be erected in a prominent position on the site
  - a) stating that unauthorised entry to the work site is prohibited;
  - b) showing the name of the principal contractor (or person in charge of the work site), and a telephone number at which that person may be contacted at any time for business purposes and outside working hours; and
  - c) showing the name, address and telephone number of the Principal Certifier for the work.

2) Any such sign must be maintained while to building work or demolition work is being carried out but must be removed when the work has been completed.

(Reason: Prescribed - Statutory)

## G. Prior to the Issue of an Occupation Certificate

## **Infrastructure Repair and Completion of Works**

- G1. Prior to the issue of any Occupation Certificate any and all works relating to the development:
  - a. in the road reserve must be fully completed; and
  - b. to repair and make good any damaged public infrastructure caused as a result of any works relating to the development (including damage caused by, but not limited to, delivery vehicles, waste collection, contractors, sub-contractors, concrete vehicles) must be fully repaired;

to the satisfaction of Council Engineers at no cost to Council. Council's development engineer must be contacted to arrange inspections of the completed works in the Public Domain.

(Reason: Maintain quality of Public assets)

## **Damage to Adjoining Properties**

G2. All precautions must be taken to prevent any damage likely to be sustained to adjoining properties. Adjoining owner property rights and the need for owner's permission must be observed at all times, including the entering onto land for the purpose of undertaking works.

(Reason: To ensure adjoining owner's property rights are protected)

## **Utility Services**

G3. All utility services shall be adjusted to the correct levels and/or location/s required by this consent, prior to issue of an occupation certificate. This shall be at no cost to Council.

(Reason: To ensure compliance with the terms of this consent)

## **BASIX Completion Receipt**

G4. In accordance with Section 45 of the Environmental Planning and Assessment (Development Certification and Fire Safety) Regulation 2021, prior to issuing a final occupation certificate the Principal Certifier must provide a BASIX completion receipt.

(Reason: To ensure compliance with the Regulations)

## Landscaping

G5. The landscaping shown in the approved plans, including new planting within the rear courtyard and adjacent to the driveway, and otherwise required by this consent must be installed prior to the issue of the Occupation Certificate.

(Reason: To ensure compliance)

## I. Ongoing/Operational Conditions

## **Single Occupancy**

11. Nothing in this consent authorises the use of the premises other than for a single occupancy.

(Reason: To ensure compliance with the terms of this consent)