Original signed by Luke Donovan on 9/4/19 Date determined: 9/4/19

Date determined: 9/4/19 Date operates: 9/4/19 Date lapses: 9/4/24

Nick Hibberd Architect PO Box 46 CAMMERAY NSW 2062

> D422/18 LD (CIS)

# ENVIRONMENTAL PLANNING AND ASSESSMENT ACT, 1979 AS AMENDED NOTICE OF DETERMINATION – Approval

Development Application Number:	422/18
Land to which this applies:	106 Bank Street, North Sydney Lot No.: 1, DP: 730270
Applicant:	Nick Hibberd Architect
Proposal:	Substantial alterations and additions to dwelling house including first floor addition with balcony, flat roof, solar cells, internal reconfigurations, shade cloth structure over driveway and associated works.
Determination of Development Application:	Subject to the provisions of Section 4.17 of the Environmental Planning and Assessment Act 1979, approval has been granted subject to conditions in the notice of determination.
Date of Determination:	9 April 2019
Reason for approval	The development application has been assessed against the North Sydney Local Environmental Plan 2013, North Sydney Development Control Plan 2013 and the relevant State Planning Policies and generally found to be satisfactory.  The proposal is compliant with the building height control in NSLEP 2013. The proposal does not seek to alter the existing ground floor side setbacks and the proposed first floor setbacks are compliant with the minimum setbacks specified in NSDCP 2013.

The proposed development is considered to maintain a reasonable level of solar access to the property at No. 102 Bank Street. Whilst the proposed upper level addition will result in some additional overshadowing, the overshadowing is caused by elements of the addition that are compliant with Council's building height envelope controls. Moreover, the additional overshadowing is to a bedroom/study which is not classified as a primary living space in Part B, Section 1.3.7 in NSDCP 2013.

Privacy screens are indicated on a number of the ground and first floor southern windows. A condition is recommended that a privacy screen is installed to the enlarged ground floor southern kitchen window to ensure reasonable privacy is maintained with the rear entertaining area at No. 102 Bank Street.

The application proposes a shade cloth structure over the right of way that whilst benefiting the subject site is burdened by 108 Bank Street. It is recommended that no consent is given for this structure under this application. Noting that the application also proposes the widening of the existing garage entry to 2810mm and therefore this existing garage would be compliant with 2890.1:2004 Off Street parking.

The existing site coverage is 58.5%, the proposed site coverage is 59.7% (not including the proposed carport structure as it is located on another site). The proposal essentially involves a 1.2% (3.6m2) increase in site coverage with the addition of the new awning over the redesigned front entry. Whilst it does result in a further noncompliance with the maximum numerical control, it is considered to satisfy the objectives of the control as it would not increase the density of the development, would not result in an overdevelopment of the site, materially alter the character of the neighbourhood or reduce opportunities for landscaped area.

Council's Conservation Planner raises no objection to the proposed works on heritage ground, subject to standard conditions of consent.

Having regard to the provisions of Section 4.15 of the EP&A Act 1979 (as amended) the application is considered to be satisfactory and is recommended for **approval** subject to conditions of consent.

Consent to operate from:	9 April 2019
Consent will lapse on:	9 April 2024
Period of Consent	Subject to Section 4.20 of the Act, this consent becomes effective and operates from the date listed above. The consent lapses five years after the date of consent in accordance with Section 4.53 of the Act and cannot be extended. To activate this consent, works must physically commence onsite by 9 April 2024.
How community views were taken into account:	The application was notified to surrounding properties and the Union/Edward Precinct between 21 December 2018 and 25 January 2019. Three (3) submissions were received against the application. The issues raised in the submissions are summarised and addressed in the delegated report and, where appropriate, conditions imposed to address the issues.
Review of determination and right of appeal:	Within 6 months after the date of notification of the decision, a review of this determination can be requested under Division 8.2 of the Act or an appeal to the Land and Environment Court made pursuant to the provisions of Section 8.7 of the Act. A review of determination should be lodged as soon as possible, and preferably no later two months after the date of notification of the decision to enable the review to be completed within the six-month period.
Plans endorsed by the consent authority –	please refer to condition A1.
Endorsed for and on behalf of North Sy	dney Council
DATE	
DATE	Signature on behalf of consent authority DAVID HOY

#### (i) Conditions

Consent is granted subject to the following conditions imposed pursuant to Section 4.17 of the Environmental Planning & Assessment Act 1979 ("the *Act*") and the provisions of the Environmental Planning & Assessment Regulation 2000 ("the *Regulation*") such conditions being reasonable and relevant to the development as assessed pursuant to Section 4.17 of the Act.

#### (ii) Definitions

Unless specified otherwise, words have the same meaning as defined by the *Act*, the *Regulation* and the *Interpretation Act* 1987 as in force at the date of consent.

Applicant means the applicant for this consent.

**Approved Plans** means the plans endorsed by Council referenced by this consent as amended by conditions of this consent.

AS or AS/NZS means Australian Standard® or Australian/New Zealand Standard®, respectively, published by Standards Australia International Limited.

*NCC* means the National Construction Code as published by the Australian Building Codes Board as in force at the date of issue of any *Construction Certificate*.

Council means North Sydney Council.

**Court** means the Land and Environment Court.

**Local Native Plants** means species of native plant endemic to North Sydney LGA.

Stormwater Drainage System means all works, facilities and documentation relating to:

- The collection of stormwater,
- The retention of stormwater,
- The reuse of stormwater.
- The detention of stormwater,
- The controlled release of stormwater; and
- Connections to easements and public stormwater systems.

**Owner** means the owner of the *site* and successors in title to the *site*.

Owner Builder has the same meaning as in the Home Building Act 1989.

**Principal Certifier** for building or subdivision work means the certifier appointed as the principal certifier for the building work under section 6.6 (1) or for the subdivision work under section 6.12 (1).

**Principal Contractor** for building work means the person responsible for the overall coordination and control of the carrying out of the building work.

Note: If any residential building work is involved, the principal contractor must be the holder of a contractor licence under the *Home Building Act 1989*.

**Professional Engineer** has the same meaning as in the NCC.

Public Place has the same meaning as in the Local Government Act 1993.

**Road** has the same meaning as in the Roads Act 1993.

**SEE** means the final version of the Statement of Environmental Effects lodged by the *Applicant*.

Site means the land being developed subject to this consent.

NSLEP 2013 means North Sydney Local Environmental Plan 2013

NSDCP 2013 means North Sydney Development Control Plan 2013

**Work** for the purposes of this consent means:

- the use of land in connection with development,
- the subdivision of land,
- the erection of a building,
- the carrying out of any work,
- the use of any site crane, machine, article, material, or thing,
- the storage of any waste, materials, site crane, machine, article, material, or thing,
- the demolition of a building,
- the piling, piercing, cutting, boring, drilling, rock breaking, rock sawing or excavation of land,
- the delivery to or removal from the *site* of any machine, article, material, or thing, or
- the occupation of the *site* by any person unless authorised by an *occupation certificate*.

Note: **Interpretation of Conditions** – Where there is any need to obtain an interpretation of the intent of any condition this must be done in writing to Council and confirmed in writing by Council.

# INDEX OF CONDITIONS

A1.   Development in Accordance with Plans/documentation   8	<b>A.</b>	Conditions that Identify Approved Plans	Page No.
A2.         Plans on Site         8           A3.         No Demolitition of Extra Fabric         8           A4.         Terms of Consent         8           C.         Prior to the Issue of a Construction Certificate (and ongoing, where indicated)           C1.         Dilapidation Report Damage to Public Infrastructure         9           C2.         Dilapidation Survey Private Property (Neighbouring Buildings)         9           C3.         Structural Adequacy of Existing Building         10           C4.         Sediment Control         10           C5.         Waste Management Plan         10           C6.         Colours, Finishes and Materials (Conservation Areas)         11           C7.         Skylight(s)         11           C8.         Roofing Materials - Reflectivity         11           C8.         Roofing Materials - Reflectivity         11           C9.         Stormwater Disposal         12           C10.         Bond for Damage and Completion of Infrastructure Works - Stormwater,			
A3. No Demolition of Extra Fabric 8 A4. Terms of Consent 8  C. Prior to the Issue of a Construction Certificate (and ongoing, where indicated)  C1. Dilapidation Report Damage to Public Infrastructure 9 C2. Dilapidation Survey Private Property (Neighbouring Buildings) 9 C3. Structural Adequacy of Existing Building 10 C4. Sediment Control 10 C5. Waste Management Plan 10 C6. Colours, Finishes and Materials (Conservation Areas) 11 C7. Skylight(s) 11 C8. Roofing Materials - Reflectivity 11 C8. Roofing Materials - Reflectivity 11 C9. Stormwater Disposal 12 C10. Bond for Damage and Completion of Infrastructure Works – Stormwater, Kerb and Gutter, Footpaths, Vehicular Crossing and Road Pavement 12 C11. Asbestos & Hazardous Material Survey 13 C13. Security Deposit/ Guarantee Schedule 14 C14. BASIX Certificate 14 C15. Solar Panels 14 C16. Prior to the Commencement of any Works (and continuing where indicated)  D. Prior to the Commencement of any Works (and continuing where indicated)  E. During Demolition and Building Work  E1. Cigarette Butt Receptacle 15 E2. Parking Restrictions 15 E3. Road Reserve Safety 16 E4. Temporary Disposal of Stormwater Runoff 16 E5. Removal of Extra Fabric 16 E6. Dust Emission and Air Quality 16 E7. Noise and Vibration 17 E8. Developer's Cost of Work on Council Property 17 E9. Special Permits 17 E10. Construction Hours 18 E11. Installation and Maintenance of Sediment Control 19 E12. Sediment and Erosion Control Signage 19 E13. Stite Amenities and Facilities 19		•	
A4. Terms of Consent  C. Prior to the Issue of a Construction Certificate (and ongoing, where indicated)  C1. Dilapidation Report Damage to Public Infrastructure  C2. Dilapidation Survey Private Property (Neighbouring Buildings)  C3. Structural Adequacy of Existing Building  C4. Sediment Control  C5. Waste Management Plan  C6. Colours, Finishes and Materials (Conservation Areas)  C7. Skylight(s)  C8. Roofing Materials - Reflectivity  C9. Stormwater Disposal  C10. Bond for Damage and Completion of Infrastructure Works – Stormwater, Kerb and Gutter, Footpaths, Vehicular Crossing and Road Pavement  C11. Asbestos & Hazardous Material Survey  C12. Privacy  C13. Security Deposit/ Guarantee Schedule  C14. BASIX Certificate  C15. Solar Panels  C16. Prior to the Commencement of any Works (and continuing where indicated)  C17. Prior to the Commencement of any Works (and continuing where indicated)  C18. Public Liability Insurance – Works on Public Land  C19. Public Liability Insurance – Works on Public Land  C19. Public Liability Insurance – Works on Public Land  C19. Parking Restrictions  C19. Parking Restrictions  C19. Parking Restrictions  C19. Removal of Extra Fabric  C19. Removal of Extra Fabric  C19. Noise and Vibration  C19. Special Permits  C19. Special Permits  C19. Special Permits  C19. Sediment and Erosion Control Signage  C19. Sediment and Erosion Control Signage  C19. Sitis Amenities and Facilities  C19. Sitis Amenities and Fac			
C. Prior to the Issue of a Construction Certificate (and ongoing, where indicated)  C1. Dilapidation Report Damage to Public Infrastructure  C2. Dilapidation Survey Private Property (Neighbouring Buildings)  Scrievarial Adequacy of Existing Building  C3. Structural Adequacy of Existing Building  C4. Sediment Control  C5. Waste Management Plan  C6. Colours, Finishes and Materials (Conservation Areas)  C7. Skylight(s)  C8. Roofing Materials - Reflectivity  C9. Stormwater Disposal  C10. Bond for Damage and Completion of Infrastructure Works – Stormwater, Kerb and Gutter, Footpaths, Vehicular Crossing and Road Pavement  C12. Privacy  C13. Security Deposit/ Guarantee Schedule  C14. BASIX Certificate  C15. Solar Panels  D. Prior to the Commencement of any Works (and continuing where indicated)  D. Prior to the Commencement of any Works (and continuing where indicated)  D. Prior gaphic Survey (Heritage Items)  D2. Public Liability Insurance – Works on Public Land  E. During Demolition and Building Work  E1. Cigarette Butt Receptacle  E2. Parking Restrictions  E3. Road Reserve Safety  E4. Temporary Disposal of Stormwater Runoff  E5. Removal of Extra Fabric  E6. Dust Emission and Air Quality  E7. Noise and Vibration  E8. Developer's Cost of Work on Council Property  E9. Special Permits  17. Special Permits  17. Special Permits  17. Oosteruction Hours  E11. Installation and Maintenance of Sediment Control  E12. Sediment and Erosion Control Signage  E13. Site Amenities and Facilities  E9. Sediment and Erosion Control Signage			
C1.         Dilapidation Report Damage to Public Infrastructure         9           C2.         Dilapidation Survey Private Property (Neighbouring Buildings)         9           C3.         Structural Adequacy of Existing Building         10           C4.         Sediment Control         10           C5.         Waste Management Plan         10           C6.         Colours, Finishes and Materials (Conservation Areas)         11           C7.         Skylight(s)         11           C8.         Roofing Materials - Reflectivity         11           C9.         Stormwater Disposal         12           C10.         Bond for Damage and Completion of Infrastructure Works – Stormwater, Kerb and Gutter, Footpaths, Vehicular Crossing and Road Pavement         12           C11.         Asbestos & Hazardous Material Survey         13           C12.         Privacy         13           C13.         Security Deposit/ Guarantee Schedule         14           C14.         AbASIX Certificate         14           C15.         Solar Panels         14           D.         Prior to the Commencement of any Works (and continuing where indicated)         15           D2.         Public Liability Insurance – Works on Public Land         15           E2.         Parking	A4.	Terms of Consent	8
C2.         Dilapidation Survey Private Property (Neighbouring Buildings)         9           C3.         Structural Adequacy of Existing Building         10           C4.         Sediment Control         10           C5.         Waste Management Plan         10           C6.         Colours, Finishes and Materials (Conservation Areas)         11           C7.         Skylight(s)         11           C8.         Roofing Materials - Reflectivity         11           C9.         Stormwater Disposal         12           C10.         Bond for Damage and Completion of Infrastructure Works – Stormwater, Kerb and Gutter, Footpaths, Vehicular Crossing and Road Pavement         12           C11.         Asbestos & Hazardous Material Survey         13           C12.         Privacy         13           C13.         Security Deposit/ Guarantee Schedule         14           C14.         AsbSIX Certificate         14           C15.         Solar Panels         14           D.         Prior to the Commencement of any Works (and continuing where indicated)           D1.         Photographic Survey (Heritage Items)         15           D2.         Public Liability Insurance – Works on Public Land         15           E         During Demolition and Building Work	<i>C</i> .	Prior to the Issue of a Construction Certificate (and ongoing, where indicated)	
C3.         Structural Adequacy of Existing Building         10           C4.         Sediment Control         10           C5.         Waste Management Plan         10           C6.         Colours, Finishes and Materials (Conservation Areas)         11           C7.         Skylight(s)         11           C8.         Roofing Materials - Reflectivity         11           C8.         Roofing Materials - Reflectivity         11           C9.         Stornwater Disposal         12           C10.         Bond for Damage and Completion of Infrastructure Works - Stormwater, Kerb and Gutter, Footpaths, Vehicular Crossing and Road Pavement         12           C11.         Asbestos & Hazardous Material Survey         13           C12.         Privacy         13           C13.         Security Deposit/ Guarantee Schedule         14           C14.         BASIX Certificate         14           C15.         Solar Panels         14           D.         Prior to the Commencement of any Works (and continuing where indicated)           D1.         Photographic Survey (Heritage Items)         15           D2.         Public Liability Insurance – Works on Public Land         15           E.         During Demolition and Building Work	C1.	Dilapidation Report Damage to Public Infrastructure	9
C4.         Sediment Control         10           C5.         Waste Management Plan         10           C6.         Colours, Finishes and Materials (Conservation Areas)         11           C7.         Skylight(s)         11           C8.         Roofing Materials - Reflectivity         11           C9.         Stormwater Disposal         12           C10.         Bond for Damage and Completion of Infrastructure Works - Stormwater,	C2.	Dilapidation Survey Private Property (Neighbouring Buildings)	9
C5.         Waste Management Plan         10           C6.         Colours, Finishes and Materials (Conservation Areas)         11           C7.         Skylight(s)         11           C8.         Roofing Materials - Reflectivity         11           C9.         Stormwater Disposal         12           C10.         Bond for Damage and Completion of Infrastructure Works – Stormwater, Kerb and Gutter, Footpaths, Vehicular Crossing and Road Pavement         12           C11.         Asbestos & Hazardous Material Survey         13           C12.         Privacy         13           C13.         Security Deposit/ Guarantee Schedule         14           C14.         BASIX Certificate         14           C15.         Solar Panels         14           D.         Prior to the Commencement of any Works (and continuing where indicated)           D1.         Photographic Survey (Heritage Items)         15           D2.         Public Liability Insurance – Works on Public Land         15           E.         During Demolition and Building Work           E1.         Cigarette Butt Receptacle         15           E2.         Parking Restrictions         15           E3.         Road Reserve Safety         16           E4. <td< td=""><td>C3.</td><td>Structural Adequacy of Existing Building</td><td>10</td></td<>	C3.	Structural Adequacy of Existing Building	10
C6.         Colours, Finishes and Materials (Conservation Areas)         11           C7.         Skylight(s)         11           C8.         Roofing Materials - Reflectivity         11           C9.         Stormwater Disposal         12           C10.         Bond for Damage and Completion of Infrastructure Works - Stormwater, Kerb and Gutter, Footpaths, Vehicular Crossing and Road Pavement         12           C11.         Asbestos & Hazardous Material Survey         13           C12.         Privacy         13           C13.         Security Deposit/ Guarantee Schedule         14           C14.         BASIX Certificate         14           C15.         Solar Panels         14           D.         Prior to the Commencement of any Works (and continuing where indicated)           D1.         Photographic Survey (Heritage Items)         15           D2.         Public Liability Insurance – Works on Public Land         15           E.         During Demolition and Building Work         15           E1.         Cigarette Butt Receptacle         15           E2.         Parking Restrictions         15           E3.         Road Reserve Safety         16           E4.         Temporary Disposal of Stormwater Runoff         16 <tr< td=""><td>C4.</td><td>Sediment Control</td><td>10</td></tr<>	C4.	Sediment Control	10
C7.         Skylight(s)         11           C8.         Roofing Materials - Reflectivity         11           C9.         Stormwater Disposal         12           C10.         Bond for Damage and Completion of Infrastructure Works - Stormwater, Kerb and Gutter, Footpaths, Vehicular Crossing and Road Pavement         12           C11.         Asbestos & Hazardous Material Survey         13           C12.         Privacy         13           C13.         Security Deposit/ Guarantee Schedule         14           C14.         BASIX Certificate         14           C15.         Solar Panels         14           D.         Prior to the Commencement of any Works (and continuing where indicated)           D1.         Photographic Survey (Heritage Items)         15           D2.         Public Liability Insurance – Works on Public Land         15           E         During Demolition and Building Work         15           E1.         Cigarette Butt Receptacle         15           E2.         Parking Restrictions         15           E3.         Road Reserve Safety         16           E4.         Temporary Disposal of Stormwater Runoff         16           E5.         Removal of Extra Fabric         16           E6.	C5.	Waste Management Plan	10
C8.         Roofing Materials - Reflectivity         11           C9.         Stormwater Disposal         12           C10.         Bond for Damage and Completion of Infrastructure Works – Stormwater, Kerb and Gutter, Footpaths, Vehicular Crossing and Road Pavement         12           C11.         Asbestos & Hazardous Material Survey         13           C12.         Privacy         13           C13.         Security Deposit/ Guarantee Schedule         14           C14.         BASIX Certificate         14           C15.         Solar Panels         14           D.         Prior to the Commencement of any Works (and continuing where indicated)           D1.         Photographic Survey (Heritage Items)         15           D2.         Public Liability Insurance – Works on Public Land         15           E.         During Demolition and Building Work           E1.         Cigarette Butt Receptacle         15           E2.         Parking Restrictions         15           E3.         Road Reserve Safety         16           E4.         Temporary Disposal of Stormwater Runoff         16           E5.         Removal of Extra Fabric         16           E6.         Dust Emission and Air Quality         16           E7.	C6.	Colours, Finishes and Materials (Conservation Areas)	11
C8.         Roofing Materials - Reflectivity         11           C9.         Stormwater Disposal         12           C10.         Bond for Damage and Completion of Infrastructure Works – Stormwater, Kerb and Gutter, Footpaths, Vehicular Crossing and Road Pavement         12           C11.         Asbestos & Hazardous Material Survey         13           C12.         Privacy         13           C13.         Security Deposit/ Guarantee Schedule         14           C14.         BASIX Certificate         14           C15.         Solar Panels         14           D.         Prior to the Commencement of any Works (and continuing where indicated)           D1.         Photographic Survey (Heritage Items)         15           D2.         Public Liability Insurance – Works on Public Land         15           E.         During Demolition and Building Work           E1.         Cigarette Butt Receptacle         15           E2.         Parking Restrictions         15           E3.         Road Reserve Safety         16           E4.         Temporary Disposal of Stormwater Runoff         16           E5.         Removal of Extra Fabric         16           E6.         Dust Emission and Air Quality         16           E7.	C7.	Skylight(s)	11
C9.       Stormwater Disposal       12         C10.       Bond for Damage and Completion of Infrastructure Works – Stormwater, Kerb and Gutter, Footpaths, Vehicular Crossing and Road Pavement       12         C11.       Asbestos & Hazardous Material Survey       13         C12.       Privacy       13         C13.       Security Deposit/ Guarantee Schedule       14         C14.       BASIX Certificate       14         C15.       Solar Panels       14         D.       Prior to the Commencement of any Works (and continuing where indicated)         D1.       Photographic Survey (Heritage Items)       15         D2.       Public Liability Insurance – Works on Public Land       15         E.       During Demolition and Building Work         E1.       Cigarette Butt Receptacle       15         E2.       Parking Restrictions       15         E3.       Road Reserve Safety       16         E4.       Temporary Disposal of Stormwater Runoff       16         E5.       Removal of Extra Fabric       16         E6.       Dust Emission and Air Quality       16         E7.       Noise and Vibration       17         E8.       Developer's Cost of Work on Council Property       17         E9.	C8.		11
C10. Bond for Damage and Completion of Infrastructure Works – Stormwater, Kerb and Gutter, Footpaths, Vehicular Crossing and Road Pavement 12 C11. Asbestos & Hazardous Material Survey 13 C12. Privacy 13 C13. Security Deposit/ Guarantee Schedule 14 C14. BASIX Certificate 14 C15. Solar Panels 14  D. Prior to the Commencement of any Works (and continuing where indicated)  D1. Photographic Survey (Heritage Items) 15 D2. Public Liability Insurance – Works on Public Land 15  E. During Demolition and Building Work  E1. Cigarette Butt Receptacle 15 E2. Parking Restrictions 15 E3. Road Reserve Safety 16 E4. Temporary Disposal of Stormwater Runoff 16 E4. Temporary Disposal of Stormwater Runoff 16 E5. Removal of Extra Fabric 16 E6. Dust Emission and Air Quality 16 E7. Noise and Vibration 17 E8. Developer's Cost of Work on Council Property 17 E9. Special Permits 17 E10. Construction Hours 18 E11. Installation and Maintenance of Sediment Control 19 E12. Sediment and Erosion Control Signage 19 E13. Site Amenities and Facilities 19		· · · · · · · · · · · · · · · · · · ·	12
Kerb and Gutter, Footpaths, Vehicular Crossing and Road Pavement 12 C11. Asbestos & Hazardous Material Survey 13 C12. Privacy 13 C13. Security Deposit/ Guarantee Schedule 14 C14. BASIX Certificate 14 C15. Solar Panels 14  D. Prior to the Commencement of any Works (and continuing where indicated)  D1. Photographic Survey (Heritage Items) 15 D2. Public Liability Insurance – Works on Public Land 15  E. During Demolition and Building Work  E1. Cigarette Butt Receptacle 15 E2. Parking Restrictions 15 E3. Road Reserve Safety 16 E4. Temporary Disposal of Stormwater Runoff 16 E5. Removal of Extra Fabric 16 E6. Dust Emission and Air Quality 16 E7. Noise and Vibration 17 E8. Developer's Cost of Work on Council Property 17 E9. Special Permits 17 E10. Construction Hours 18 E11. Installation and Maintenance of Sediment Control 19 E12. Sediment and Erosion Control Signage 19 E13. Site Amenities and Facilities 19		<u>*</u>	
C11.       Asbestos & Hazardous Material Survey       13         C12.       Privacy       13         C13.       Security Deposit/ Guarantee Schedule       14         C14.       BASIX Certificate       14         C15.       Solar Panels       14         D.       Prior to the Commencement of any Works (and continuing where indicated)         D1.       Photographic Survey (Heritage Items)       15         D2.       Public Liability Insurance – Works on Public Land       15         E.       During Demolition and Building Work         E1.       Cigarette Butt Receptacle       15         E2.       Parking Restrictions       15         E3.       Road Reserve Safety       16         E4.       Temporary Disposal of Stormwater Runoff       16         E5.       Removal of Extra Fabric       16         E6.       Dust Emission and Air Quality       16         E7.       Noise and Vibration       17         E8.       Developer's Cost of Work on Council Property       17         E9.       Special Permits       17         E10.       Construction Hours       18         E11.       Installation and Maintenance of Sediment Control       19         E12. <td></td> <td></td> <td>12</td>			12
C12.       Privacy       13         C13.       Security Deposit/ Guarantee Schedule       14         C14.       BASIX Certificate       14         C15.       Solar Panels       14         D. Prior to the Commencement of any Works (and continuing where indicated)         D1. Photographic Survey (Heritage Items)       15         D2.       Public Liability Insurance – Works on Public Land       15         E. During Demolition and Building Work         E1.       Cigarette Butt Receptacle       15         E2.       Parking Restrictions       15         E3.       Road Reserve Safety       16         E4.       Temporary Disposal of Stormwater Runoff       16         E5.       Removal of Extra Fabric       16         E6.       Dust Emission and Air Quality       16         E7.       Noise and Vibration       17         E8.       Developer's Cost of Work on Council Property       17         E9.       Special Permits       17         E10.       Construction Hours       18         E11.       Installation and Maintenance of Sediment Control       18         E12.       Sediment and Erosion Control Signage       19         E13.       <	C11.	· · · · · · · · · · · · · · · · · · ·	13
C14.BASIX Certificate14C15.Solar Panels14D.Prior to the Commencement of any Works (and continuing where indicated)D1.Photographic Survey (Heritage Items)15D2.Public Liability Insurance – Works on Public Land15E.During Demolition and Building WorkE1.Cigarette Butt Receptacle15E2.Parking Restrictions15E3.Road Reserve Safety16E4.Temporary Disposal of Stormwater Runoff16E5.Removal of Extra Fabric16E6.Dust Emission and Air Quality16E7.Noise and Vibration17E8.Developer's Cost of Work on Council Property17E9.Special Permits17E10.Construction Hours18E11.Installation and Maintenance of Sediment Control19E12.Sediment and Erosion Control Signage19E13.Site Amenities and Facilities19	C12.	•	13
C14.BASIX Certificate14C15.Solar Panels14D.Prior to the Commencement of any Works (and continuing where indicated)D1.Photographic Survey (Heritage Items)15D2.Public Liability Insurance – Works on Public Land15E.During Demolition and Building WorkE1.Cigarette Butt Receptacle15E2.Parking Restrictions15E3.Road Reserve Safety16E4.Temporary Disposal of Stormwater Runoff16E5.Removal of Extra Fabric16E6.Dust Emission and Air Quality16E7.Noise and Vibration17E8.Developer's Cost of Work on Council Property17E9.Special Permits17E10.Construction Hours18E11.Installation and Maintenance of Sediment Control19E12.Sediment and Erosion Control Signage19E13.Site Amenities and Facilities19		•	14
D. Prior to the Commencement of any Works (and continuing where indicated)D1. Photographic Survey (Heritage Items)15D2. Public Liability Insurance – Works on Public Land15E. During Demolition and Building WorkE1. Cigarette Butt Receptacle15E2. Parking Restrictions15E3. Road Reserve Safety16E4. Temporary Disposal of Stormwater Runoff16E5. Removal of Extra Fabric16E6. Dust Emission and Air Quality16E7. Noise and Vibration17E8. Developer's Cost of Work on Council Property17E9. Special Permits17E10. Construction Hours18E11. Installation and Maintenance of Sediment Control19E12. Sediment and Erosion Control Signage19E13. Site Amenities and Facilities19		•	14
D1.Photographic Survey (Heritage Items)15D2.Public Liability Insurance – Works on Public Land15E.During Demolition and Building WorkE1.Cigarette Butt Receptacle15E2.Parking Restrictions15E3.Road Reserve Safety16E4.Temporary Disposal of Stormwater Runoff16E5.Removal of Extra Fabric16E6.Dust Emission and Air Quality16E7.Noise and Vibration17E8.Developer's Cost of Work on Council Property17E9.Special Permits17E10.Construction Hours18E11.Installation and Maintenance of Sediment Control19E12.Sediment and Erosion Control Signage19E13.Site Amenities and Facilities19	C15.	Solar Panels	14
D2.Public Liability Insurance – Works on Public Land15E.During Demolition and Building WorkE1.Cigarette Butt Receptacle15E2.Parking Restrictions15E3.Road Reserve Safety16E4.Temporary Disposal of Stormwater Runoff16E5.Removal of Extra Fabric16E6.Dust Emission and Air Quality16E7.Noise and Vibration17E8.Developer's Cost of Work on Council Property17E9.Special Permits17E10.Construction Hours18E11.Installation and Maintenance of Sediment Control19E12.Sediment and Erosion Control Signage19E13.Site Amenities and Facilities19	D.	Prior to the Commencement of any Works (and continuing where indicated)	
D2.Public Liability Insurance – Works on Public Land15E.During Demolition and Building WorkE1.Cigarette Butt Receptacle15E2.Parking Restrictions15E3.Road Reserve Safety16E4.Temporary Disposal of Stormwater Runoff16E5.Removal of Extra Fabric16E6.Dust Emission and Air Quality16E7.Noise and Vibration17E8.Developer's Cost of Work on Council Property17E9.Special Permits17E10.Construction Hours18E11.Installation and Maintenance of Sediment Control19E12.Sediment and Erosion Control Signage19E13.Site Amenities and Facilities19	D1.	Photographic Survey (Heritage Items)	15
E1. Cigarette Butt Receptacle E2. Parking Restrictions E3. Road Reserve Safety E4. Temporary Disposal of Stormwater Runoff E5. Removal of Extra Fabric E6. Dust Emission and Air Quality E7. Noise and Vibration E8. Developer's Cost of Work on Council Property E9. Special Permits E10. Construction Hours E11. Installation and Maintenance of Sediment Control E12. Sediment and Erosion Control Signage E13. Site Amenities and Facilities			
E2.Parking Restrictions15E3.Road Reserve Safety16E4.Temporary Disposal of Stormwater Runoff16E5.Removal of Extra Fabric16E6.Dust Emission and Air Quality16E7.Noise and Vibration17E8.Developer's Cost of Work on Council Property17E9.Special Permits17E10.Construction Hours18E11.Installation and Maintenance of Sediment Control19E12.Sediment and Erosion Control Signage19E13.Site Amenities and Facilities19	<b>E</b> .	During Demolition and Building Work	
E2.Parking Restrictions15E3.Road Reserve Safety16E4.Temporary Disposal of Stormwater Runoff16E5.Removal of Extra Fabric16E6.Dust Emission and Air Quality16E7.Noise and Vibration17E8.Developer's Cost of Work on Council Property17E9.Special Permits17E10.Construction Hours18E11.Installation and Maintenance of Sediment Control19E12.Sediment and Erosion Control Signage19E13.Site Amenities and Facilities19	E1.	Cigarette Butt Receptacle	15
<ul> <li>E3. Road Reserve Safety</li> <li>E4. Temporary Disposal of Stormwater Runoff</li> <li>E5. Removal of Extra Fabric</li> <li>E6. Dust Emission and Air Quality</li> <li>E7. Noise and Vibration</li> <li>E8. Developer's Cost of Work on Council Property</li> <li>E9. Special Permits</li> <li>E10. Construction Hours</li> <li>E11. Installation and Maintenance of Sediment Control</li> <li>E12. Sediment and Erosion Control Signage</li> <li>E13. Site Amenities and Facilities</li> </ul>			
E4.Temporary Disposal of Stormwater Runoff16E5.Removal of Extra Fabric16E6.Dust Emission and Air Quality16E7.Noise and Vibration17E8.Developer's Cost of Work on Council Property17E9.Special Permits17E10.Construction Hours18E11.Installation and Maintenance of Sediment Control19E12.Sediment and Erosion Control Signage19E13.Site Amenities and Facilities19			
<ul> <li>E5. Removal of Extra Fabric</li> <li>E6. Dust Emission and Air Quality</li> <li>E7. Noise and Vibration</li> <li>E8. Developer's Cost of Work on Council Property</li> <li>E9. Special Permits</li> <li>E10. Construction Hours</li> <li>E11. Installation and Maintenance of Sediment Control</li> <li>E12. Sediment and Erosion Control Signage</li> <li>E13. Site Amenities and Facilities</li> </ul>		·	
E6.Dust Emission and Air Quality16E7.Noise and Vibration17E8.Developer's Cost of Work on Council Property17E9.Special Permits17E10.Construction Hours18E11.Installation and Maintenance of Sediment Control19E12.Sediment and Erosion Control Signage19E13.Site Amenities and Facilities19			
<ul> <li>E7. Noise and Vibration</li> <li>E8. Developer's Cost of Work on Council Property</li> <li>E9. Special Permits</li> <li>E10. Construction Hours</li> <li>E11. Installation and Maintenance of Sediment Control</li> <li>E12. Sediment and Erosion Control Signage</li> <li>E13. Site Amenities and Facilities</li> </ul>			
E8.Developer's Cost of Work on Council Property17E9.Special Permits17E10.Construction Hours18E11.Installation and Maintenance of Sediment Control19E12.Sediment and Erosion Control Signage19E13.Site Amenities and Facilities19		~ •	
<ul> <li>E9. Special Permits</li> <li>E10. Construction Hours</li> <li>E11. Installation and Maintenance of Sediment Control</li> <li>E12. Sediment and Erosion Control Signage</li> <li>E13. Site Amenities and Facilities</li> </ul>			
E10.Construction Hours18E11.Installation and Maintenance of Sediment Control19E12.Sediment and Erosion Control Signage19E13.Site Amenities and Facilities19			
<ul> <li>E11. Installation and Maintenance of Sediment Control</li> <li>E12. Sediment and Erosion Control Signage</li> <li>E13. Site Amenities and Facilities</li> <li>19</li> </ul>		•	
<ul> <li>E12. Sediment and Erosion Control Signage</li> <li>E13. Site Amenities and Facilities</li> <li>19</li> </ul>			
E13. Site Amenities and Facilities 19			
		~ · ·	
17			
E15. Prohibition on Use of Pavements		•	
E16. Plant & Equipment Kept Within Site			

E17.	Waste Disposal	20
F.	Prescribed Conditions imposed under EP&A Act and Regulations and other relevant Legislation	
F1.	National Construction Code	20
F2.	Home Building Act	20
F3.	Appointment of a Principal Certifier (previously known as a PCA)	21
F4.	Construction Certificate	21
F5.	Occupation Certificate	21
F6.	Mandatory Critical Stage Inspections	22
F7.	Excavation/Demolition	22
F8.	Site Sign	22
G.	Prior to the Issue of an Occupation Certificate	
G1.	Infrastructure Repair and Completion of Works	22
G2.	Damage to Adjoining Properties	23
G3.	Utility Services	23
G4.	BASIX Completion Certificate	23
G5.	Works wholly within subject site	23
G6.	Compliance with Certain conditions	23
I.	On-Going / Operational Conditions	
I1.	Non-trafficable Roof	23

# A. Conditions that Identify Approved Plans

## **Development in Accordance with Plans/documentation**

A1. The development must be carried out in accordance with the following drawings and documentation and endorsed with Council's approval stamp, except where amended by the following conditions of this consent.

Drawing Number	Issue/ Revision	Title	Drawn by	Dated
05	I	Site plan	Nick hibberd architect	10/12/1
10	I	Proposed basement, ground plans	Nick hibberd architect	10/12/1
11	J	Proposed upper and roof plans	Nick hibberd architect	18/03/19
20	J	Section sheet 1	Nick hibberd architect	10/12/1
21	K	Sections sheet 2	Nick hibberd architect	8/04/19
22	K	Finishes elevation	Nick hibberd architect	8/04/19
23	K	Section sheet 3	Nick hibberd architect	8/04/19

(Reason:

To ensure that the form of the development undertaken is in accordance with the determination of Council, Public Information)

#### Plans on Site

A2. A copy of all stamped approved plans, specifications and documents (including the plans, specifications and documents submitted and approved with the Construction Certificate) must be kept on site at all times so as to be readily available for perusal by any officer of Council or the Principal Certifying Authority.

All documents kept on site in accordance with this condition must be provided to any officer of the Council or the certifying authority upon their request.

(Reason:

To ensure that the form of the development undertaken is in accordance with the determination of Council, Public Information and to ensure ongoing compliance)

#### **No Demolition of Extra Fabric**

A3. Alterations to, and demolition of the existing building shall be limited to that documented on the approved plans.

(Reason: To ensure compliance with the approved development)

#### **Terms of consent**

A4. No approval is given or implied under this consent for the construction of the shade cloth structure and associated post over the right of way that burdens No. 108 Bank Street, North Sydney

(Reason:

The existing garage is to be widened to be compliant with the relevant Australian Standard and therefore one parking space will be provided on the site. The carport cannot be approved as the existing site coverage is already above the maximum control and a carport would result in an overdevelopment of the site and uncharacteristic of the neighbourhood)

# C. Prior to the Issue of a Construction Certificate (and ongoing, where indicated)

## **Dilapidation Report Damage to Public Infrastructure**

C1. A dilapidation survey and report (including photographic record) must be prepared by a suitably qualified consultant which details the pre-developed condition of the existing public infrastructure in the vicinity of the development site. Particular attention must be paid to accurately recording any pre-developed damaged areas so that Council is fully informed when assessing any damage to public infrastructure caused as a result of the development. A copy of the dilapidation survey and report is to be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate.

The developer may be held liable for all damage to public infrastructure in the vicinity of the site, where such damage is not accurately recorded and demonstrated as pre-existing under the requirements of this condition.

The developer shall bear the cost of carrying out works to restore all public infrastructure damaged as a result of the carrying out of the development, and no occupation of the development shall occur until damage caused as a result of the carrying out of the development is rectified.

A copy of the dilapidation survey and report must be lodged with North Sydney Council by the Certifying Authority with submission of the Construction Certificate documentation.

(Reason: To record the condition of public infrastructure prior to the commencement of construction)

# **Dilapidation Survey Private Property (Neighbouring Properties)**

C2. A photographic survey and dilapidation report of adjoining property at No 104 Bank Street detailing the physical condition of the rear of this property, in addition to the Right of Way that burdens No. 108 Bank Street, SHALL BE submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The survey and report is to be prepared by an appropriately qualified person agreed to by both the applicant and the owner of the adjoining property. A copy of the report is to be provided to Council, if Council is not the Certifying Authority, prior to the issue of any Construction Certificate.

All costs incurred in achieving compliance with this condition shall be borne by the person entitled to act on this Consent.

In the event that access for undertaking the photographic survey and dilapidation report is denied by an adjoining owner, the applicant MUST DEMONSTRATE, in writing, to the satisfaction of Council that all reasonable steps have been taken to obtain access and advise the affected property owner of the reason for the survey and that these steps have failed. Written concurrence must be obtained from Council in such circumstances.

Note:

This documentation is for record keeping purposes only, and may be used by an applicant or affected property owner to assist in any action required to resolve any dispute over damage to adjoining properties arising from the works. It is in the applicant's and adjoining owner's interest for it to be as full and detailed as possible.

(Reason: Proper management of records)

# Structural Adequacy of Existing Building

C3. A report prepared by an appropriately qualified and practising structural engineer, certifying the structural adequacy of the property and its ability to withstand the proposed additional, or altered structural loads during all stages of construction shall be submitted to the Certifying Authority for approval prior to issue of any Construction Certificate. The certified report must also include all details of the methodology to be employed in construction phases to achieve the above requirements. The methodology in the certified report must be complied with at all times.

(Reason: To ensure the structural integrity of the building is maintained)

#### **Sediment Control**

C4. Where construction or excavation activity requires the disturbance of the soil surface or existing vegetation, erosion and sediment control techniques, as a minimum, are to be in accordance with the publication Managing Urban Stormwater: Soils & Construction (4th edition, Landcom, 2004) commonly referred to as the "Blue Book" or a suitable and effective alternative method.

A Sediment Control Plan must be prepared and submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate and prior to any works commencing. The Sediment Control Plan must be consistent with the Blue Book and disclose:

- a) All details of drainage to protect and drain the site during the construction processes;
- b) All sediment control devices, barriers and the like;
- c) Sedimentation tanks, ponds or the like;
- d) Covering materials and methods; and
- e) A schedule and programme of the sequence of the sediment and erosion control works or devices to be installed and maintained.
- f) Methods for the temporary and controlled disposal of stormwater during construction.

All works must be undertaken in accordance with the approved Sediment Control plan.

The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To protect the environment from the effects of sedimentation and erosion from development sites)

#### **Waste Management Plan**

C5. A Waste Management Plan is to be submitted for approval by the Certifying Authority prior to the issue of any Construction Certificate. The plan must include, but not be limited to:

- a) The estimated volume of waste and method of disposal for the construction and operation phases of the development;
- b) The design of the on-site waste storage and recycling area; and
- c) Administrative arrangements for waste and recycling management during the construction process.

The approved Waste Management Plan must be complied with at all times in the carrying out of the development.

(Reason: To encourage the minimisation of waste and recycling of building waste)

## **Colours, Finishes and Materials (Conservation Areas)**

C6. The finishes, materials and exterior colours shall be complementary to the architectural style of the original building and sympathetic to the character of the Conservation Area. A schedule of finishes, materials and external colours shall be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the building plans and specifications submitted fully satisfy the requirements of this condition prior to the release of the Construction Certificate.

(Reason: To ensure that the completed colours, finishes and materials are complementary to the Conservation Area)

## Skylight(s)

C7. Skylight flashing(s) and frame(s) to be coloured to match the roof material. Skylight(s) to sit no higher than 100mm above roof plane when in a closed position. Plans and specifications which comply with this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate.

The Certifying Authority must ensure that the building plans and specifications submitted fully satisfy the requirements of this condition.

(Reason: To minimise the visual impact of the skylight(s) on the roof plane)

## **Roofing Materials - Reflectivity**

C8. Roofing materials must be factory pre-finished with low glare and reflectivity properties to be compatible with the colours of neighbouring buildings. The selected roofing material must not cause a glare nuisance or excessive reflectivity to adjoining or nearby properties. Plans and specifications which comply with this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To ensure that excessive glare or reflectivity nuisance from roofing materials does not occur as a result of the development)

## **Stormwater Disposal**

C9. Stormwater runoff generated by the approved development must be conveyed by gravity to the existing site stormwater drainage disposal system. A licensed tradesman shall install plumbing components to achieve this requirement in accordance with the BCA and current plumbing standards and guidelines. Plans and specifications which comply with this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To ensure appropriate provision for disposal and stormwater management arising from the development)

# Bond for Damage and Completion of Infrastructure Works – Stormwater, Kerb and Gutter, Footpaths, Vehicular Crossing and Road Pavement

- C10. Prior to the issue of any Construction Certificate, security deposit or bank guarantee must be provided to Council to the sum of \$3,500 to be held by Council for the payment of cost for any/all of the following:
  - a) making good any damage caused to any property of the Council as a consequence of the doing of anything to which this consent relates,
  - b) completing any public work (such as road work, kerbing and guttering, footway construction, stormwater drainage and <u>environmental</u> <u>controls</u>) required in connection with this consent
  - c) remedying any defects in any such public work that arise within 6 months after the work is completed.

The security required by this condition and in the schedule contained later in these conditions must be provided by way of a deposit with the Council; or other such guarantee that is satisfactory to Council (such as a bank guarantee). Any guarantee provided as security must name North Sydney Council as the nominated beneficiary and must not be subject to an expiry date.

The security will be refundable following the expiration of 6 months from the issue of any final Occupation Certificate or completion of public work required to be completed (whichever is the latest) but only upon inspection and release by Council's Engineers.

Council shall have full authority to make use of the bond for such restoration works as deemed necessary by Council in circumstances including the following: -

- where the damage constitutes a hazard in which case Council may make use of the security immediately;
- the applicant has not repaired or commenced repairing damage within 48 hours of the issue by Council in writing of instructions to undertake such repairs or works;
- works in the public road associated with the development are to an unacceptable quality;
   and

• the Certifying Authority must ensure that security is provided to North Sydney Council prior to issue of any Construction Certificate.

(Reason: To ensure appropriate security for works on public land and an appropriate

quality for new public infrastructure)

## Asbestos & Hazardous Material Survey

C11. A report must be prepared by a suitably qualified person in relation to the existing building fabric to be demolished and/or disturbed identifying the presence or otherwise of asbestos contamination and, if asbestos contamination is present, making recommendations as to the work required to safely address the contamination.

Any demolition works or other works identified in the report as having to be carried out must be carried out in accordance with the recommendations of the report and the following:

- a) the removal of asbestos must be undertaken by a WorkCover licensed contractor;
- b) all removal must be in strict accordance with the requirements of the WorkCover Authority in relation to the removal, handling and disposal of material containing asbestos and any Work Safe Australia requirements.
- c) during the removal of any asbestos a sign stating "DANGER ASBESTOS REMOVAL IN PROGRESS" must be erected in a visible position at the boundary of the site; and
- d) Waste disposal receipts must be provided to the Certifying Authority as proof of correct disposal of asbestos laden waste.

The report must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the report, and other plans, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To ensure the long term health of workers on site and occupants of the building is not put at risk unnecessarily)

## **Privacy**

- C12. The following privacy devices are to be provided:
  - a) The privacy screens nominated on the plans to be attached to the ground floor southern lounge room windows must be solid and lack transparency.
  - b) A privacy screen to a minimum height of 1.6m above floor level must be attached to the ground floor southern kitchen window (WD/3). The privacy screen must be solid and lack transparency.
  - c) The angled privacy screens, on the roof of the dwelling and attached to the first floor southern wall which is located off the stairwell and bedroom 4 windows (WD6 and WD/7) must be solid, lack transparency and be to the height indicated on the elevation plans.
  - d) The timber framed canopy around the perimeter of the ground floor southern dining room window (WD/4) must extend out a minimum depth of 300mm from the existing masonry wall.

Plans and specifications complying with this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To ensure an adequate level of privacy is provided to adjoining property located

at No. 102 and 104 Bank Street, North Sydney)

# **Security Deposit/Guarantee Schedule**

C13. All fees and security deposits/ guarantees in accordance with the schedule below must be provided to Council prior to the issue of any Construction Certificate:

Security deposit/ guarantee	Amount (\$)
Footpath Damage Bond	\$2,000
Council's Reserve Damage bond	\$1,500
TOTAL BONDS	\$3,500

The security required by the above schedule must be provided by way of a deposit with the Council; or other such guarantee that is satisfactory to Council (such as a bank guarantee). Any guarantee provided as security must name North Sydney Council as the nominated beneficiary and must not be subject to an expiry date.

(Reason: Compliance with the development consent)

#### **BASIX Certificate**

C14. Under clause 97A(3) of the Environmental Planning & Assessment Regulation 2000, it is a condition of this development consent that all the commitments listed in BASIX Certificate No. A332933 for the development are fulfilled. Plans and specifications complying with this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To ensure the proposed development will meet the Government's requirements for sustainability and statutory requirements)

# Solar panels

C15. The solar panels located on the western half of the roof must be laid flat on the roof membrane and must not be tilted or angled above the level of the roof parapet.

(Reason: To minimise the visual impact of the solar panels on the public domain)

## D. Prior to the Commencement of any Works (and continuing where indicated)

# **Photographic Survey**

D1. Prior to any works commencing a photographic survey recording, including remnants of the earlier building around which the current dwelling is built must be provided in accordance with the NSW Heritage Office Guidelines "Photographic recording of Heritage Items using file or digital capture", is to be prepared to the satisfaction of Council's Historian and Conservation Planner. Two (2) copies of the photographic survey must be provided to Council.

(Reason: To provide a historical record of heritage significant fabric on site for archival purposes)

## Public Liability Insurance - Works on Public Land

D2. Any person or contractor undertaking works on public land must take out Public Risk Insurance with a minimum cover of \$20 million in relation to the occupation of public land and the undertaking of approved works within Council's road reserve or public land, as approved by this consent. The Policy is to note, and provide protection/full indemnification for North Sydney Council, as an interested party. A copy of the Policy must be submitted to Council prior to commencement of any works. The Policy must be valid for the entire period that the works are being undertaken.

(Note: Applications for hoarding permits, vehicular crossings etc. will require evidence

of insurance upon lodgement of the application.)

(Reason: To ensure the community is protected from the cost of any claim for damages

arising from works on public land)

## E. During Demolition and Building Work

## **Cigarette Butt Receptacle**

E1. A cigarette butt receptacle is to be provided on the site for the duration of excavation/demolition/construction process, for convenient use of site workers.

(Reason: To ensure adequate provision is made for builders' waste)

## **Parking Restrictions**

E2. Existing public parking provisions in the vicinity of the site must be maintained at all times during works. The placement of any barriers, traffic cones, obstructions or other device in the road shoulder or kerbside lane is prohibited without the prior written consent of Council. Changes to existing public parking facilities/restrictions must be approved by the North Sydney Local Traffic Committee. The Developer will be held responsible for any breaches of this condition, and will incur any fines associated with enforcement by Council regulatory officers.

(Reason: To ensure that existing kerbside parking provisions are not compromised during

works)

## **Road Reserve Safety**

E3. All public footways and roadways fronting and adjacent to the site must be maintained in a safe condition at all times during the course of the development works, with no obstructions caused to the said footways and roadways. Construction materials and plant must not be stored in the road reserve without approval of Council. A safe pedestrian circulation route and a pavement/route free of trip hazards must be maintained at all times on or adjacent to any public access ways fronting the construction site.

Where public infrastructure is damaged, repair works must be carried out in when and as directed by Council officers (at full Developer cost). Where pedestrian circulation is diverted on to the roadway or verge areas, clear directional signage and protective barricades must be installed in accordance with AS1742-3 (1996) "Traffic Control Devices for Work on Roads". If pedestrian circulation is not satisfactorily maintained across the site frontage, and action is not taken promptly to rectify the defects, Council may undertake proceedings to stop work.

(Reason: Public Safety)

## **Temporary Disposal of Stormwater Runoff**

E4. During construction, stormwater runoff must be disposed in a controlled manner that is compatible with the erosion and sediment controls on the site. Immediately upon completion of any impervious areas on the site (including roofs, driveways, paving) and where the final drainage system is incomplete, the necessary temporary drainage systems must be installed to reasonably manage and control runoff as far as the approved point of stormwater discharge. Such ongoing measures must be to the satisfaction of the Certifying Authority.

(Reason: Stormwater control during construction)

#### Removal of Extra Fabric

E5. Should any portion of the existing building, trees, or curtilage of the site which is indicated on the approved plans to be retained be damaged for whatever reason, all the works in the area of the damaged portion are to cease and written notification of the damage is to be given to Council forthwith. No work is to resume until the written approval of Council to do so is obtained. Failure to comply with the provisions of this condition may result in the Council taking further action including legal proceedings if necessary.

(Reason: To ensure compliance with the terms of this development consent)

## **Dust Emission and Air Quality**

- E6. The following must be complied with at all times:
  - (a) Materials must not be burnt on the site.
  - (b) Vehicles entering and leaving the site with soil or fill material must be covered.
  - (c) Dust suppression measures must be carried out to minimise wind-borne emissions in accordance with the NSW Department of Housing's 1998 guidelines Managing Urban Stormwater: Soils and Construction.

(d) Odour suppression measures must also be carried out where appropriate so as to prevent nuisance occurring at adjoining properties.

(Reason: To ensure residential amenity is maintained in the immediate vicinity)

#### Noise and Vibration

E7. The works must be undertaken in accordance with the "Interim Construction Noise Guideline" published by the NSW Environment Protection Authority, to ensure excessive levels of noise and vibration do not occur so as to minimise adverse effects experienced on any adjoining land.

(Reason: To ensure residential amenity is maintained in the immediate vicinity)

## **Developer's Cost of Work on Council Property**

E8. The developer must bear the cost of all works associated with the development that occurs on Council's property, including the restoration of damaged areas.

(Reason: To ensure the proper management of public land and funds)

# **Special Permits**

E9. Unless otherwise specifically approved in writing by Council, all works, processes, storage of materials, loading and unloading associated with the development must occur entirely on the property.

The developer, owner or builder may apply for specific permits available from Council's Customer Service Centre for the undermentioned activities on Council's property. In the event that a permit is granted by Council for the carrying out of works, processes, storage of materials, loading and unloading associated with the development on Council's property, the development must be carried out in accordance with the requirements of the permit. A minimum of forty-eight (48) hours' notice is required for any permit: -

# 1) On-street mobile plant

E.g. cranes, concrete pumps, cherry-pickers, etc. - restrictions apply to the hours of operation, the area of operation, etc. Separate permits are required for each occasion and each piece of equipment. It is the developer's, owner's and builder's responsibilities to take whatever steps are necessary to ensure that the use of any equipment does not violate adjoining property owner's rights.

(Reason: Proper management of public land)

## 2) Hoardings

Permits are required to erect Class A and Class B hoardings. If an 'A' Class hoarding is to alienate a section of Council's property, that section will require a permit for the occupation of Council's property.

(Reason: Proper management of public land)

# 3) Storage of building materials and building waste containers (skips) on Council's property

Permits to utilise Council property for the storage of building materials and building waste containers (skips) are required for each location. Failure to obtain the relevant permits will result in the building materials or building waste containers (skips) being impounded by Council with no additional notice being given. Storage of building materials and waste containers on open space reserves and parks is prohibited.

(Reason: Proper management of public land)

# 4) Kerbside restrictions, construction zones

Attention is drawn to the existing kerbside restrictions adjacent to the development. Should alteration of existing kerbside restrictions be required, or the provision of a construction zone, the appropriate application must be made and the fee paid to Council. Alternatives to such restrictions may require referral to Council's Traffic Committee and may take considerable time to be resolved. An earlier application is suggested to avoid delays in construction programs.

(Reason: Proper management of public land)

#### **Construction Hours**

E10. Building construction and works must be restricted to within the hours of 7.00 am to 5.00 pm Monday to Friday and on Saturday to within the hours of 8.00 am to 1.00 pm inclusive, with no work on Sundays and Public Holidays.

Demolition and excavation works must be restricted to within the hours of 8.00 am to 5.00 pm Monday to Friday only. For the purposes of this condition:

- a) "Building construction" means any physical activity on the site involved in the erection of a structure, cladding, external finish, formwork, fixture, fitting of service installation and the unloading of plant, machinery, materials or the like.
- b) "Demolition works" means any physical activity to tear down or break up a structure (or part thereof) or surface, or the like, and includes the loading of demolition waste and the unloading of plant or machinery.
- c) "Excavation work" means the use of any excavation machinery and the use of jackhammers, rock breakers, excavators, loaders, or the like, regardless of whether the activities disturb or alter the natural state of the existing ground stratum or are breaking up/removing materials from the site and includes the unloading of plant or machinery associated with excavation work.

All builders, excavators must display, on-site, their twenty-four (24) hour contact telephone number, which is to be clearly visible and legible from any public place adjoining the site.

(Reason: To ensure that works do not interfere with reasonable amenity expectations of residents and the community)

#### **Installation and Maintenance of Sediment Control**

E11. Erosion and sediment controls must be installed and maintained at all times in accordance with the Sediment and erosion control plan submitted and approved with the Construction Certificate.

Erosion and sediment measures must be maintained in accordance with the publication Managing Urban Stormwater: Soils & Construction (4th edition, Landcom, 2004), commonly referred to as the "Blue Book" and can only be removed when development activities have been completed and the site fully stabilised.

(Reason: To protect the environment from the effects of sedimentation and erosion from

development sites)

## **Sediment and Erosion Control Signage**

E12. A durable sign must be erected during building works in a prominent location on site, warning of penalties should appropriate erosion and sedimentation control devices not be maintained. A sign of the type referred to in this condition is available from Council.

(Reason: To protect the environment from the effects of sedimentation and erosion from

development sites)

#### **Site Amenities and Facilities**

E13. Where work involved in the erection and demolition of a building is being carried out, amenities which satisfy applicable occupational health and safety and construction safety regulations, including any WorkCover Authority requirements, must be provided and maintained at all times. The type of work place determines the type of amenities required.

Further information and details can be obtained from the Internet at <a href="https://www.workcover.nsw.gov.au">www.workcover.nsw.gov.au</a>

(Reason: To ensure the health and safety of the community and workers on the site)

# **Health and Safety**

E14. All work undertaken must satisfy applicable occupational health and safety and construction safety regulations, including any WorkCover Authority requirements to prepare a health and safety plan. Site fencing must be installed sufficient to exclude the public from the site. Safety signs must be erected that warn the public to keep out of the site, and provide a contact telephone number for enquiries.

Further information and details regarding occupational health and safety requirements for construction sites can be obtained from the internet at www.workcover.nsw.gov.au

(Reason: To ensure the health and safety of the community and workers on the site)

#### **Prohibition on Use of Pavements**

E15. Building materials must not be placed on Council's footpaths, roadways, parks or grass verges, (unless a permit is obtained from Council beforehand). A suitable sign to this effect must be erected adjacent to the street alignment.

(Reason: To ensure public safety and amenity on public land)

## Plant & Equipment Kept Within Site

E16. All plant and equipment used in the undertaking of the development/ works, including concrete pumps, wagons, lifts, mobile cranes, hoardings etc., must be situated within the boundaries of the site (unless a permit is obtained from Council beforehand) and so placed that all concrete slurry, water, debris and the like must be discharged onto the building site, and is to be contained within the site boundaries.

Details of Council requirements for permits on public land for standing plant, hoardings, storage of materials and construction zones and the like are available on Council's website at <a href="https://www.northsydney.nsw.gov.au">www.northsydney.nsw.gov.au</a>.

(Reason: To ensure public safety and amenity on public land)

#### **Waste Disposal**

E17. All records demonstrating the lawful disposal of waste must be retained and kept readily accessible for inspection by regulatory authorities such as North Sydney Council and the Environmental Protection Authority.

(Reason: To ensure the lawful disposal of construction and demolition waste)

F. Prescribed Conditions imposed under EP&A Act and Regulations and other relevant Legislation

#### **National Construction Code**

F1. All building work must be carried out in accordance with the provisions of the National Construction Code.

(Reason: Prescribed - Statutory)

## **Home Building Act**

- F2. 1) Building work that involves residential building work (within the meaning and exemptions provided in the Home Building Act 1989) for which the *Home Building Act* 1989 requires there to be a contract of insurance under Part 6 of that Act must not be carried out unless the Principal Certifying Authority for the development to which the work relates has given North Sydney Council written notice of the contract of insurance being issued and of the following:
  - a) in the case of work for which a principal contractor is required to be appointed:
    - i) the name and licence number of the principal contractor, and

- ii) the name of the insurer by which the work is insured under Part 6 of that Act, or
- b) in the case of work to be done by an owner-builder:
  - i) the name of the owner-builder, and
  - ii) if the owner-builder is required to hold an owner-builder permit under that Act, the number of the owner-builder permit.
- If arrangements for doing residential building work are changed while the work is in progress such that the information submitted to Council in accordance with this conditions is out of date, work must cease and no further work may be carried out unless the Principal Certifying Authority for the development to which the work relates (not being the Council), has given the Council written notice of the updated information.

Note:

A certificate purporting to be issued by an approved insurer under Part 6 of the Home Building Act 1989 that states that a person is the holder of an insurance policy issued for the purposes of that Part is, for the purposes of this clause, sufficient evidence that the person has complied with the requirements of that Part.

(Reason: Pr

Prescribed - Statutory)

# Appointment of a Principal Certifying Authority (PCA)

F3. Building work, demolition or excavation in accordance with the development consent must not be commenced until the developer has appointed a Principal Certifying Authority for the building work in accordance with the provisions of the EP&A Act and its Regulations.

(Reason:

Statutory; To ensure appropriate safeguarding measures are in place prior to the commencement of any building work, demolition or excavation)

#### **Construction Certificate**

F4. Building work, demolition or excavation in accordance with the development consent must not be commenced until a Construction Certificate for the relevant part of the building work has been issued in accordance with the provisions of the EP&A Act and its Regulations.

(Reason:

Statutory; To ensure appropriate safeguarding measures are in place prior to the commencement of any building work, demolition or excavation)

# **Occupation Certificate**

F5. A person must not commence occupation or use of the whole or any part of a new building (new building includes an altered portion of, or an extension to, an existing building) unless an Occupation Certificate has been issued in relation to the building or part. Only the Principal Certifying Authority appointed for the building work can issue an Occupation Certificate.

(Reason: Statutory)

# **Mandatory Critical Stage Inspections**

F6. Building work must be inspected by the Principal Certifying Authority on the critical stage occasions prescribed by the EP&A Act and its Regulations, and as directed by the appointed Principal Certifying Authority.

(Reason: Statutory)

#### **Excavation/Demolition**

- F7. 1) All excavations and backfilling associated with the erection or demolition of a building must be executed safely and in accordance with appropriate professional standards.
  - 2) All excavations associated with the erection or demolition of a building must be properly guarded and protected to prevent them from being dangerous to life or property.
  - 3) Demolition work must be undertaken in accordance with the provisions of AS2601-Demolition of Structures.

(Reason: To ensure that work is undertaken in a professional and responsible manner and protect adjoining property and persons from potential damage)

## Site Sign

- F8. 1) A sign must be erected in a prominent position on the site
  - a) stating that unauthorised entry to the work site is prohibited;
  - b) showing the name of the principal contractor (or person in charge of the work site), and a telephone number at which that person may be contacted at any time for business purposes and outside working hours; and
  - c) showing the name, address and telephone number of the Principal Certifying Authority for the work.
  - 2) Any such sign must be maintained while to building work or demolition work is being carried out, but must be removed when the work has been completed.

(Reason: Prescribed - Statutory)

# G. Prior to the Issue of an Occupation Certificate

# **Infrastructure Repair and Completion of Works**

- G1. Prior to the issue of any Occupation Certificate any and all works relating to the development:
  - a. to repair and make good any damaged public infrastructure caused as a result of any works relating to the development (including damage caused by, but not limited to, delivery vehicles, waste collection, contractors, sub-contractors, concrete vehicles) must be fully repaired;

to the satisfaction of Council Engineers at no cost to Council.

(Reason: Maintain quality of Public assets)

# **Damage to Adjoining Properties**

G2. All precautions must be taken to prevent any damage likely to be sustained to adjoining properties. Adjoining owner property rights and the need for owner's permission must be observed at all times, including the entering onto land for the purpose of undertaking works.

(Reason: To ensure adjoining owner's property rights are protected)

# **Utility Services**

G3. All utility services shall be adjusted, to the correct levels and/or location/s required by this consent, prior to issue of an occupation certificate. This shall be at no cost to Council.

(Reason: To ensure compliance with the terms of this consent)

# **BASIX Completion Certificate**

G4. In accordance with Clause 154C of the Environmental Planning and Assessment Regulation 2000, prior to issuing a final occupation certificate the Certifying Authority must apply to the Director-General for a BASIX completion receipt.

(Reason: To ensure compliance with the specified BASIX Certificate)

# Works wholly within subject site

G5. Prior to the issue of any occupation certificate, a registered surveyor must certify that the reconstructed deck, roof and posts on the western side of the property are constructed wholly within the confines of the subject site.

(Reason: To ensure consistency with the terms of this consent)

## **Compliance with Certain conditions**

G6. Prior to the issue of any Occupation Certificate, Conditions C12 and C15 must be certified as having been implemented on site and complied with.

(Reason: To ensure the development is completed in accordance with the requirements of this consent)

## I. On-Going / Operational Conditions

#### Non trafficable roof

I1. The roof of the dwelling, beyond the balustrade of the deck, must be non-trafficable except for maintenance purposes.

(Reason: To ensure consistency with the terms of this consent)