# Original signed by Robyn Pearson on 13/5/2020

Date determined: 30/4/2020 Date operates: 13/5/2020 Date lapses: 13/5/2025

Victoria and Geoffrey Rousel C/- Contemporary Architecture 203/10-12 Clarke Street CROWS NEST NSW 2065

> D290/19 MS3(CIS)

# ENVIRONMENTAL PLANNING AND ASSESSMENT ACT, 1979 AS AMENDED NOTICE OF DETERMINATION – Approval

<b>Development Application Number:</b>	290/19
Land to which this applies:	24 Cowdroy Avenue, Cammeray Lot No.: 12, DP: 8933
Applicant:	Victoria and Geoffrey Rousel C/- Contemporary Architecture
Proposal:	Alterations and additions to an existing dwelling house and construction of a new garage outbuilding, and associated landscaping.
Determination of Development Application:	Subject to the provisions of Section 4.17 of the Environmental Planning and Assessment Act 1979, approval has been granted subject to conditions in the notice of determination.
Date of Determination:	30 April 2020
	The matters for consideration as outlined in section 4.15(1) of the Act have been satisfied. The proposed development is permissible within the zone, meets the development standards and relevant provisions of NSLEP 2013 subject to a clause 4.6 exemption and is generally in accordance with the objectives of the NSDCP 2013.
Reason for approval:	The proposed development would result in significant alterations and additions to an existing dwelling house however would not result in its demolition. The primary façade to the foreshore is generally retained and the additions are proposed at the front of the dwelling. The proposed development would not result in adverse overshadowing or overlooking to adjoining properties and would have minimal impacts to the water views available from other properties.

The proposed outbuilding provides a street level garage and entryway that is characteristic of the surrounding development along Cowdroy Avenue. The north eastern corner of this building would result in a small height variation of 400mm to the development standard however the applicant has provided a written request pursuant to clause 4.6 that demonstrates that strict compliance with the development standard would be unreasonable and unnecessary. The minor height variation is due to the variation in the landform and is otherwise considered to be appropriately sited given the topography of the site.

The proposed development is considered reasonable and is recommended for approval.

**Consent to operate from:** 

13 May 2020

Consent will lapse on:

13 May 2025

# **Period of Consent**

Subject to Section 4.20 of the Act, this consent becomes effective and operates from the date listed above. The consent lapses five years after the date of consent in accordance with Section 4.53 of the Act and cannot be extended. To activate this consent, works must physically commence onsite by 13 May 2025.

How community views were taken into account:

The development application was notified in accordance with Council's Community Engagement Protocol and one submission was received. The issues raised in the submission were assessed and conditions imposed to ensure that any unreasonable adverse impact was addressed. Furthermore, standard conditions have been recommended to ensure that construction impacts do not unreasonably impact the surrounding area.

Review of determination and right of appeal:

Within 6 months after the date of notification of the decision, a review of this determination can be requested under Division 8.2 of the Act or an appeal to the Land and Environment Court made pursuant to the provisions of Section 8.7 of the Act. A review of determination should be lodged as soon as possible, and preferably no later two months after the date of notification of the decision to enable the review to be completed within the six-month period.

Plans endorsed by the consent authority – please refer to	o condition A1.
Endorsed for and on behalf of North Sydney Counci	1
DATE	Signature on behalf of consent authority ROBYN PEARSON TEAM LEADER (ASSESSMENTS)

## (i) Conditions

Consent is granted subject to the following conditions imposed pursuant to Section 4.17 of the Environmental Planning & Assessment Act 1979 ("the Act") and the provisions of the Environmental Planning & Assessment Regulation 2000 ("the Regulation") such conditions being reasonable and relevant to the development as assessed pursuant to Section 4.17 of the Act.

## (ii) Definitions

Unless specified otherwise, words have the same meaning as defined by the *Act*, the *Regulation* and the *Interpretation Act* 1987 as in force at the date of consent.

*Applicant* means the applicant for this consent.

**Approved Plans** means the plans endorsed by Council referenced by this consent as amended by conditions of this consent.

AS or AS/NZS means Australian Standard® or Australian/New Zealand Standard®, respectively, published by Standards Australia International Limited.

*NCC* means the National Construction Code as published by the Australian Building Codes Board as in force at the date of issue of any *Construction Certificate*.

Council means North Sydney Council.

Court means the Land and Environment Court.

Local Native Plants means species of native plant endemic to North Sydney LGA.

Stormwater Drainage System means all works, facilities and documentation relating to:

- The collection of stormwater,
- The retention of stormwater,
- The reuse of stormwater,
- The detention of stormwater,
- The controlled release of stormwater; and
- Connections to easements and public stormwater systems.

**Owner** means the owner of the *site* and successors in title to the *site*.

Owner Builder has the same meaning as in the Home Building Act 1989.

**Principal Certifier** for building or subdivision work means the certifier appointed as the principal certifier for the building work under section 6.6 (1) or for the subdivision work under section 6.12 (1).

**Principal Contractor** for building work means the person responsible for the overall coordination and control of the carrying out of the building work.

Note: If any residential building work is involved, the principal contractor must be the holder of a contractor licence under the *Home Building Act 1989*.

**Professional Engineer** has the same meaning as in the NCC.

**Public Place** has the same meaning as in the Local Government Act 1993.

**Road** has the same meaning as in the Roads Act 1993.

SEE means the final version of the Statement of Environmental Effects lodged by the Applicant.

Site means the land being developed subject to this consent.

NSLEP 2013 means North Sydney Local Environmental Plan 2013

*NSDCP 2013* means *North Sydney Development Control Plan 2013* 

*Work* for the purposes of this consent means:

- the use of land in connection with development,
- the subdivision of land,
- the erection of a building,
- the carrying out of any work,
- the use of any site crane, machine, article, material, or thing,
- the storage of any waste, materials, site crane, machine, article, material, or thing,
- the demolition of a building,
- the piling, piercing, cutting, boring, drilling, rock breaking, rock sawing or excavation of land,
- the delivery to or removal from the *site* of any machine, article, material, or thing, or
- the occupation of the *site* by any person unless authorised by an *occupation certificate*.

Note: **Interpretation of Conditions** – Where there is any need to obtain an interpretation of the intent of any condition this must be done in writing to Council and confirmed in writing by Council.

# INDEX OF CONDITIONS

		Page No.
<b>A.</b>	Conditions that Identify Approved Plans	
A1.	Development in Accordance with Plans/documentation	9
A2.	Plans on Site	9
A3.	External Finishes & Materials	10
В.	Matters to be Completed before the lodgement of an Application for a Construction Certification	ficate
B1.	Construction and Traffic Management Plan (Major Das & sites with difficult access)	10
<i>C</i> .	Prior to the Issue of a Construction Certificate (and ongoing, where indicated)	
C1.	Amendments to Plans – Garage & Front Fence	12
C2.	Waterfront Access Stair deleted	12
C3.	Dilapidation Report Damage to Public Infrastructure	12
C4.	Dilapidation Report Private Property (Excavation)	13
C5.	Structural Adequacy of Adjoining Properties – Excavation Works	14
C6.	Structural Adequacy of Existing Building	14
C7.	Geotechnical Report	14
C8.	Sediment Control	16
C9.	Waste Management Plan	16
C10.	Skylight(s)	17
C11.	Roofing Materials - Reflectivity	17
C12.	Work Zone	17
C13.	Obtain Driveway Crossing Permit under S.138 Roads Act 1993	18
C14.	Stormwater Management and Disposal Design Plan –	
	Construction Issue Detail	19
C15.	Bond for Damage and Completion of Infrastructure Works – Stormwater,	
	Kerb and Gutter, Footpaths, Vehicular Crossing and Road Pavement	20
C16.	Protection of Trees	21
C17.	Protection of Trees	21
C18.	Approval for Tree Removal	22
C19.	Asbestos & Hazardous Material Survey	22
C20.	Air Conditioners in Residential Premises	23
C21.	Swimming Pool Pumps on Residential Premises	23
C22.	Pool Access	24
C23.	Pool Filter	24
C24.	Security Deposit/ Guarantee Schedule	24
C25.	BASIX Certificate	25
C26.	Amendments to the Landscape Plan	25
D.	Prior to the Commencement of any Works (and continuing where indicated)	
D1.	Protection of Trees	26
D2.	Public Liability Insurance – Works on Public Land	26
D3.	Sydney Water Approvals	26
D4.	Installation of Tree Protection prior to any commencement	27

<b>E</b> .	During Demolition and Building Work	
E1.	Parking Restrictions	27
E2.	Road Reserve Safety	27
E3.	Temporary Disposal of Stormwater Runoff	27
E4.	Geotechnical Stability during Works	28
E5.	Council Inspection of Public Infrastructure Works	28
E6.	Progress Survey	28
E7.	Removal of Extra Fabric	29
E8.	Dust Emission and Air Quality	29
E9.	Noise and Vibration	29
E10.	No Work on Public Open Space	30
E11.	Developer's Cost of Work on Council Property	30
E12.	No Removal of Trees on Public Property	30
E13.	Protection of Trees	30
E14.	Trees to be Removed	31
E15.	Special Permits	31
E16.	Construction Hours	32
E17.	Installation and Maintenance of Sediment Control	33
E18.	Sediment and Erosion Control Signage	33
E19.	Site Amenities and Facilities	33
E20.	Health and Safety	33
E21.	Prohibition on Use of Pavements	34
E22.	Plant & Equipment Kept Within Site	34
E23.	Waste Disposal	34
E24.	Asbestos Removal	34
E25.	Service Adjustments	34
F.	Prescribed Conditions imposed under EP&A Act and Regulations and other relevant Legislation	
F1.	National Construction Code	35
F2.	Home Building Act	35
F3.	Appointment of a Principal Certifier (previously known as a PCA)	36
F4.	Construction Certificate	36
F5.	Occupation Certificate	36
F6.	Critical Stage Inspections	36
F7.	Commencement of Works	36
F8.	Excavation/Demolition	37
F9.	Protection of Public Places	37
F10.	Site Sign	37
G.	Prior to the Issue of an Occupation Certificate	
G1.	Infrastructure Repair and Completion of Works	38
G2.	Noise from Plant	38
G3.	Certification- Civil Works	38
G4.	Pool Access	39
G5.	Pool Safety Requirements	39
G6.	Damage to Adjoining Properties	39
G0. G7.	Utility Services	39
G7. G8.	Certification of Tree Condition	40
G9.	Height	40
G10.	Landscaping	40
~ · · · ·		rU

# RE: 24 COWDROY AVENUE, CAMMERAY DEVELOPMENT CONSENT NO. 290/19

Page !	<b>8</b> o	f 41	l
--------	------------	------	---

I.	On-Going / Operational Conditions	
I1.	Pool Filter	41
I2.	Single Occupancy	41
I3.	Maintenance of Approved Landscaping	41

# A. Conditions that Identify Approved Plans

# **Development in Accordance with Plans/documentation**

A1. The development must be carried out in accordance with the following drawings and documentation and endorsed with Council's approval stamp, except where amended by the following conditions of this consent.

Plan No.	Issue	Title	Dated	Drawn by	Received
DA02	В	Site Plan	17/03/2020		17/03/2020
DA11	A	Lower Ground Floor Plan (L1)	17/09/2019		17/03/2020
DA12	В	Ground Floor Plan (L2) Part 1	02/03/2019		17/03/2020
DA13	В	Ground Floor Plan (L2) Part 1	02/03/2019		17/03/2020
DA14	В	Workshop and Gym Plan (L3)	02/03/2019		17/03/2020
DA15	В	"Teenage Retreat" Plan (L4)	02/03/2019		17/03/2020
DA16	В	Garage Plan (L5)	02/03/2019		17/03/2020
DA17	С	Roof Plan, Part 1	17/03/2020		17/03/2020
DA18	В	Roof Plan, Part 2	17/03/2020		17/03/2020
DA19	С	Elevation 1 and Street	17/03/2020	Company of the compan	17/03/2020
DA20	В	Elevation 2	17/03/2020	Contemporary	17/03/2020
DA21	В	Elevation 3	17/03/2020	Architecture	17/03/2020
DA22	В	Elevation 4	17/03/2020		17/03/2020
DA23	A	Elevation 5	17/09/2019		17/03/2020
DA24	A	Section A, Part 1	17/09/2019		17/03/2020
DA25	A	Section A, Part 2	17/09/2019		17/03/2020
DA26	A	Section B, Part 1	17/09/2019		17/03/2020
DA27	A	Section B, Part 2	17/09/2019		17/03/2020
DA28	A	Section C, Part 1	17/09/2019	7	17/03/2020
DA29	A	Section C, Part 2	17/09/2019		17/03/2020
DA30	A	Section D & E	17/09/2019		17/03/2020
L01 of 1	A	Landscape Plan	11/09/2019	Hortus Design	23/09/2019

(Reason: To ensure that the form of the development undertaken is in accordance with the determination of Council, Public Information)

## **Plans on Site**

A2. A copy of all stamped approved plans, specifications and documents (including the plans, specifications and documents submitted and approved with the Construction Certificate) must be kept on site at all times so as to be readily available for perusal by any officer of Council or the Principal Certifying Authority.

All documents kept on site in accordance with this condition must be provided to any officer of the Council or the certifying authority upon their request.

(Reason: To ensure that the form of the development undertaken is in accordance with the determination of Council, Public Information and to ensure ongoing compliance)

## **External Finishes & Materials**

A3. External finishes and materials must be in accordance with the submitted *Finishes Schedule*, drawing reference *DA40*, dated *18 October 2019*, prepared by *Contemporary Architecture* and received by Council on *18 October 2019* unless otherwise modified by Council in writing.

(Reason: To ensure that the form of the development undertaken is in accordance with the determination of Council, Public Information)

B. Matters to be Completed before the lodgement of an Application for a Construction Certificate

# Construction and Traffic Management Plan (Major DAs & sites with difficult access)

- B1. Prior to issue of any Construction Certificate, a Construction and Traffic Management Plan must be prepared. The following matters must be specifically addressed in this Plan:
  - a) A plan view (min 1:100 scale) of the entire site and frontage roadways indicating:
    - i. Dedicated construction site entrances and exits, controlled by a certified traffic controller, to safely manage pedestrians and construction related vehicles in the frontage roadways;
    - ii. Signage type and location to manage pedestrians in the vicinity;
    - iii. The locations of any proposed Work Zones in the frontage roadways;
    - iv. Locations and type of any hoardings proposed;
    - v. Area of site sheds and the like;
    - vi. Location of any proposed crane standing areas;
    - vii. A dedicated unloading and loading point within the site for all construction vehicles, plant and deliveries;
    - viii. Material, plant and spoil bin storage areas within the site, where all materials are to be dropped off and collected; and
    - ix. The provision of an on-site parking area for employees, tradesperson and construction vehicles as far as possible.
  - b) A Traffic Control Plan(s) for the site incorporating the following:
    - i. Traffic control measures proposed in the road reserve that are in accordance with the RMS publication "Traffic Control Worksite Manual" and designed by a person licensed to do so (minimum RMS 'red card' qualification).
    - ii. The main stages of the development requiring specific construction management measures are to be identified and specific traffic control measures identified for each.
  - c) A detailed description and map of the proposed route for vehicles involved in spoil removal, material delivery and machine floatage must be provided detailing light traffic roads and those subject to a load or height limit must be avoided at all time.

A copy of this route is to be made available to all contractors, and must be clearly depicted at a location within the site.

- d) A Waste Management Plan in accordance with the provisions of Part B Section 19 of the North Sydney DCP 2013 must be provided. The Waste Management Plan must include, but not be limited to, the estimated volume of waste and method of disposal for the construction and operation phases of the development, design of on-site waste storage and recycling area and administrative arrangements for waste and recycling management during the construction process;
- (e) Evidence of RMS concurrence where construction access is provided directly or within 20m of an Arterial and/or Classified Road:
- (f) A schedule of site inductions to be held on regular occasions and as determined necessary to ensure all new employees are aware of the construction management obligations. These must specify that construction-related vehicles to comply with the approved requirements; and
- (g) For those construction personnel that drive to the site, the Site Manager shall attempt to provide on-site parking so that their personnel's vehicles do not impact on the current parking demand in the area.

A suitably qualified and experienced traffic engineer or consultant must prepare the Construction and Traffic Management Plan.

As this plan has a direct impact on the local road network, it must be submitted to and reviewed by Council prior to the issue of any Construction Certificate. A certificate of compliance with this condition from Council's Development Engineers as to the result of this review must be obtained and must be submitted as part of the supporting documentation lodged with the Certifying Authority for approval of the application for a Construction Certificate.

The construction management measures contained in the approved Construction and Traffic Management Plan must be implemented prior to the commencement of, and during, works onsite. To obtain the permit, an application must be made to Council on a 'Application to satisfy development consent' form with payment of the adopted assessment.

All works must be undertaken in accordance with the approved Construction and Traffic Management Plan.

A copy of the approved Construction and Traffic Management Plan must be kept on the site at all times and be made available to any officer of the Council on request.

#### Notes:

- 1) North Sydney Council's adopted fee for certification of compliance with this condition must be paid upon lodgement, or in any event, prior to the issue of the relevant approval.
- 2) Any use of Council property will require appropriate approvals and demonstration of liability insurances prior to such work commencing.
- 3) Failure to provide complete and detailed information may result in delays. It is recommended that your Construction and Traffic Management Plan be lodged with Council as early as possible.

4) Dependent on the circumstances of the site, Council may request additional information to that detailed in the condition above.

(Reason:

To ensure appropriate measures have been considered for site access, storage and the operation of the site during all phases of the demolition and construction process in a manner that respects adjoining owner's property rights and residential amenity in the locality, without unreasonable inconvenience to the community)

C. Prior to the Issue of a Construction Certificate (and ongoing, where indicated)

# Amendment to Plans - Garage and Front Fence

- C1. The following amendments are to be provided:
  - a) The splayed portion of the front fence adjacent to the eastern side of the garage is to be of an open design consistent with the remainder of the proposed front fence.
  - b) The solid portion of the new front fence is to be constructed of or clad with sandstone.
  - c) The garage door is to be a panel lift or segmented panel door and is not to be specified as a roller door. The door is to be recessed behind the front wall of the garage.

The Certifying Authority must also ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To minimise the extent of blank walls fronting the street)

# **Waterfront Access Stair Deleted**

C2. The masonry waterfront access stairs shown on the Lower Ground Floor Plan (L1), drawing reference *DA11*, prepared by *Contemporary Architecture*, dated *17/03/2020* and received *17/03/2020* is to be deleted and the existing staircase repaired.

The Certifying Authority must also ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To retain the characteristic natural rock outcrops along the foreshore area)

## **Dilapidation Report Damage to Public Infrastructure**

C3. A dilapidation survey and report (including photographic record) must be prepared by a suitably qualified consultant which details the pre-developed condition of the existing public infrastructure in the vicinity of the development site. Particular attention must be paid to accurately recording any pre-developed damaged areas so that Council is fully informed when assessing any damage to public infrastructure caused as a result of the development. A copy of the dilapidation survey and report is to be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate.

The developer may be held liable for all damage to public infrastructure in the vicinity of the site, where such damage is not accurately recorded and demonstrated as pre-existing under the requirements of this condition.

The developer shall bear the cost of carrying out works to restore all public infrastructure damaged as a result of the carrying out of the development, and no occupation of the development shall occur until damage caused as a result of the carrying out of the development is rectified.

A copy of the dilapidation survey and report must be lodged with North Sydney Council by the Certifying Authority with submission of the Construction Certificate documentation.

(Reason: To record the condition of public infrastructure prior to the commencement of construction)

## **Dilapidation Report Private Property (Excavation)**

C4. A full dilapidation survey and report on the visible and structural condition of all neighbouring structures within the 'zone of influence' of the required excavations must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The zone of influence is to be defined as the horizontal distance from the edge of the excavation face to twice the excavation depth.

The dilapidation report and survey is to be prepared by a consulting structural/geotechnical engineer agreed to by both the applicant and the owner of any affected adjoining property.

All costs incurred in achieving compliance with this condition shall be borne by the person entitled to act on this Consent.

In the event that access for undertaking the dilapidation survey is denied by an adjoining owner, the applicant MUST DEMONSTRATE, in writing, to the satisfaction of Council that all reasonable steps have been taken to obtain access and advise the affected property owner of the reason for the survey and that these steps have failed. Written concurrence must be obtained from Council in such circumstances.

Note: This documentation is for record keeping purposes only, and may be used by the developer or affected property owner to assist in any action required to resolve any dispute over damage to adjoining properties arising from the works. It is in the applicant's and adjoining owner's interest for it to be as full and detailed as possible.

(Reason: To record the condition of property/ies prior to the commencement of construction)

# Structural Adequacy of Adjoining Properties – Excavation Works

C5. A report prepared by an appropriately qualified and practising structural engineer detailing the structural adequacy of adjoining property No. 22 Cowdroy Avenue, which certifies their ability to withstand the proposed excavation and outlines any measures required to be implemented to ensure that no damage will occur to the adjoining property during the course of the works, must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The measures outlined in the certified report must be complied with at all times.

(Reason: To ensure the protection and structural integrity of adjoining properties in close proximity during excavation works)

# Structural Adequacy of Existing Building

C6. A report prepared by an appropriately qualified and practising structural engineer, certifying the structural adequacy of the property and its ability to withstand the proposed additional, or altered structural loads during all stages of construction shall be submitted to the Certifying Authority for approval prior to issue of any Construction Certificate. The certified report must also include all details of the methodology to be employed in construction phases to achieve the above requirements. The methodology in the certified report must be complied with at all times.

(Reason: To ensure the structural integrity of the building is maintained)

# **Geotechnical Report**

- C7. Prior to issue of any Construction Certificate a Geotechnical/Civil Engineering report must be prepared which addresses at a minimum (but is not limited to) the following:
  - a) the type and extent of substrata formations by the provision of a minimum of four (4) representative bore hole logs which are to provide a full description of all material from ground surface to 1.0m below the finished basement floor level and include the location and description of any anomalies encountered in the profile. The surface and depth of the bore hole logs must be related to Australian Height Datum;
  - b) the appropriate means of excavation/shoring in light of point (a) above and proximity to adjacent property and structures. Potential vibration caused by method of excavation and potential settlements affecting nearby footings/foundations must be discussed and mechanisms to ameliorate any such impacts recommended;
  - c) the proposed method to temporarily and permanently support the excavation for the basement adjacent to adjoining property, structures and road reserve if nearby (full support must be provided within the subject site);
  - d) the existing groundwater levels in relation to the basement structure, where influenced;

- e) the drawdown effects on adjacent properties (including road reserve), if any, the basement excavation will have on groundwater together with the appropriate construction methods to be utilised in controlling groundwater. Where it is considered there is the potential for the development to create a "dam" for natural groundwater flows, a groundwater drainage system must be designed to transfer groundwater through or under the proposed development without a change in the range of the natural groundwater level fluctuations. Where an impediment to the natural flow path is constructed, artificial drains such as perimeter drains and through drainage may be utilised; and
- f) recommendations to allow the satisfactory implementation of the works. An implementation program is to be prepared along with a suitable monitoring program including control levels for vibration, shoring support, ground level and groundwater level movements during construction. The implementation program is to nominate suitable hold points at the various stages of the works for verification of the design intent before sign-off and before proceeding with subsequent stages.

The geotechnical report must be prepared by an appropriately qualified consulting geotechnical/ hydrogeological engineer with previous experience in such investigations and reporting.

It is the responsibility of the consulting geotechnical/ hydrological specialist to undertake the appropriate investigations, reporting and specialist recommendations to ensure a reasonable level of protection to adjacent property and structures both during and after construction. The report must contain site-specific geotechnical recommendations and shall specify the necessary hold/inspection points by relevant professionals as appropriate.

The design principles for the geotechnical report are as follows:

- a) no ground settlement or movement is to be induced which is sufficient enough to cause an adverse impact to adjoining property and/or infrastructure;
- b) no changes to the ground water level are to occur as a result of the development that are sufficient enough to cause an adverse impact to the surrounding property and infrastructure;
- c) no changes to the ground water level are to occur during the construction of the development that are sufficient enough to cause an adverse impact to the surrounding property and infrastructure;
- d) vibration is to be minimised or eliminated to ensure no adverse impact on the surrounding property and infrastructure occurs, as a result of the construction of the development;
- e) appropriate support and retention systems are to be recommended and suitable designs prepared to allow the proposed development to comply with these Design Principles; and
- f) an adverse impact can be assumed to be crack damage as identified within the relevant Australian Standard for determining such damage.

The report, satisfying the requirements of this condition, must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate.

The professional recommendations, implementation program, monitoring program, mitigation measures and the like contained in the report must be implemented in full during the relevant stages of excavation and construction.

(Reason: To ensure the structural integrity of the subject site and adjoining sites during

the excavation process)

## **Sediment Control**

C8. Where construction or excavation activity requires the disturbance of the soil surface or existing vegetation, erosion and sediment control techniques, as a minimum, are to be in accordance with the publication Managing Urban Stormwater: Soils & Construction (4th edition, Landcom, 2004) commonly referred to as the "Blue Book" or a suitable and effective alternative method.

A Sediment Control Plan must be prepared and submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate and prior to any works commencing. The Sediment Control Plan must be consistent with the Blue Book and disclose:

- a) All details of drainage to protect and drain the site during the construction processes;
- b) All sediment control devices, barriers and the like;
- c) Sedimentation tanks, ponds or the like;
- d) Covering materials and methods; and
- e) A schedule and programme of the sequence of the sediment and erosion control works or devices to be installed and maintained.
- f) Methods for the temporary and controlled disposal of stormwater during construction.

All works must be undertaken in accordance with the approved Sediment Control plan.

The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To protect the environment from the effects of sedimentation and erosion from development sites)

## **Waste Management Plan**

C9. A Waste Management Plan is to be submitted for approval by the Certifying Authority prior to the issue of any Construction Certificate. The plan must include, but not be limited to:

- a) The estimated volume of waste and method of disposal for the construction and operation phases of the development;
- b) The design of the on-site waste storage and recycling area; and
- c) Administrative arrangements for waste and recycling management during the construction process.

The approved Waste Management Plan must be complied with at all times in the carrying out of the development.

(Reason: To encourage the minimisation of waste and recycling of building waste)

# Skylight(s)

C10. Skylight flashing(s) and frame(s) to be coloured to match the roof material. Skylight(s) to sit no higher than 100mm above roof plane when in a closed position. Plans and specifications which comply with this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate.

The Certifying Authority must ensure that the building plans and specifications submitted fully satisfy the requirements of this condition.

(Reason: To minimise the visual impact of the skylight(s) on the roof plane)

# **Roofing Materials - Reflectivity**

C11. Roofing materials must be factory pre-finished with low glare and reflectivity properties to be compatible with the colours of neighbouring buildings. The selected roofing material must not cause a glare nuisance or excessive reflectivity to adjoining or nearby properties. Plans and specifications which comply with this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To ensure that excessive glare or reflectivity nuisance from roofing materials does not occur as a result of the development)

## **Work Zone**

C12. If a Work Zone is proposed, an application must be made to the North Sydney Local Traffic Committee to install the 'Work Zone'. A Work Zone permit is required to be issued by the Council prior to the issue of any Construction Certificate.

Work Zones are provided specifically for the set down and pick up of materials and not for the parking of private vehicles associated with the site. Works Zones will generally not be approved where there is sufficient space on-site for the setting down and picking up of goods being taken to or from a construction site. If the Works Zone is approved by the Committee, the Applicant must obtain a written copy of the related resolution from the North Sydney Local Traffic Committee and submit a copy of this to the Certifying Authority to enable issue of the Construction Certificate.

Where approval of the 'Work Zone' is given by the Committee, the requirements of the Committee, including installation of the necessary 'Work Zone' signage and payment of any fees, must occur prior to commencement of any works on the site. Further, at the expiration of the Work Zone approval, the developer is required to remove the Work Zone signs and reinstate any previous signs, all at the developer's cost. The requirements imposed by the Committee on the Work Zone permit (or permits) must be complied with at all times.

(Reason: Amenity and convenience during construction)

# Obtain Driveway Crossing Permit under S.138 Roads Act 1993

- C13. Prior to the issue of the Construction Certificate, North Sydney Council must issue the applicant with a driveway crossing and road infrastructure works permit to suit the approved off-street parking facilities. To obtain the permit, an application must be made to Council on a 'Vehicular Access Application' form with payment of the adopted assessment/inspection fees. Council will require civil design construction drawings and certification from the applicant's Civil Engineer to verify design details and enable permit issue. The responsibility for accuracy of the design fully rests with the designing engineer. All responsibility on implementation and supervision of works specified on design plans fully rests on designing engineer or whoever is chosen to be applicant's engineering representative. The civil design drawings shall detail the following infrastructure construction requirements of Council in relation to the consent:
  - a) The proposed vehicular access ways must comply with AS 2890.1 and Council's current Vehicular Access Application Guidelines and Specification (gutter bridges not permitted) to ensure that a B85 vehicle will not scrape/strike the surface of the carriageway, layback, vehicular crossing or parking floor.
  - b) The redundant layback crossing on Cowdroy Avenue must be reinstated as upright kerb gutter and concrete footpath.
  - c) The width of the vehicular layback must be 8.0m (including the wings).
  - d) The vehicular laybacks must be set square to the kerb.
  - e) The boundary footpath levels must match the existing levels and shall not be altered unless agreed to by Council.
  - f) Alignment levels at the boundary have an important impact on the proposed levels for new driveway. The works must not start until confirmation of boundary alignment levels from registered surveyor. Council has the authority to remove any unauthorized works at the cost of the property owner.
  - g) The Certifying Authority must ensure that the internal property levels at boundary matches council's confirmed boundary levels.
  - h) The gutter invert levels and road shoulder levels on Cowdroy Avenue must stay unchanged.
  - i) The kerb gutter, and 600 mm road shoulder wide- strip, adjacent to all new layback and gutter works, on Cowdroy Avenue must be reconstructed, to ensure uniformity in the road reserve.
  - j) The footpath on Cowdroy Avenue must be reconstructed and is to be transitioned at least 1.5m on both sides of the crossing to ensure uniformity on the footpath.
  - k) Any twisting of driveway access to ensure vehicles do not scrape must occur wholly within the subject property.
  - 1) All inspection openings, utility services must be adjusted to match the proposed driveway levels and location.

- m) The design detail has to be provided with **vehicular access application** and must include sections along centre-line and extremities of the crossing at a scale of 1:25. Sections are to be taken from the centre of the roadway through to the parking area itself and shall include all changes of grade and levels, **both** existing and proposed.
- n) A longitudinal section along the footpath property boundary at a scale of 1:50 is required and shall include all changes of grade and levels, **both** existing and proposed.
- o) The sections must show the calculated clearance to the underside of any overhead structure.
- p) Pipelines within the footpath area must be hot dipped galvanized rectangular steel hollow section with a minimum wall thickness of 4.0 millimetres and a section height of 100 millimetres.
- q) Any footpath panel on Cowdroy Avenue that is disturbed for the purpose of stormwater connection must be reconstructed as a whole panel.

All driveway and infrastructure works on the road reserve must proceed in accordance with the terms of the permit issued by Council. Inspections by Council will be required as specified on the permit. The Certifying Authority issuing the Construction Certificate must ensure that the permit issued by Council is obtained prior to its issue, is referenced on and accompanies the relevant Construction Certificate issued.

(Reason: To facilitate appropriate vehicular access to private sites, without disruption to pedestrian and vehicular traffic)

# Stormwater Management and Disposal Design Plan - Construction Issue Detail

- C14. Prior to issue of the Construction Certificate, the applicant shall have a site drainage management plan prepared by a qualified drainage design engineer. The site drainage management plan must detail the following requirements of North Sydney Council:
  - a) Compliance with BCA drainage requirements, Councils Engineering Performance guide and current Australian Standards and guidelines, such as AS/NZ3500.3.2 1998, National Plumbing and Drainage Code.
  - b) Stormwater runoff and subsoil drainage generated by the approved dwellings must be conveyed in a controlled manner by gravity to the Long Bay waters
  - c) Any redundant stormwater pipelines within the footpath area shall be removed and the footpath and kerb reinstated.
  - d) Pipelines within the footpath area shall be hot dipped galvanized steel rectangular hollow section with a minimum wall thickness of 4.0 millimetres and a section height of 100 millimetres.
  - e) Any footpath panel on Cowdroy Avenue disturbed for the purpose of stormwater connection shall be reconstructed as whole panel.
  - f) Provision is to be made for the collection and disposal in an approved manner of any overland flow entering the subject property or concentrated as a result of the proposed works.
  - g) All sub-soil seepage drainage shall be discharged via a suitable silt arrester pit. Details of all plans certified as being adequate for their intended purpose and complaint with the provisions of AS3500.3.2 by an appropriately qualified and practising civil engineer, shall be submitted with the application for a Construction Certificate.

- h) The design and installation of the Rainwater Tanks shall comply with Basix and **Sydney Water** requirements. Overflow from tank shall be connected by gravity to the stormwater disposal system.
- i) Prevent any stormwater egress into adjacent properties by creating physical barriers and surface drainage interception.

Details demonstrating compliance are to be submitted with the Construction Certificate.

The Certifying Authority issuing the Construction Certificate must ensure that the approved drainage plan and specifications, satisfying the requirements of this condition, is referenced on and accompanies the Construction Certificate.

(Reason To ensure controlled stormwater management and disposal without nuisance)

# Bond for Damage and Completion of Infrastructure Works – Stormwater, Kerb and Gutter, Footpaths, Vehicular Crossing and Road Pavement

- C15. Prior to the issue of any Construction Certificate, security deposit or bank guarantee must be provided to Council to the sum of \$5,000.00 to be held by Council for the payment of cost for any/all of the following:
  - a) making good any damage caused to any property of the Council as a consequence of the doing of anything to which this consent relates,
  - b) completing any public work (such as road work, kerbing and guttering, footway construction, stormwater drainage and <u>environmental</u> <u>controls</u>) required in connection with this consent
  - c) remedying any defects in any such public work that arise within 6 months after the work is completed.

The security required by this condition and in the schedule contained later in these conditions must be provided by way of a deposit with the Council; or other such guarantee that is satisfactory to Council (such as a bank guarantee). Any guarantee provided as security must name North Sydney Council as the nominated beneficiary and must not be subject to an expiry date.

The security will be refundable following the expiration of 6 months from the issue of any final Occupation Certificate or completion of public work required to be completed (whichever is the latest) but only upon inspection and release by Council's Engineers.

Council shall have full authority to make use of the bond for such restoration works as deemed necessary by Council in circumstances including the following: -

- where the damage constitutes a hazard in which case Council may make use of the security immediately;
- the applicant has not repaired or commenced repairing damage within 48 hours of the issue by Council in writing of instructions to undertake such repairs or works;
- works in the public road associated with the development are to an unacceptable quality; and

• the Certifying Authority must ensure that security is provided to North Sydney Council prior to issue of any Construction Certificate.

(Reason: To ensure appropriate security for works on public land and an appropriate

quality for new public infrastructure)

## **Tree Protection**

C16. The tree protection measures contained in the arborist report prepared by Hugh the Arborist, dated 2 July 2019, and received by Council on 20 September 2019, shall be shown clearly on the Construction Certificate drawings. Plans and specifications showing the said tree protection measures must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure the construction plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To ensure that appropriate tree protection measures are shown on construction

drawings)

## **Protection of Trees**

C17. The following tree(s) are required to be protected and retained as part of the development consent in accordance with AS 4970-2009 – Protection of trees on development sites:

Tree	Location	Height
Tree 7 Archontophoenix cunninghamiana	Front setback (Cowdroy Ave)	10m
Tree 8-10 Cupressus torulosa	Front setback (Cowdroy Ave)	16m
Tree 11 Washingtonia robusta	Front setback (Cowdroy Ave)	10m
Tree 12 Dypsis lutescens	Front setback (Cowdroy Ave)	6m
Tree 14 Dracena draco	Eastern boundary (middle level)	5m
Tree 15 Archontophoenix cunninghamiana	Eastern boundary (middle level)	12m
Tree 20 Syagrus romanzoffianum	Western boundary – pool level	11m
G1 Mixed species	Gardens below pool level	5m

Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

Any tree(s) shown as being retained on the approved plans (regardless of whether they are listed in the above schedule or not) must be protected and retained in accordance with this condition.

(Reason: Protection of existing environmental and community assets)

# **Approval for Tree Removal**

C18. The following tree(s) are approved for removal in accordance with the development consent:

Trees to be removed	Location	Height
Tree 1 <i>Yucca</i> spp.	Front setback (Cowdroy Ave)	6m
Tree 2 Nerium oleander	Front setback (Cowdroy Ave)	6m
Tree 3 Howea forsteriana	Front setback (Cowdroy Ave)	6m
Tree 4 Syagrus romanzoffianum	Front setback (Cowdroy Ave)	12m
Tree 5 Eriobotyra japonica	Front setback (Cowdroy Ave)	7m
Tree 6 Michelia figo	Front setback (Cowdroy Ave)	5m
Tree 13 Cyathea cooperi	Front setback (Cowdroy Ave)	5m
Tree 16 Howea forsteriana	Eastern boundary (middle level)	11m
Trees17-19 Cupressus sempervirens	Rear of existing garage	8m

Removal or pruning of any other tree on the site is not approved, excluding species exempt under Council's Tree Preservation Order.

Any tree(s) shown as being retained on the approved plans (regardless of whether they are listed in the above schedule or not) must be protected and retained in accordance with this condition.

(Reason: Protection of existing environmental and community assets)

# **Asbestos Material Survey**

C19. A report must be prepared by a suitably qualified person in relation to the existing building fabric to be demolished and/or disturbed identifying the presence or otherwise of asbestos contamination and, if asbestos contamination is present, making recommendations as to the work required to safely address the contamination.

Any demolition works or other works identified in the report as having to be carried out must be carried out in accordance with the recommendations of the report and the following:

- a) the removal of asbestos must be undertaken by a WorkCover licensed contractor;
- b) all removal must be in strict accordance with the requirements of the WorkCover Authority in relation to the removal, handling and disposal of material containing asbestos and any Work Safe Australia requirements.
- c) during the removal of any asbestos a sign stating "DANGER ASBESTOS REMOVAL IN PROGRESS" must be erected in a visible position at the boundary of the site; and
- d) Waste disposal receipts must be provided to the Certifying Authority as proof of correct disposal of asbestos laden waste.

The report must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the report, and other plans, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To ensure the long term health of workers on site and occupants of the building is not put at risk unnecessarily)

#### **Air Conditioners in Residential Premises**

- C20. The use of any air conditioner installed on the premises must comply with the requirements of the Protection of the Environment Operations (Noise Control) Regulations 2008 and State Environmental Planning Policy (Infrastructure) 2007 and must not:
  - (a) emit a noise that is audible within a habitable room in any affected residence (regardless of whether any door or window to that room is open);
    - (i) before 8.00am and after 10.00pm on any Saturday, Sunday or Public Holiday; or
    - (ii) before 7.00am or after 10.00pm on any other day
  - (b) cause an LAeq(15min) which exceeds the RBL background noise level by more than 5dB when measured at the boundary of any affected residence. The modifying factor adjustments in Section 4 of the EPA Industrial Noise Policy will be applied.

"affected residence" includes residential premises (including any lot in the strata scheme or another strata scheme), premises for short-term accommodation and hospitals.

"boundary" includes any window or elevated window of an affected residence.

Terms in this condition have the same meaning as in the Noise Guide for Local Government and the Industrial Noise Policy published by the NSW Environment Protection Authority.

(Reason: To maintain residential amenity)

## **Swimming Pool Pumps on Residential Premises**

- C21. The Certifying Authority must be satisfied that the swimming pool pump to be installed on the premises must not:
  - a) emit a noise that is audible within a habitable room in any affected residence (regardless of whether any door or window to that room is open);
    - (i) before 8.00am and after 8.00pm on any Sunday or Public Holiday; or
    - (ii) before 7.00am or after 8.00pm on any other day
  - (c) cause an LAeq(15min) which exceeds the RBL background noise level by more than 5dB when measured at the boundary of any affected residence. The modifying factor adjustments in Section 4 of the EPA Industrial Noise Policy shall be applied.

"affected residence" includes residential premises (including any lot in the strata scheme or another strata scheme), premises for short-term accommodation and hospitals.

"boundary" includes any window or elevated window of an affected residence.

Terms in this condition have the same meaning as in the Noise Guide for Local Government and the Industrial Noise Policy published by the NSW Environment Protection Authority.

Details demonstrating compliance with the requirements of this condition must be submitted to the Certifying Authority prior to the issue of the Construction Certificate.

(Reason: To maintain residential amenity)

#### **Pool Access**

C22. Access to the pool must be restricted by a child resistant barrier in accordance with the regulations prescribed in the Swimming Pools Act 1992, and the barrier is to conform to the requirements of the applicable Australian Standard. Plans and specifications complying with this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To ensure the safety of children and make applicant aware of the need to comply with applicable pool fencing legislation)

#### **Pool Filter**

C23. The pool filtering equipment must be encased by a soundproof cover and must be located six (6) metres from any habitable room in a dwelling on a neighbouring property. Plans and specifications complying with this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To ensure noise generated by equipment does not result in offensive noise)

# **Security Deposit/ Guarantee Schedule**

C24. All fees and security deposits/ guarantees in accordance with the schedule below must be provided to Council prior to the issue of any Construction Certificate:

Security deposit/ guarantee	Amount (\$)
Engineering Construction Bond	\$5,000.00
TOTAL BONDS	\$5,000.00

The security required by the above schedule must be provided by way of a deposit with the Council; or other such guarantee that is satisfactory to Council (such as a bank guarantee). Any guarantee provided as security must name North Sydney Council as the nominated beneficiary and must not be subject to an expiry date.

(Reason: Compliance with the development consent)

#### **BASIX** Certificate

C25. Under clause 97A(3) of the Environmental Planning & Assessment Regulation 2000, it is a condition of this development consent that all the commitments listed in BASIX Certificate No. A349567 dated 20 September 2019 for the development are fulfilled. Plans and specifications complying with this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To ensure the proposed development will meet the Government's requirements for sustainability and statutory requirements)

# **Amendments to the Landscape Plan**

C26. To provide and appropriate landscaped setting, the landscape plan must be amended as follows:

- Soft landscaping to be provided within the south western corner of the site where the bin bay has been deleted as shown on the *Garage Plan (L5)*, drawn by *Contemporary Architecture*, drawing reference *DA16-B* and dated 2 *March 2020*. Suitable species are to be specified to allow filtered views to be retained through this view corridor.
- Lawn or additional landscaping is to be provided within the central courtyard "Courtyard 1" as shown on the Ground Floor Plan (L2) part 2, drawn by Contemporary Architecture, drawing reference DA13-B and dated 2 March 2020.
- 1 x Cupaniopsis anacardiodes (751) and 2 x Tristaniopsis laurina (451) shall be planted in the front setback (Cowdroy Ave), uppermost level garden or lawn areas (Lawn Level RL 18.40)
- 1 x *Tristaniopsis laurina* (451) shall be planted in the front setback (Cowdroy Ave), middle-upper level garden or lawn areas (Lawn Level RL 16.10)
- 2 x *Tristaniopsis laurina* (45l) shall be planted in the, middle level garden or lawn areas (Lawn Level RL 14.00)
- Species selection for 'Hardy Pocket Planting' (foreshore levels) shall include at least 50% native species
- A fully automatic irrigation system shall be installed to all garden areas

An amended landscape plan complying with this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the amended landscape plan and other plans and specifications submitted fully satisfy the requirements of this condition.

(Reason: To ensure residential amenity)

# D. Prior to the Commencement of any Works (and continuing where indicated)

## **Protection of Trees**

D1. All protected trees on-site that are specifically nominated to be retained by notation on plans or as per Condition C17 must be tagged with luminous tape or the like for purposes of identification prior to demolition, excavation or construction works and must remain so for the duration of works on the site. No materials or builder's waste are to be stored in the vicinity of the nominated tree/trees at any time.

Appropriate fencing or barricades in accordance with AS4970-2009 (Protection of trees on development sites), not less than the distance shown in the schedule hereunder, must be installed to the satisfaction of the Certifying Authority prior to demolition or commencement of any works and must be maintained for the duration of the works: -

(Reason: To protect the trees to be retained on the site during construction works)

# Public Liability Insurance - Works on Public Land

D2. Any person or contractor undertaking works on public land must take out Public Risk Insurance with a minimum cover of \$20 million in relation to the occupation of public land and the undertaking of approved works within Council's road reserve or public land, as approved by this consent. The Policy is to note, and provide protection/full indemnification for North Sydney Council, as an interested party. A copy of the Policy must be submitted to Council prior to commencement of any works. The Policy must be valid for the entire period that the works are being undertaken.

(Note: Applications for hoarding permits, vehicular crossings etc will require evidence of insurance upon lodgement of the application.)

(Reason: To ensure the community is protected from the cost of any claim for damages arising from works on public land)

# **Sydney Water Approvals**

D3. Prior to the commencement of any works, the approved plans must be submitted to Sydney Water to determine whether the development application will affect Sydney Water's sewer and water mains, stormwater drains and/or easements, and if further requirements need to be met. The Certifying Authority must ensure that Sydney Water has appropriately stamped the plans before the commencement of building works.

Notes:

■ Sydney Water Building Plan Approvals can be obtained from the Sydney Water Tap in<sup>TM</sup> online service. Building plans must be submitted to the Tap in<sup>TM</sup> to determine whether the development will affect any Sydney Water sewer or water main, stormwater drains and/or easement, and if further requirements need to be met. For further information visit <a href="http://www.sydneywater.com.au/tapin/index.htm">http://www.sydneywater.com.au/tapin/index.htm</a> or call 13 000 TAP IN (1300 082 746) for further information.

(Reason: To ensure compliance with Sydney Water requirements)

# Installation of Tree Protection prior to any commencement

D4. The tree protection measures detailed in the approved Tree Protection and Management Plan, as amended by further conditions shall be established prior to the commencement of any work on site.

(Reason: To ensure the stability and ongoing viability of trees to be retained are not

compromised before work

## E. During Demolition and Building Work

# **Parking Restrictions**

E1. Existing public parking provisions in the vicinity of the site must be maintained at all times during works. The placement of any barriers, traffic cones, obstructions or other device in the road shoulder or kerbside lane is prohibited without the prior written consent of Council. Changes to existing public parking facilities/restrictions must be approved by the North Sydney Local Traffic Committee. The Developer will be held responsible for any breaches of this condition, and will incur any fines associated with enforcement by Council regulatory officers.

(Reason: To ensure that existing kerbside parking provisions are not compromised during

works)

# **Road Reserve Safety**

E2. All public footways and roadways fronting and adjacent to the site must be maintained in a safe condition at all times during the course of the development works, with no obstructions caused to the said footways and roadways. Construction materials and plant must not be stored in the road reserve without approval of Council. A safe pedestrian circulation route and a pavement/route free of trip hazards must be maintained at all times on or adjacent to any public access ways fronting the construction site.

Where public infrastructure is damaged, repair works must be carried out in when and as directed by Council officers (at full Developer cost). Where pedestrian circulation is diverted on to the roadway or verge areas, clear directional signage and protective barricades must be installed in accordance with AS1742-3 (1996) "Traffic Control Devices for Work on Roads". If pedestrian circulation is not satisfactorily maintained across the site frontage, and action is not taken promptly to rectify the defects, Council may undertake proceedings to stop work.

(Reason: Public Safety)

# **Temporary Disposal of Stormwater Runoff**

E3. During construction, stormwater runoff must be disposed in a controlled manner that is compatible with the erosion and sediment controls on the site. Immediately upon completion of any impervious areas on the site (including roofs, driveways, paving) and where the final drainage system is incomplete, the necessary temporary drainage systems must be installed to reasonably manage and control runoff as far as the approved point of stormwater discharge. Such ongoing measures must be to the satisfaction of the Certifying Authority.

(Reason: Stormwater control during construction)

# **Geotechnical Stability during Works**

E4. A contractor with specialist excavation experience must undertake the excavations for the development and a suitably qualified and consulting geotechnical engineer must oversee the excavation procedure.

Geotechnical aspects of the development work, namely appropriate excavation method and vibration control, support and retention of excavated faces, and hydro geological considerations must be undertaken in accordance with the recommendations of the Geotechnical Engineer and all subsequent geotechnical inspections carried out during the excavation and construction phase.

Approval must be obtained from all affected property owners, including North Sydney Council where rock anchors (both temporary and permanent) are proposed below adjacent private or public property.

(Reason: Ensure appropriate professional are engaged at appropriate stages during construction)

# **Council Inspection of Public Infrastructure Works**

- E5. During the works on public infrastructure reverting to Council's care and control, Council's development engineer must undertake inspections of the works at the following hold points:
  - a) Vehicular access; and associated road civil works.

All works must proceed in accordance with Roads Act 1993 approvals or other permits relating to roads issued by Council. A minimum of 48 hours notice must be given to Council to book an inspection. Work must not proceed until the works or activity covered by the inspection is approved.

(Reason: To ensure quality of construction joints and connections in the drainage system)

# **Progress Survey**

- E6. In order to ensure compliance with approved plans, a Survey Certificate, to Australian Height Datum, must be prepared by a Registered Surveyor as follows:
  - a) at the completion of the first structural floor level indicating the level of that floor and the relationship of the building to the boundaries;
  - b) at the completed height of the building, prior to the placement of concrete inform work, or the laying of roofing materials; and
  - c) at completion, the relationship of the building, and any projections thereto, to the boundaries.

Progress certifications in response to points (a) through (c) must be provided to the Certifying Authority for approval at the time of carrying out relevant progress inspections. In the event that such survey information is not provided or reveals discrepancies between the approved plans and the proposed works, all works, save for works necessary to bring the development into compliance with the approved plans, must cease. Works may only continue upon notification by the Certifying Authority to the Applicant that survey information (included updated survey information following the carrying out of works to comply with the approved plans) complies with this condition.

(Reason: To ensure compliance with approved plans)

#### Removal of Extra Fabric

E7. Should any portion of the existing building, trees, or curtilage of the site which is indicated on the approved plans to be retained be damaged for whatever reason, all the works in the area of the damaged portion are to cease and written notification of the damage is to be given to Council forthwith. No work is to resume until the written approval of Council to do so is obtained. Failure to comply with the provisions of this condition may result in the Council taking further action including legal proceedings if necessary.

(Reason: To ensure compliance with the terms of this development consent)

## **Dust Emission and Air Quality**

- E8. The following must be complied with at all times:
  - (a) Materials must not be burnt on the site.
  - (b) Vehicles entering and leaving the site with soil or fill material must be covered.
  - (c) Dust suppression measures must be carried out to minimise wind-borne emissions in accordance with the NSW Department of Housing's 1998 guidelines Managing Urban Stormwater: Soils and Construction.
  - (d) Odour suppression measures must also be carried out where appropriate so as to prevent nuisance occurring at adjoining properties.

(Reason: To ensure residential amenity is maintained in the immediate vicinity)

# **Noise and Vibration**

E9. The works must be undertaken in accordance with the "Interim Construction Noise Guideline" published by the NSW Environment Protection Authority, to ensure excessive levels of noise and vibration do not occur so as to minimise adverse effects experienced on any adjoining land.

(Reason: To ensure residential amenity is maintained in the immediate vicinity)

# No Work on Public Open Space

E10. No work can be undertaken within adjoining public lands (ie. Parks, Reserves, Roads etc) without the prior written consent of Council. In this regard the developer is to liaise with Council prior to the commencement of any design works or preparation of a Construction and Traffic Management Plan.

(Reason: Protection of existing public infrastructure and land and to ensure public safety

and proper management of public land)

# **Developer's Cost of Work on Council Property**

E11. The developer must bear the cost of all works associated with the development that occurs on Council's property, including the restoration of damaged areas.

(Reason: To ensure the proper management of public land and funds)

# No Removal of Trees on Public Property

E12. No trees on public property (footpaths, roads, reserves, etc.) unless specifically approved by this consent shall be removed or damaged during construction including for the erection of any fences, hoardings or other temporary works.

(Reason: Protection of existing environmental infrastructure and community assets)

# **Protection of Trees**

E13. All trees required to be retained, as part of this consent must be protected from any damage during construction works in accordance with AS4970-2009. All recommendations contained within the tree report prepared by *Hugh The Arborist*, dated 02/07/2019 and received by Council on 20/09/2019 must be implemented for the duration of the works.

In the event that any tree required to be retained is damaged during works on the site, notice of the damage must be given to Council forthwith.

## Notes:

- a. If the nominated tree is damaged to a significant degree or removed from the site without prior written approval being obtained from Council, the issuing of fines or legal proceedings may be commenced for failure to comply with the conditions of this consent.
- b. An application to modify this consent pursuant to Section 96 of the Environmental Planning and Assessment Act 1979 will be required to address the non-compliance with any of the conditions of consent relating to the retention of nominated trees, and Council may require tree replenishment.

(Reason: Protection of existing environmental infrastructure and community assets)

#### Trees to be Removed

E14. All trees on the site must be protected and retained save for those expressly identified below as being approved for removal:-

Trees that are acceptable to remove	Location	Height
Tree 1 <i>Yucca</i> spp.	Front setback (Cowdroy Ave)	6m
Tree 2 Nerium oleander	Front setback (Cowdroy Ave)	6m
Tree 3 Howea forsteriana	Front setback (Cowdroy Ave)	6m
Tree 4 Syagrus romanzoffianum	Front setback (Cowdroy Ave)	12m
Tree 5 Eriobotyra japonica	Front setback (Cowdroy Ave)	7m
Tree 6 Michelia figo	Front setback (Cowdroy Ave)	5m
Tree 13 Cyathea cooperi	Front setback (Cowdroy Ave)	5m
Tree 16 Howea forsteriana	Eastern boundary (middle level)	11m
Trees17-19 Cupressus sempervirens	Rear of existing garage	8m

(Reason: To ensure compliance with the terms of this development consent)

## **Special Permits**

E15. Unless otherwise specifically approved in writing by Council, all works, processes, storage of materials, loading and unloading associated with the development must occur entirely on the property.

The developer, owner or builder may apply for specific permits available from Council's Customer Service Centre for the undermentioned activities on Council's property. In the event that a permit is granted by Council for the carrying out of works, processes, storage of materials, loading and unloading associated with the development on Council's property, the development must be carried out in accordance with the requirements of the permit. A minimum of forty-eight (48) hours notice is required for any permit: -

# 1) On-street mobile plant

Eg. cranes, concrete pumps, cherry-pickers, etc. - restrictions apply to the hours of operation, the area of operation, etc. Separate permits are required for each occasion and each piece of equipment. It is the developer's, owner's and builder's responsibilities to take whatever steps are necessary to ensure that the use of any equipment does not violate adjoining property owner's rights.

(Reason: Proper management of public land)

# 2) Hoardings

Permits are required to erect Class A and Class B hoardings. If an 'A' Class hoarding is to alienate a section of Council's property, that section will require a permit for the occupation of Council's property.

(Reason: Proper management of public land)

# 3) Storage of building materials and building waste containers (skips) on Council's property

Permits to utilise Council property for the storage of building materials and building waste containers (skips) are required for each location. Failure to obtain the relevant permits will result in the building materials or building waste containers (skips) being impounded by Council with no additional notice being given. Storage of building materials and waste containers on open space reserves and parks is prohibited.

(Reason: Proper management of public land)

## 4) Kerbside restrictions, construction zones

Attention is drawn to the existing kerbside restrictions adjacent to the development. Should alteration of existing kerbside restrictions be required, or the provision of a construction zone, the appropriate application must be made and the fee paid to Council. Alternatives to such restrictions may require referral to Council's Traffic Committee and may take considerable time to be resolved. An earlier application is suggested to avoid delays in construction programs.

(Reason: Proper management of public land)

#### **Construction Hours**

E16. Building construction and works must be restricted to within the hours of 7.00 am to 5.00 pm Monday to Friday and on Saturday to within the hours of 8.00 am to 1.00 pm inclusive, with no work on Sundays and Public Holidays.

Demolition and excavation works must be restricted to within the hours of 8.00 am to 5.00 pm Monday to Friday only. For the purposes of this condition:

- a) "Building construction" means any physical activity on the site involved in the erection of a structure, cladding, external finish, formwork, fixture, fitting of service installation and the unloading of plant, machinery, materials or the like.
- b) "Demolition works" means any physical activity to tear down or break up a structure (or part thereof) or surface, or the like, and includes the loading of demolition waste and the unloading of plant or machinery.
- c) "Excavation work" means the use of any excavation machinery and the use of jackhammers, rock breakers, excavators, loaders, or the like, regardless of whether the activities disturb or alter the natural state of the existing ground stratum or are breaking up/removing materials from the site and includes the unloading of plant or machinery associated with excavation work.

All builders, excavators must display, on-site, their twenty-four (24) hour contact telephone number, which is to be clearly visible and legible from any public place adjoining the site.

(Reason: To ensure that works do not interfere with reasonable amenity expectations of residents and the community)

## **Installation and Maintenance of Sediment Control**

E17. Erosion and sediment controls must be installed and maintained at all times in accordance with the Sediment and erosion control plan submitted and approved with the Construction Certificate.

Erosion and sediment measures must be maintained in accordance with the publication Managing Urban Stormwater: Soils & Construction (4th edition, Landcom, 2004), commonly referred to as the "Blue Book" and can only be removed when development activities have been completed and the site fully stabilised.

(Reason: To protect the environment from the effects of sedimentation and erosion from development sites)

# **Sediment and Erosion Control Signage**

E18. A durable sign must be erected during building works in a prominent location on site, warning of penalties should appropriate erosion and sedimentation control devices not be maintained. A sign of the type referred to in this condition is available from Council.

(Reason: To protect the environment from the effects of sedimentation and erosion from development sites)

#### **Site Amenities and Facilities**

E19. Where work involved in the erection and demolition of a building is being carried out, amenities which satisfy applicable occupational health and safety and construction safety regulations, including any WorkCover Authority requirements, must be provided and maintained at all times. The type of work place determines the type of amenities required.

Further information and details can be obtained from the Internet at <a href="https://www.workcover.nsw.gov.au">www.workcover.nsw.gov.au</a>

(Reason: To ensure the health and safety of the community and workers on the site)

# **Health and Safety**

E20. All work undertaken must satisfy applicable occupational health and safety and construction safety regulations, including any WorkCover Authority requirements to prepare a health and safety plan. Site fencing must be installed sufficient to exclude the public from the site. Safety signs must be erected that warn the public to keep out of the site, and provide a contact telephone number for enquiries.

Further information and details regarding occupational health and safety requirements for construction sites can be obtained from the internet at www.workcover.nsw.gov.au

(Reason: To ensure the health and safety of the community and workers on the site)

### **Prohibition on Use of Pavements**

E21. Building materials must not be placed on Council's footpaths, roadways, parks or grass verges, (unless a permit is obtained from Council beforehand). A suitable sign to this effect must be erected adjacent to the street alignment.

(Reason: To ensure public safety and amenity on public land)

## Plant & Equipment Kept Within Site

E22. All plant and equipment used in the undertaking of the development/ works, including concrete pumps, wagons, lifts, mobile cranes, hoardings etc, must be situated within the boundaries of the site (unless a permit is obtained from Council beforehand) and so placed that all concrete slurry, water, debris and the like must be discharged onto the building site, and is to be contained within the site boundaries.

Details of Council requirements for permits on public land for standing plant, hoardings, storage of materials and construction zones and the like are available on Council's website at <a href="https://www.northsydney.nsw.gov.au">www.northsydney.nsw.gov.au</a>.

(Reason: To ensure public safety and amenity on public land)

# **Waste Disposal**

E23. All records demonstrating the lawful disposal of waste must be retained and kept readily accessible for inspection by regulatory authorities such as North Sydney Council and the Environmental Protection Authority.

(Reason: To ensure the lawful disposal of construction and demolition waste)

#### **Asbestos Removal**

E24. All demolition works involving the removal and disposal of asbestos cement must only be undertaken by contractors who hold a current WorkCover Asbestos or "Demolition Licence" and a current WorkCover "Class 2 (Restricted) Asbestos Licence and removal must be carried out in accordance with National Occupational Health and Safety Commission.

(Reason: To ensure works are carried out in accordance with relevant WorkCover requirements)

## **Service Adjustments**

E25. Where required, the adjustment or inclusion of any new utility service facilities must be carried out by the person acting on the consent and in accordance with the requirements of the relevant utility authority. These works shall be at no cost to Council. It is the Applicants full responsibility to make contact with the relevant utility authorities to ascertain the impacts of the proposal upon utility services at the appropriate stage of the development (including water, phone, gas and the like). Council accepts no responsibility whatsoever for any matter arising from its approval of this application involving any influence upon utility services provided by another authority.

(Reason: To ensure the service requirements are met)

# F. Prescribed Conditions imposed under EP&A Act and Regulations and other relevant Legislation

## **National Construction Code**

F1. All building work must be carried out in accordance with the provisions of the National Construction Code.

(Reason: Prescribed - Statutory)

# **Home Building Act**

- F2. 1) Building work that involves residential building work (within the meaning and exemptions provided in the Home Building Act 1989) for which the *Home Building Act* 1989 requires there to be a contract of insurance under Part 6 of that Act must not be carried out unless the Principal Certifying Authority for the development to which the work relates has given North Sydney Council written notice of the contract of insurance being issued and of the following:
  - a) in the case of work for which a principal contractor is required to be appointed:
    - i) the name and licence number of the principal contractor, and
    - ii) the name of the insurer by which the work is insured under Part 6 of that Act, or
  - (b) in the case of work to be done by an owner-builder:
    - (i) the name of the owner-builder, and
    - (ii) if the owner-builder is required to hold an owner-builder permit under that Act, the number of the owner-builder permit.
  - If arrangements for doing residential building work are changed while the work is in progress such that the information submitted to Council in accordance with this conditions is out of date, work must cease and no further work may be carried out unless the Principal Certifying Authority for the development to which the work relates (not being the Council), has given the Council written notice of the updated information.

Note: A certificate purporting to be issued by an approved insurer under Part 6 of the Home Building Act 1989 that states that a person is the holder of an insurance policy issued for the purposes of that Part is, for the purposes of this clause, sufficient evidence that the person has complied with the requirements of that Part.

(Reason: Prescribed - Statutory)

# Appointment of a Principal Certifying Authority (PCA)

F3. Building work, demolition or excavation in accordance with the development consent must not be commenced until the developer has appointed a Principal Certifying Authority for the building work in accordance with the provisions of the EP&A Act and its Regulations.

(Reason: Statutory; To ensure appropriate safeguarding measures are in place prior to the

commencement of any building work, demolition or excavation)

## **Construction Certificate**

F4. Building work, demolition or excavation in accordance with the development consent must not be commenced until a Construction Certificate for the relevant part of the building work has been issued in accordance with the provisions of the EP&A Act and its Regulations.

(Reason: Statutory; To ensure appropriate safeguarding measures are in place prior to the

commencement of any building work, demolition or excavation)

# **Occupation Certificate**

F5. A person must not commence occupation or use of the whole or any part of a new building (new building includes an altered portion of, or an extension to, an existing building) unless an Occupation Certificate has been issued in relation to the building or part. Only the Principal Certifying Authority appointed for the building work can issue an Occupation Certificate.

(Reason: Statutory)

# **Critical Stage Inspections**

F6. Building work must be inspected by the Principal Certifying Authority on the critical stage occasions prescribed by the EP&A Act and its Regulations, and as directed by the appointed Principal Certifying Authority.

(Reason: Statutory)

## **Commencement of Works**

F7. Building work, demolition or excavation in accordance with this development consent must not be commenced until the developer has given at least 2 days notice to North Sydney Council of the person's intention to commence the erection of the building.

(Reason: Statutory; To ensure appropriate safeguarding measures are in place prior to the

commencement of any building work, demolition or excavation)

## **Excavation/Demolition**

- F8. 1) All excavations and backfilling associated with the erection or demolition of a building must be executed safely and in accordance with appropriate professional standards.
  - 2) All excavations associated with the erection or demolition of a building must be properly guarded and protected to prevent them from being dangerous to life or property.
  - 3) Demolition work must be undertaken in accordance with the provisions of AS2601-Demolition of Structures.

(Reason: To ensure that work is undertaken in a professional and responsible manner and protect adjoining property and persons from potential damage)

## **Protection of Public Places**

- F9. 1) A hoarding and site fencing must be erected between the work site and adjoining public place.
  - 2) If necessary, an awning is to be erected, sufficient to prevent any substance from, or in connection with, the work falling into the public place.
  - 3) The work site must be kept lit between sunset and sunrise if it is likely to be hazardous to persons in the public place.
  - 4) Any such hoarding, fence or awning is to be removed when the work has been completed.
  - 5) No access across public reserves or parks is permitted.

Note: Prior to the erection of any temporary fence or hoarding over property owned or managed by Council, written approval must be obtained. Any application needs to be accompanied by plans indicating the type of hoarding and its layout. Fees are assessed and will form part of any approval given. These fees must be paid prior to the approval being given. Approval for hoardings will generally only be given in association with approved building works, maintenance or to ensure protection of the public. An application form for a Hoarding Permit can be downloaded from Council's website.

(Reason: To ensure public safety and the proper management of public land)

# Site Sign

- F10. 1) A sign must be erected in a prominent position on the site
  - a) stating that unauthorised entry to the work site is prohibited;
  - b) showing the name of the principal contractor (or person in charge of the work site), and a telephone number at which that person may be contacted at any time for business purposes and outside working hours; and

- c) showing the name, address and telephone number of the Principal Certifying Authority for the work.
- 2) Any such sign must be maintained while to building work or demolition work is being carried out, but must be removed when the work has been completed.

(Reason: Prescribed - Statutory)

# G. Prior to the Issue of an Occupation Certificate

# **Infrastructure Repair and Completion of Works**

- G1. Prior to the issue of any Occupation Certificate any and all works relating to the development:
  - a. in the road reserve must be fully completed; and
  - b. to repair and make good any damaged public infrastructure caused as a result of any works relating to the development (including damage caused by, but not limited to, delivery vehicles, waste collection, contractors, sub-contractors, concrete vehicles) must be fully repaired;

to the satisfaction of Council Engineers at no cost to Council.

(Reason: Maintain quality of Public assets)

## **Noise from Plant**

G2. Prior to issue of the any Occupation Certificate a certificate from an appropriately qualified acoustical consultant eligible for membership of the Association of Australian Acoustic Consultants is to be submitted to, and approved by, the Certifying Authority certifying that the noise and vibration from use of the development complies with the conditions of consent herein.

(Reason: To ensure acoustic amenity)

## **Certification- Civil Works**

- G3. a) An appropriately qualified and practising Civil Engineer must certify to the Certifying Authority that the stormwater drainage system is constructed in accordance with this consent and the provisions of the applicable Australian Standard. A copy of the certificate must be submitted to Council (if it is not the Certifying Authority) upon completion of the development works and prior to the issue of an Occupation Certificate.
  - An appropriately qualified and practicing Civil Engineer must certify to the Certifying Authority that the vehicular crossing and associated works and road works were constructed in accordance with this consent and any approval for works in the road reserve issued by the Council. A copy of the certificate must be submitted to Council (if it is not the Certifying Authority), upon completion of the development works and prior to the issue of an Occupation Certificate.

(Reason: Compliance with the Consent)

#### **Pool Access**

G4. Access to the pool must be restricted by a child resistant barrier in accordance with the regulations prescribed in the Swimming Pools Act 1992, and the requirements of the applicable Australian Standard. The pool must not be filled with water or be allowed to collect stormwater until the installation of the child resistant barrier is completed. Certification from an appropriately qualified person confirming compliance with these requirements must be provided prior to the issuing of any Occupation Certificate.

(Reason: To ensure that any person acting upon this consent is aware of their obligations under the provisions of the Swimming Pools Act)

# **Pool Safety Requirements**

- G5. A notice must be displayed in a prominent position in the immediate vicinity of the pool at all times showing:
  - a) Appropriate instructions of artificial resuscitation methods.
  - b) A warning stating:
    - (i) "YOUNG CHILDREN SHOULD BE SUPERVISED WHEN USING THIS SWIMMING POOL", and
    - (ii) "POOL GATES MUST BE KEPT CLOSED AT ALL TIMES", and
    - (iii) "KEEP ARTICLES, OBJECTS AND STRUCTURES AT LEAST 900 MILLIMETRES CLEAR OF THE POOL FENCE AT ALL TIMES",

Details demonstrating compliance are to be provided with any Occupation Certificate issued for the pool.

This notice must be kept in a legible condition and at the poolside.

(Reason: To ensure an adequate level of safety for young pool users)

# **Damage to Adjoining Properties**

G6. All precautions must be taken to prevent any damage likely to be sustained to adjoining properties. Adjoining owner property rights and the need for owner's permission must be observed at all times, including the entering onto land for the purpose of undertaking works.

(Reason: To ensure adjoining owner's property rights are protected)

## **Utility Services**

G7. All utility services shall be adjusted, to the correct levels and/or location/s required by this consent, prior to issue of an occupation certificate. This shall be at no cost to Council.

(Reason: To ensure compliance with the terms of this consent)

#### **Certification of Tree Condition**

G8. Prior to the issue of an Occupation Certificate, a report prepared by an appropriately qualified person (being an arborist or the like) must be submitted to the Certifying Authority, describing the health of the tree(s) specifically nominated below: -

Tree	Location	Height/Size
Tree 7 Archontophoenix cunninghamiana	Front setback (Cowdroy Ave)	10m
Tree 8-10 Cupressus torulosa	Front setback (Cowdroy Ave)	16m
Tree 11 Washingtonia robusta	Front setback (Cowdroy Ave)	10m
Tree 12 Dypsis lutescens	Front setback (Cowdroy Ave)	6m
Tree 14 Dracena draco	Eastern boundary (middle level)	5m
Tree 15 Archontophoenix cunninghamiana	Eastern boundary (middle level)	12m
Tree 20 Syagrus romanzoffianum	Western boundary – pool level	11m
G1 Mixed species	Gardens below pool level	5m
1 x Cupaniopsis anacardiodes	Upper level replacement plantings	751
5 x Tristaniopsis laurina	Upper level replacement plantings	451

The report must detail the condition and health of the nominated tree(s) upon completion of the works, and shall certify that the tree(s) has/have not been significantly damaged during the works on the site, and has/have reasonable prospects for survival.

(Reason: To ensure compliance with the terms of this consent)

# **Disposal Information**

- G9. Upon completion of works and prior to occupation, a report including the following information must be provided to Council's Open Space and Environmental Services Department:
  - a) the total tonnage of all waste and excavated material disposed of from the site (including any tipping dockets); and
  - b) the disposal points and methods used.

(Reason: To ensure appropriate disposal methods are undertaken for auditing and inspection purposes)

## Landscaping

G10. The landscaping shown in the approved landscape plan *Landscape Plan*, drawn by *Hortus Design*, drawing reference *L01 of 1*, issues A and dated *17 September 2020*, as amended by Condition C26 must be completed prior to the issue of any Occupation Certificate.

(Reason: To ensure compliance)

# I. On-Going / Operational Conditions

## **Pool Filter**

- I1. The swimming pool pump installed at the premises must not operate so as to:
  - (a) emit a noise that is audible within a habitable room in any affected residence (regardless of whether any door or window to that room is open);
    - (j) before 8.00am and after 8.00pm on any Sunday or Public Holiday; or
    - (ii) before 7.00am or after 8.00pm on any other day
  - (b) cause an LAeq(15min) which exceeds the RBL background noise level by more than 5dB when measured at the boundary of any affected residence. The modifying factor adjustments in Section 4 of the EPA Industrial Noise Policy shall be applied.

"affected residence" includes residential premises (including any lot in the strata scheme or another strata scheme), premises for short-term accommodation and hospitals.

"boundary" includes any window or elevated window of an affected residence.

Terms in this condition have the same meaning as in the Noise Guide for Local Government and the Industrial Noise Policy published by the NSW Environment Protection Authority.

(Reason: To ensure noise generated by equipment does not result in offensive noise)

## **Single Occupancy**

I2. Nothing in this consent authorises the use of the premises other than for a single occupancy.

(Reason: To ensure compliance with the terms of this consent)

# **Maintenance of Approved Landscaping**

I3. The landscaping as approved by this consent, generally in accordance with the landscape plan *Landscape Plan*, drawn by *Hortus Design*, drawing reference L01 of 1, issues A and dated *17 September 2020*, as amended by Condition C27 must be reasonably maintained.

Any replacement plants required shall be advanced in growth and be selected to maintain the anticipated mature height, canopy density and nature of those plant species as originally approved.

(Reason: to maintain the amenity of the area)