Original signed by Robyn Pearson on 01/03/2022

Date determined: 22/02/2022 Date operates: 01/03/2022 Date lapses: 01/03/2027

Linda Jays 1 Nott Lane LONGUEVILLE NSW 2066

> D314/21 AB7 (CIS)

ENVIRONMENTAL PLANNING AND ASSESSMENT ACT, 1979 AS AMENDED NOTICE OF DETERMINATION - Approval

Development Application Number:	314/21
Land to which this applies:	27 Edward Street, North Sydney Lot No.: 7, DP: 210322
Applicant:	Linda Jays
Proposal:	Alterations and additions to an existing dwelling, including an attic and associated works.
Determination of Development Application:	Subject to the provisions of Section 4.17 of the <i>Environmental Planning and Assessment Act 1979</i> , approval has been granted subject to conditions in the notice of determination.
Date of Determination:	22 February 2022
Reasons for Approval	The proposed works have been assessed under the relevant planning instruments including NSLEP 2013 and NSDCP 2013 and was found to be satisfactory. Notwithstanding the existing non-compliances with side setbacks and the landscaped area controls, the proposal maintains an acceptable level of compliance with the provisions and the objectives of Part B Section of NSDCP 2013 and does not significantly increase these existing non-compliances. The proposal is also broadly consistent with the objectives of the R2 Low Density Zone and the Edward Street Conservation Area, as it retains the primary built form visible from Edward Street and the works are confined to less visible areas at the rear of the site.

	The new additions will also not result in any significant environmental impacts in terms of views, solar access, or privacy for adjoining properties. Conditions have been recommended to further enhance the overall landscaping on the site, alongside ensuring that the front fence is sympathetic to the conservation area.
Consent to operate from:	1 March 2022
Consent will lapse on:	1 March 2027
Period of Consent	Subject to Section 4.20 of the Act, this consent becomes effective and operates from the date listed above. The consent lapses five years after the date of consent in accordance with Section 4.53 of the Act and cannot be extended. To activate this consent, works must physically commence onsite 1 March 2027.
How community views were taken into account:	The subject application was notified to adjoining properties and the Edward Precinct Committee seeking comment, and four submissions were received of which two raised objections. Nevertheless, the proposal would provide improved amenity for the residents without causing any unreasonable impacts to the streetscape and/or adjoining properties, subject to appropriate conditions of consent.
Review of determination and right of appeal:	Within six months after the date of notification of the decision, a review of this determination can be requested under Division 8.2 of the Act or an appeal to the Land and Environment Court made pursuant to the provisions of Section 8.7 of the Act. A review of determination should be lodged as soon as possible, and preferably no later two months after the date of notification of the decision to enable the review to be completed within the six-month period.
Plans endorsed by the consent authority - ple	ase refer to condition A1.

Endorsed for and on behalf of North Sydney Council

DATE Signature on behalf of consent authority

ROBYN PEARSON

TEAM LEADER ASSESSMENTS

(i) Conditions

Consent is granted subject to the following conditions imposed pursuant to Section 4.17 of the Environmental Planning and Assessment Act 1979 ("the Act") and the provisions of the Environmental Planning and Assessment Regulation 2000 ("the Regulation") such conditions being reasonable and relevant to the development as assessed pursuant to Section 4.17 of the Act.

(ii) Definitions

Unless specified otherwise, words have the same meaning as defined by the *Act*, the *Regulation* and the *Interpretation Act* 1987 as in force at the date of consent.

Applicant means the applicant for this consent.

Approved Plans means the plans endorsed by Council referenced by this consent as amended by conditions of this consent.

AS or **AS/NZS** means Australian Standard® or Australian/New Zealand Standard®, respectively, published by Standards Australia International Limited.

NCC means the National Construction Code as published by the Australian Building Codes Board as in force at the date of issue of any *Construction Certificate*.

Council means North Sydney Council.

Court means the Land and Environment Court.

Local Native Plants means species of native plant endemic to North Sydney LGA.

Stormwater Drainage System means all works, facilities and documentation relating to:

- The collection of stormwater,
- The retention of stormwater,
- The reuse of stormwater,
- The detention of stormwater,
- The controlled release of stormwater; and
- Connections to easements and public stormwater systems.

Owner means the owner of the *site* and successors in title to the *site*.

Owner Builder has the same meaning as in the Home Building Act 1989.

Principal Certifier for building or subdivision work means the certifier appointed as the principal certifier for the building work under section 6.6 (1) or for the subdivision work under section 6.12 (1).

Principal Contractor for building work means the person responsible for the overall coordination and control of the carrying out of the building work.

Note: If any residential building work is involved, the principal contractor must be the holder of a contractor licence under the *Home Building Act 1989*.

Professional Engineer has the same meaning as in the NCC.

Public Place has the same meaning as in the Local Government Act 1993.

Road has the same meaning as in the Roads Act 1993.

SEE means the final version of the Statement of Environmental Effects lodged by the *Applicant*.

Site means the land being developed subject to this consent.

NSLEP 2013 means North Sydney Local Environmental Plan 2013

NSDCP 2013 means North Sydney Development Control Plan 2013

Work for the purposes of this consent means:

- the use of land in connection with development,
- the subdivision of land,
- the erection of a building,
- the carrying out of any work,
- the use of any site crane, machine, article, material, or thing,
- the storage of any waste, materials, site crane, machine, article, material, or thing,
- the demolition of a building,
- the piling, piercing, cutting, boring, drilling, rock breaking, rock sawing or excavation of land,
- the delivery to or removal from the site of any machine, article, material, or thing, or
- the occupation of the site by any person unless authorised by an occupation certificate.

Note: **Interpretation of Conditions** - Where there is any need to obtain an interpretation of the intent of any condition this must be done in writing to Council and confirmed in writing by Council.

INDEX OF CONDITIONS

A. Conditions that Identify Approved Plans A1. Development in Accordance with Plans/Documentation A2. Plans on Site 77 A3. No Demolition of Extra Fabric A4. External Finishes and Materials C. Prior to the Issue of a Construction Certificate (and ongoing, where indicated) C1. Dilapidation Report Damage to Public Infrastructure C2. Dilapidation Survey Private Property (Neighbouring Buildings) 88 C3. Structural Adequacy (Semi Detached and Terrace Buildings) 99 C4. Structural Adequacy of Existing Building C5. Sediment Control 99 C6. Waste Management Plan 99 C7. Colours, Finishes and Materials (Conservation Areas) 100 C8. Skylight(s) 111 C9. Heritage Requirements 112 C10. Work Zone 112 C11. Parking Meter Relocation 112 C12. Obtain Driveway Crossing Permit under S.138 Roads Act 1993 12 C13. Stormwater Disposal 14 C14. Bond for Damage and Completion of Infrastructure Works - Stormwater, Kerb And Gutter, Footpaths, Vehicular Crossing and Road Pavement 14 C15. Tree Protection Measures to be shown on Construction Drawings 15 C17. Garbage and Recycling Facilities 15 C18. Asbestos and Hazardous Material Survey 16 C19. Section 7.12 Contributions 16 C20. Security Deposit/Guarantee Schedule 17 C21. BASIX Commitments 17 C22. Landscape Amendments 17 C23. Southern Boundary Fence 18 C24. Works to be Contained within Lot 18 C72. Prior to the Commencement of any Works (and continuing where indicated) C73. Road Reserve Safety 19 C74. Prior to the Commencement of Any Works (and continuing where indicated) C75. Prior to the Commencement of Source Analogue Commencement of Source Control			Page No.
A2. Plans on Site A3. No Demolition of Extra Fabric A4. External Finishes and Materials C. Prior to the Issue of a Construction Certificate (and ongoing, where indicated) C1. Dilapidation Report Damage to Public Infrastructure Dilapidation Survey Private Property (Neighbouring Buildings) A3. Structural Adequacy (Semi Detached and Terrace Buildings) A4. Structural Adequacy of Existing Building A5. Structural Adequacy of Existing Building A5. Structural Adequacy of Existing Building A6. Waste Management Plan A7. Colours, Finishes and Materials (Conservation Areas) A8. Skylight(s) A8. Skylight(sylight(s) A8. Skylight(sylight(sylight(sylight(syli	A.	Conditions that Identify Approved Plans	_
A2. Plans on Site A3. No Demolition of Extra Fabric A4. External Finishes and Materials C. Prior to the Issue of a Construction Certificate (and ongoing, where indicated) C1. Dilapidation Report Damage to Public Infrastructure Dilapidation Survey Private Property (Neighbouring Buildings) A3. Structural Adequacy (Semi Detached and Terrace Buildings) A4. Structural Adequacy of Existing Building A5. Structural Adequacy of Existing Building A5. Structural Adequacy of Existing Building A6. Waste Management Plan A7. Colours, Finishes and Materials (Conservation Areas) A8. Skylight(s) A8. Skylight(sylight(s) A8. Skylight(sylight(sylight(sylight(syli	۸1	Dayalanment in Assardance with Blans/Decumentation	7
A3. No Demolition of Extra Fabric A4. External Finishes and Materials C. Prior to the Issue of a Construction Certificate (and ongoing, where indicated) C1. Dilapidation Report Damage to Public Infrastructure 8 Dilapidation Survey Private Property (Neighbouring Buildings) 8 Structural Adequacy (Semi Detached and Terrace Buildings) 8 Structural Adequacy (Semi Detached and Terrace Buildings) 9 Sediment Control 9 Octours, Finishes and Materials (Conservation Areas) 10 C7. Colours, Finishes and Materials (Conservation Areas) 10 Skylight(s) 11 Heritage Requirements 11 Ovork Zone 11 Parking Meter Relocation 12 Obtain Driveway Crossing Permit under S.138 Roads Act 1993 12 C13. Stornwater Disposal 14 Bond for Damage and Completion of Infrastructure Works - Stornwater, Kerb And Gutter, Footpaths, Vehicular Crossing and Road Pavement 14 Tree Protection Measures to be shown on Construction Drawings 15 Protection of Trees 17 Garbage and Recycling Facilities 18 Asbestos and Hazardous Material Survey 19 Section 7.12 Contributions 10 Section 7.12 Contributions 10 Section 7.12 Contributions 11 Asbestos and Hazardous Material Survey 12 BASIX Commitments 17 C22. Landscape Amendments 18 ASIX Commitments 19 Protection of Trees 18 ASIX Commitments 19 Protection of Trees 19 ASIX Commitments 10 Prior to the Commencement of any Works (and continuing where indicated) 11 Protection of Trees 12 Public Liability Insurance - Works on Public Land 13 Commencement of Works' Notice 19 Protection and Building Work 19 Prace Requirement of Stornwater Runoff 10 Section 7.12 Cigarette Butt Receptacle 11 Parking Restrictions 12 Parking Restrictions 13 Road Reserve Safety 14 Temporary Disposal of Stornwater Runoff 15 Removal of Extra Fabric 20 Parking Restrictions 20 Permoval of Extra Fabric 21 Parking Restrictions 22 Parking Restrictions			
A4. External Finishes and Materials C. Prior to the Issue of a Construction Certificate (and ongoing, where indicated) C1. Dilapidation Report Damage to Public Infrastructure C2. Dilapidation Survey Private Property (Neighbouring Buildings) Structural Adequacy (Semi Detached and Terrace Buildings) Structural Adequacy (Semi Detached and Terrace Buildings) Structural Adequacy (Semi Detached and Terrace Buildings) Sylight (S) Sediment Control G2. Waste Management Plan G3. Skylight(s) G4. Structural Adequacy of Existing Building G5. Waste Management Plan G6. Waste Management Plan G7. Colours, Finishes and Materials (Conservation Areas) G8. Skylight(s) G9. Heritage Requirements G9. Heritage Requirements G9. Parking Meter Relocation G10. Work Zone G11. Parking Meter Relocation G11. Parking Meter Relocation G12. Obtain Driveway Crossing Permit under S.138 Roads Act 1993 G13. Stormwater Disposal G14. Bond for Damage and Completion of Infrastructure Works - Stormwater, Kerb And Gutter, Footpaths, Vehicular Crossing and Road Pavement G15. Tree Protection Measures to be shown on Construction Drawings G16. Protection of Trees G17. Garbage and Recycling Facilities G18. Asbestos and Hazardous Material Survey G19. Section 7.12 Contributions G10. Security Deposit/Guarantee Schedule G21. BASIX Commitments G22. Landscape Amendments G23. Southern Boundary Fence G24. Works to be Contained within Lot D. Prior to the Commencement of any Works (and continuing where indicated) D1. Protection of Trees Pullic Liability Insurance - Works on Public Land G33. Commencement of Works' Notice E5. During Demolition and Building Work E1. Cigarette Butt Receptacle E2. Parking Restrictions G20. Second of Extra Fabric G21. Second of Extra Fabric G2			
C. Prior to the Issue of a Construction Certificate (and ongoing, where indicated) C1. Dilapidation Report Damage to Public Infrastructure C2. Dilapidation Survey Private Property (Neighbouring Buildings) Structural Adequacy (Semi Detached and Terrace Buildings) 9. C4. Structural Adequacy (Semi Detached and Terrace Buildings) 9. C5. Sediment Control 9. C6. Waste Management Plan 10. C7. Colours, Finishes and Materials (Conservation Areas) 10. C8. Skylight(s) 11. C9. Heritage Requirements 11. C10. Work Zone 11. C11. Parking Meter Relocation 11. C11. Parking Meter Relocation 11. C12. Obtain Driveway Crossing Permit under S.138 Roads Act 1993 12. C13. Stormwater Disposal 14. Bond for Damage and Completion of Infrastructure Works - Stormwater, Kerb And Gutter, Footpaths, Vehicular Crossing and Road Pavement 14. C15. Tree Protection Measures to be shown on Construction Drawings 15. C16. Protection of Trees 15. C17. Garbage and Recycling Facilities 15. C18. Asbestos and Hazardous Material Survey 16. C19. Section 7.12 Contributions 16. C19. Section 7.12 Contributions 16. C20. Security Deposit/Guarantee Schedule 17. C21. BASIX Commitments 17. C22. Landscape Amendments 17. C23. Southern Boundary Fence 18. C24. Works to be Contained within Lot D. Prior to the Commencement of any Works (and continuing where indicated) D1. Protection of Trees D2. Public Liability Insurance - Works on Public Land D3. Commencement of Works' Notice 19. E. During Demolition and Building Work E1. Cigarette Butt Receptacle E2. Parking Restrictions 19. Road Reserve Safety 19. E4. Temporary Disposal of Stormwater Runoff E5. Removal of Extra Fabric 20. E5. Removal of Extra Fabric 20. C5. Removal of Extra Fabric 20. C6. Removal of Extra Fabric 20. C6. Removal of Extra Fabric 20. C6. Removal of Extra Fabric 20. C7. Removal of Extra Fabric 20. C7. Removal of Extra Fabric			
C1. Dilapidation Report Damage to Public Infrastructure C2. Dilapidation Survey Private Property (Neighbouring Buildings) C3. Structural Adequacy (Semi Detached and Terrace Buildings) C4. Structural Adequacy of Existing Building C5. Sediment Control C6. Waste Management Plan C7. Colours, Finishes and Materials (Conservation Areas) C8. Skylight(s) C9. Heritage Requirements C10. Work Zone C11. Parking Meter Relocation C12. Obtain Driveway Crossing Permit under S.138 Roads Act 1993 C13. Stormwater Disposal C14. Bond for Damage and Completion of Infrastructure Works - Stormwater, Kerb And Gutter, Footpaths, Vehicular Crossing and Road Pavement C15. Tree Protection Measures to be shown on Construction Drawings C16. Protection of Trees C17. Garbage and Recycling Facilities C18. Asbestos and Hazardous Material Survey C19. Section 7.12 Contributions C20. Security Deposit/Guarantee Schedule C21. BASIX Commitments C22. Landscape Amendments C23. Southern Boundary Fence C24. Works to be Contained within Lot C25. Protection of Trees C26. Protection of Trees C27. Works to be Contained within Lot C87. Protection of Trees C88. SASS Commencement of any Works (and continuing where indicated) C89. Prior to the Commencement of any Works (and continuing where indicated) C80. Protection of Trees C81. Cigarette Butt Receptacle C81. Cigarette Butt Receptacle C82. Parking Restrictions C83. Road Reserve Safety C84. Temporary Disposal of Stormwater Runoff C85. Removal of Extra Fabric C86. Removal of Extra Fabric C86. Removal of Extra Fabric C87. Cigarette Butt Receptacle C87. Parking Restrictions C88. Removal of Extra Fabric C89. Removal of Extra Fabric C89. Parking Restrictions C89. Removal of Extra Fabric C89. Removal of Extra Fabric C80. Removal of Extra Fabric C80. Removal of Extra Fabric C80. Security Deposity of Extra Fabric C80. Removal of Extra Fabric	A4.	External rinishes and iviaterials	8
C2. Dilapidation Survey Private Property (Neighbouring Buildings) Structural Adequacy (Semi Detached and Terrace Buildings) 9 C5. Sediment Control 66. Waste Management Plan 77. Colours, Finishes and Materials (Conservation Areas) 10 C8. Skylight(s) 11 C9. Heritage Requirements 11 C10. Work Zone 11 C11. Parking Meter Relocation 11 C12. Obtain Driveway Crossing Permit under S.138 Roads Act 1993 12 C13. Stormwater Disposal 14 C14. Bond for Damage and Completion of Infrastructure Works - Stormwater, Kerb And Gutter, Footpaths, Vehicular Crossing and Road Pavement 14 C15. Tree Protection Measures to be shown on Construction Drawings 15 C16. Protection of Trees 15 C17. Garbage and Recycling Facilities 15 C18. Asbestos and Hazardous Material Survey 16 C19. Section 7.12 Contributions 16 C20. Security Deposity Guarantee Schedule 17 C21. BASIX Commitments 17 C22. Landscape Amendments 17 C23. Southern Boundary Fence 18 C24. Works to be Contained within Lot 18 CD. Prior to the Commencement of any Works (and continuing where indicated) E. During Demolition and Building Work E1. Cigarette Butt Receptacle 19 Caparity Eposity Disposal of Stormwater Runoff 20 Eemporary Disposal of Stormwater Runoff 20 Emporary Disposal of Stormwater Runoff 21 22 23 24 25 26 26 26 26 26 26 27 27 28 28 29 20 20 20 20 20 20 20 20 20 20 20 20 20	С.	Prior to the Issue of a Construction Certificate (and ongoing, where indicated)	
C3. Structural Adequacy (Semi Detached and Terrace Buildings) 9 Structural Adequacy of Existing Building 9 Waste Management Plan 10 C7. Colours, Finishes and Materials (Conservation Areas) 10 Heritage Requirements 11 C9. Heritage Requirements 11 Parking Meter Relocation 11 Parking Meter Relocation 11 Parking Meter Relocation 12 Obtain Driveway Crossing Permit under S.138 Roads Act 1993 12 Stormwater Disposal 13 Stormwater Disposal 14 Bond for Damage and Completion of Infrastructure Works - Stormwater, Kerb And Gutter, Footpaths, Vehicular Crossing and Road Pavement 15 Tree Protection Measures to be shown on Construction Drawings 15 Protection of Trees 15 Garbage and Recycling Facilities 15 Garbage and Recycling Facilities 15 Section 7.12 Contributions 16 Section 7.12 Contributions 16 Sectivity Deposit/Guarantee Schedule 17 BASIX Commitments 17 Landscape Amendments 17 Landscape Amendments 17 Works to be Contained within Lot 18 Protection of Trees 18 Works to be Contained within Lot 19 Protection of Trees 18 Cyblic Liability Insurance - Works on Public Land 20 Commencement of Works' Notice 21 Public Liability Insurance - Works on Public Land 22 Public Liability Insurance - Works on Public Land 23 Road Reserve Safety 24 Parking Restrictions 25 Removal of Extra Fabric 26 Parking Restrictions 27 Eemporary Disposal of Stormwater Runoff 28 Removal of Extra Fabric 29 Parkmoval of Extra Fabric 20 Eemporary Disposal of Stormwater Runoff	C1.	Dilapidation Report Damage to Public Infrastructure	8
C4. Structural Adequacy of Existing Building C5. Sediment Control G6. Waste Management Plan C7. Colours, Finishes and Materials (Conservation Areas) C8. Skylight(s) C9. Heritage Requirements C10. Work Zone C11. Parking Meter Relocation C12. Obtain Driveway Crossing Permit under S.138 Roads Act 1993 C13. Stormwater Disposal C14. Bond for Damage and Completion of Infrastructure Works - Stormwater, Kerb And Gutter, Footpaths, Vehicular Crossing and Road Pavement C15. Tree Protection Measures to be shown on Construction Drawings C16. Protection of Trees C17. Garbage and Recycling Facilities C18. Asbestos and Hazardous Material Survey C19. Section 7.12 Contributions C10. Security Deposit/Guarantee Schedule C11. BASIX Commitments C12. Landscape Amendments C13. Southern Boundary Fence C14. Works to be Contained within Lot C15. Prior to the Commencement of any Works (and continuing where indicated) C16. Prior to the Commencement of My Works (and continuing where indicated) C17. Cigarette Butt Receptacle C18. Cigarette Butt Receptacle C19. Parking Restrictions C19. Section Fores C19. Section Special Stormwater Runoff C20. Secmoval of Extra Fabric	C2.	Dilapidation Survey Private Property (Neighbouring Buildings)	8
C5. Sediment Control C6. Waste Management Plan C7. Colours, Finishes and Materials (Conservation Areas) C8. Skylight(s) C9. Heritage Requirements C10. Work Zone C11. Parking Meter Relocation C12. Obtain Driveway Crossing Permit under S.138 Roads Act 1993 C13. Stormwater Disposal C14. Bond for Damage and Completion of Infrastructure Works - Stormwater, Kerb And Gutter, Footpaths, Vehicular Crossing and Road Pavement C15. Tree Protection Measures to be shown on Construction Drawings C16. Protection of Trees C17. Garbage and Recycling Facilities C18. Asbestos and Hazardous Material Survey C19. Section 7.12 Contributions C10. Security Deposit/Guarantee Schedule C11. BASIX Commitments C12. Landscape Amendments C13. Southern Boundary Fence C14. Works to be Contained within Lot C15. Protection of Trees C17. Owner of Trees C18. As Southern Boundary Fence C19. Security Deposit/Guarantee Schedule C20. Prior to the Commencement of any Works (and continuing where indicated) C21. Protection of Trees C22. Landscape Amendments C23. Commencement of Works' Notice C24. Works to be Contained within Lot C25. Protection of Trees C26. Protection of Trees C27. Removal of Extra Fabric C28. Removal of Extra Fabric C29. Removal of Extra Fabric C20. Removal of Extra Fabric	C3.	Structural Adequacy (Semi Detached and Terrace Buildings)	9
C6.Waste Management Plan10C7.Colours, Finishes and Materials (Conservation Areas)108.Skylight(s)11C9.Heritage Requirements11C10.Work Zone11C11.Parking Meter Relocation12C12.Obtain Driveway Crossing Permit under S.138 Roads Act 199312C13.Stornwater Disposal14C14.Bond for Damage and Completion of Infrastructure Works - Stornwater, Kerb And Gutter, Footpaths, Vehicular Crossing and Road Pavement14C15.Tree Protection Measures to be shown on Construction Drawings15C16.Protection of Trees15C17.Garbage and Recycling Facilities15C18.Asbestos and Hazardous Material Survey16C19.Section 7.12 Contributions16C20.Security Deposit/Guarantee Schedule17C21.BASIX Commitments17C22.Landscape Amendments17C23.Southern Boundary Fence18C24.Works to be Contained within Lot18D.Prior to the Commencement of any Works (and continuing where indicated)E.During Demolition and Building WorkE.During Demolition and Building WorkE.Cigarette Butt Receptacle19E.Parking Restrictions19E.Parking Restrictions19E.Parking Restrictions20E.Removal of Extra Fabric20	C4.	Structural Adequacy of Existing Building	9
C7. Colours, Finishes and Materials (Conservation Areas) Skylight(s) Heritage Requirements 11 C10. Work Zone 11 C11. Parking Meter Relocation 12 C12. Obtain Driveway Crossing Permit under S.138 Roads Act 1993 12 C13. Stormwater Disposal 14 Bond for Damage and Completion of Infrastructure Works - Stormwater, Kerb And Gutter, Footpaths, Vehicular Crossing and Road Pavement C15. Tree Protection Measures to be shown on Construction Drawings 15 C16. Protection of Trees C17. Garbage and Recycling Facilities C18. Asbestos and Hazardous Material Survey 16 C19. Section 7.12 Contributions C20. Security Deposit/Guarantee Schedule C11. BASIX Commitments C12. Landscape Amendments C13. Southern Boundary Fence C24. Works to be Contained within Lot C25. Protection of Trees C26. Protection of Trees C27. Protection of Trees C28. Works to be Contained within Lot C29. Public Liability Insurance - Works on Public Land C30. Commencement of Works' Notice C40. Protection of Trees C51. Cigarette Butt Receptacle C52. Parking Restrictions C53. Road Reserve Safety C44. Temporary Disposal of Stormwater Runoff C55. Removal of Extra Fabric C50. Removal of Extra Fabric	C5.	Sediment Control	9
C8. Skylight(s) 11 C9. Heritage Requirements 11 C10. Work Zone 11 C11. Parking Meter Relocation 12 C12. Obtain Driveway Crossing Permit under S.138 Roads Act 1993 12 C13. Stornwater Disposal 14 C14. Bond for Damage and Completion of Infrastructure Works - Stormwater, Kerb And Gutter, Footpaths, Vehicular Crossing and Road Pavement 14 C15. Tree Protection Measures to be shown on Construction Drawings 15 C16. Protection of Trees 15 C17. Garbage and Recycling Facilities 15 C18. Asbestos and Hazardous Material Survey 16 C19. Section 7.12 Contributions 16 C20. Security Deposit/Guarantee Schedule 17 C21. BASIX Commitments 17 C22. Landscape Amendments 17 C23. Southern Boundary Fence 18 C24. Works to be Contained within Lot 18 D. Prior to the Commencement of any Works (and continuing where indicated) E. During Demolition and Building Work <	C6.	Waste Management Plan	10
C9. Heritage Requirements 11 C10. Work Zone 11 C11. Parking Meter Relocation 12 C12. Obtain Driveway Crossing Permit under S.138 Roads Act 1993 12 C13. Stormwater Disposal 14 C14. Bond for Damage and Completion of Infrastructure Works - Stormwater, Kerb And Gutter, Footpaths, Vehicular Crossing and Road Pavement 14 C15. Tree Protection Measures to be shown on Construction Drawings 15 C16. Protection of Trees 15 C17. Garbage and Recycling Facilities 15 C18. Asbestos and Hazardous Material Survey 16 C19. Section 7.12 Contributions 16 C20. Security Deposit/Guarantee Schedule 17 C21. BASIX Commitments 17 C22. Landscape Amendments 17 C23. Southern Boundary Fence 18 C24. Works to be Contained within Lot 18 D. Prior to the Commencement of any Works (and continuing where indicated) D1. Protection of Trees 18 D2. Public Liability Insurance - Works on Public Land 18 D3. Commencement of Works' Notice 19 E. During Demolition and Building Work E1. Cigarette Butt Receptacle 19 E2. Parking Restrictions 19 E3. Road Reserve Safety 19 E4. Temporary Disposal of Stormwater Runoff 20 E5. Removal of Extra Fabric 20	C7.	Colours, Finishes and Materials (Conservation Areas)	10
C10. Work Zone 11 C11. Parking Meter Relocation 12 C12. Obtain Driveway Crossing Permit under S.138 Roads Act 1993 12 C13. Stormwater Disposal 14 C14. Bond for Damage and Completion of Infrastructure Works - Stormwater, Kerb And Gutter, Footpaths, Vehicular Crossing and Road Pavement 14 C15. Tree Protection Measures to be shown on Construction Drawings 15 C16. Protection of Trees 15 C17. Garbage and Recycling Facilities 15 C18. Asbestos and Hazardous Material Survey 16 C19. Section 7.12 Contributions 16 C20. Security Deposit/Guarantee Schedule 17 C21. BASIX Commitments 17 C22. Landscape Amendments 17 C23. Southern Boundary Fence 18 C24. Works to be Contained within Lot 18 D. Prior to the Commencement of any Works (and continuing where indicated) E. During Demolition and Building Work E1. Cigarette Butt Receptacle 19 E2. Parking Restrictions 19 E3. Road Reserve Safety 19 E4. Temporary Disposal of Stormwater Runoff 20 E5. Removal of Extra Fabric 20	C8.	Skylight(s)	11
C11.Parking Meter Relocation12C12.Obtain Driveway Crossing Permit under S.138 Roads Act 199312C13.Stormwater Disposal14C14.Bond for Damage and Completion of Infrastructure Works - Stormwater, Kerb And Gutter, Footpaths, Vehicular Crossing and Road Pavement14C15.Tree Protection Measures to be shown on Construction Drawings15C16.Protection of Trees15C17.Garbage and Recycling Facilities15C18.Asbestos and Hazardous Material Survey16C19.Section 7.12 Contributions16C20.Security Deposit/Guarantee Schedule17C21.BASIX Commitments17C22.Landscape Amendments17C23.Southern Boundary Fence18C24.Works to be Contained within Lot18D. Prior to the Commencement of any Works (and continuing where indicated)D1.Protection of Trees18D2.Public Liability Insurance - Works on Public Land18D3.Commencement of Works' Notice19E. During Demolition and Building WorkE1.Cigarette Butt Receptacle19E2.Parking Restrictions19E3.Road Reserve Safety19E4.Temporary Disposal of Stormwater Runoff20E5.Removal of Extra Fabric20	C9.	Heritage Requirements	11
C12. Obtain Driveway Crossing Permit under S.138 Roads Act 1993 12 C13. Stormwater Disposal 14 C14. Bond for Damage and Completion of Infrastructure Works - Stormwater, Kerb And Gutter, Footpaths, Vehicular Crossing and Road Pavement 14 C15. Tree Protection Measures to be shown on Construction Drawings 15 C16. Protection of Trees 15 C17. Garbage and Recycling Facilities 15 C18. Asbestos and Hazardous Material Survey 16 C19. Section 7.12 Contributions 16 C20. Security Deposit/Guarantee Schedule 17 C21. BASIX Commitments 17 C22. Landscape Amendments 17 C23. Southern Boundary Fence 18 C24. Works to be Contained within Lot 18 D. Prior to the Commencement of any Works (and continuing where indicated) E. During Demolition and Building Work E1. Cigarette Butt Receptacle 19 C2. Parking Restrictions 19 C3. Road Reserve Safety 19 C4. Temporary Disposal of Stormwater Runoff 20 C5. Removal of Extra Fabric	C10.	Work Zone	11
C13. Stormwater Disposal 14 C14. Bond for Damage and Completion of Infrastructure Works - Stormwater, Kerb And Gutter, Footpaths, Vehicular Crossing and Road Pavement 14 C15. Tree Protection Measures to be shown on Construction Drawings 15 C16. Protection of Trees 15 C17. Garbage and Recycling Facilities 15 C18. Asbestos and Hazardous Material Survey 16 C19. Section 7.12 Contributions 16 C20. Security Deposit/Guarantee Schedule 17 C21. BASIX Commitments 17 C22. Landscape Amendments 17 C23. Southern Boundary Fence 18 C24. Works to be Contained within Lot 18 D. Prior to the Commencement of any Works (and continuing where indicated) D1. Protection of Trees 18 D2. Public Liability Insurance - Works on Public Land 18 D3. Commencement of Works' Notice 19 E. During Demolition and Building Work E1. Cigarette Butt Receptacle 19 E2. Parking Restrictions 19 E3. Road Reserve Safety 19 E4. Temporary Disposal of Stormwater Runoff 20 E5. Removal of Extra Fabric 20	C11.	Parking Meter Relocation	12
C14. Bond for Damage and Completion of Infrastructure Works - Stormwater, Kerb And Gutter, Footpaths, Vehicular Crossing and Road Pavement 14 C15. Tree Protection Measures to be shown on Construction Drawings 15 C16. Protection of Trees 15 C17. Garbage and Recycling Facilities 15 C18. Asbestos and Hazardous Material Survey 16 C19. Section 7.12 Contributions 16 C20. Security Deposit/Guarantee Schedule 17 C21. BASIX Commitments 17 C22. Landscape Amendments 17 C23. Southern Boundary Fence 18 C24. Works to be Contained within Lot 18 D. Prior to the Commencement of any Works (and continuing where indicated) D1. Protection of Trees 18 D2. Public Liability Insurance - Works on Public Land 18 D3. Commencement of Works' Notice 19 E. During Demolition and Building Work E1. Cigarette Butt Receptacle 19 E2. Parking Restrictions 19 E3. Road Reserve Safety 19 E4. Temporary Disposal of Stormwater Runoff 20 E5. Removal of Extra Fabric 20	C12.	Obtain Driveway Crossing Permit under S.138 Roads Act 1993	12
And Gutter, Footpaths, Vehicular Crossing and Road Pavement C15. Tree Protection Measures to be shown on Construction Drawings C16. Protection of Trees C17. Garbage and Recycling Facilities C18. Asbestos and Hazardous Material Survey C19. Section 7.12 Contributions C20. Security Deposit/Guarantee Schedule C21. BASIX Commitments C22. Landscape Amendments C23. Southern Boundary Fence C24. Works to be Contained within Lot C25. Prior to the Commencement of any Works (and continuing where indicated) C67. Protection of Trees C87. Public Liability Insurance - Works on Public Land C88. During Demolition and Building Work C89. Parking Restrictions C90. Parking Restrictions C91. Parking Restrictions C92. Parking Restrictions C93. Road Reserve Safety C94. Temporary Disposal of Stormwater Runoff C95. Removal of Extra Fabric	C13.	Stormwater Disposal	14
C15. Tree Protection Measures to be shown on Construction Drawings 15 C16. Protection of Trees 15 C17. Garbage and Recycling Facilities 15 C18. Asbestos and Hazardous Material Survey 16 C19. Section 7.12 Contributions 16 C20. Security Deposit/Guarantee Schedule 17 C21. BASIX Commitments 17 C22. Landscape Amendments 17 C23. Southern Boundary Fence 18 C24. Works to be Contained within Lot 18 D. Prior to the Commencement of any Works (and continuing where indicated) D1. Protection of Trees 18 D2. Public Liability Insurance - Works on Public Land 18 D3. Commencement of Works' Notice 19 E. During Demolition and Building Work E1. Cigarette Butt Receptacle 19 E2. Parking Restrictions 19 E3. Road Reserve Safety 19 E4. Temporary Disposal of Stormwater Runoff 20 E5. Removal of Extra Fabric 20	C14.	·	4.4
C16. Protection of Trees 15 C17. Garbage and Recycling Facilities 15 C18. Asbestos and Hazardous Material Survey 16 C19. Section 7.12 Contributions 16 C20. Security Deposit/Guarantee Schedule 17 C21. BASIX Commitments 17 C22. Landscape Amendments 17 C23. Southern Boundary Fence 18 C24. Works to be Contained within Lot 18 D. Prior to the Commencement of any Works (and continuing where indicated) D1. Protection of Trees 18 D2. Public Liability Insurance - Works on Public Land 18 D3. Commencement of Works' Notice 19 E. During Demolition and Building Work E1. Cigarette Butt Receptacle 19 E2. Parking Restrictions 19 E3. Road Reserve Safety 19 E4. Temporary Disposal of Stormwater Runoff 20 E5. Removal of Extra Fabric 20	C4.F	· · · · · · · · · · · · · · · · · · ·	
C17. Garbage and Recycling Facilities 15 C18. Asbestos and Hazardous Material Survey 16 C19. Section 7.12 Contributions 16 C20. Security Deposit/Guarantee Schedule 17 C21. BASIX Commitments 17 C22. Landscape Amendments 17 C23. Southern Boundary Fence 18 C24. Works to be Contained within Lot 18 D. Prior to the Commencement of any Works (and continuing where indicated) D1. Protection of Trees 18 D2. Public Liability Insurance - Works on Public Land 18 D3. Commencement of Works' Notice 19 E. During Demolition and Building Work E1. Cigarette Butt Receptacle 19 E2. Parking Restrictions 19 E3. Road Reserve Safety 19 E4. Temporary Disposal of Stormwater Runoff 20 E5. Removal of Extra Fabric 20		-	
C18. Asbestos and Hazardous Material Survey C19. Section 7.12 Contributions C20. Security Deposit/Guarantee Schedule C21. BASIX Commitments C22. Landscape Amendments C23. Southern Boundary Fence C24. Works to be Contained within Lot C25. Prior to the Commencement of any Works (and continuing where indicated) C26. Prior to the Commencement of any Works (and continuing where indicated) C27. Protection of Trees C28. Public Liability Insurance - Works on Public Land C29. Public Liability Insurance - Works on Public Land C09. Prior to the Commencement of Works' Notice C19. Puring Demolition and Building Work C10. Parking Restrictions C10. Parking Rest			
C19. Section 7.12 Contributions 16 C20. Security Deposit/Guarantee Schedule 17 C21. BASIX Commitments 17 C22. Landscape Amendments 17 C23. Southern Boundary Fence 18 C24. Works to be Contained within Lot 18 D. Prior to the Commencement of any Works (and continuing where indicated) D1. Protection of Trees 18 D2. Public Liability Insurance - Works on Public Land 18 D3. Commencement of Works' Notice 19 E. During Demolition and Building Work E1. Cigarette Butt Receptacle 19 E2. Parking Restrictions 19 E3. Road Reserve Safety 19 E4. Temporary Disposal of Stormwater Runoff 20 E5. Removal of Extra Fabric 20			
C20. Security Deposit/Guarantee Schedule 17 C21. BASIX Commitments 17 C22. Landscape Amendments 17 C23. Southern Boundary Fence 18 C24. Works to be Contained within Lot 18 D. Prior to the Commencement of any Works (and continuing where indicated) D1. Protection of Trees 18 D2. Public Liability Insurance - Works on Public Land 18 D3. Commencement of Works' Notice 19 E. During Demolition and Building Work E1. Cigarette Butt Receptacle 19 E2. Parking Restrictions 19 E3. Road Reserve Safety 19 E4. Temporary Disposal of Stormwater Runoff 20 E5. Removal of Extra Fabric 20		·	
C21. BASIX Commitments 17 C22. Landscape Amendments 17 C23. Southern Boundary Fence 18 C24. Works to be Contained within Lot 18 D. Prior to the Commencement of any Works (and continuing where indicated) D1. Protection of Trees 18 D2. Public Liability Insurance - Works on Public Land 18 D3. Commencement of Works' Notice 19 E. During Demolition and Building Work E1. Cigarette Butt Receptacle 19 E2. Parking Restrictions 19 E3. Road Reserve Safety 19 E4. Temporary Disposal of Stormwater Runoff 20 E5. Removal of Extra Fabric 20			
C22.Landscape Amendments17C23.Southern Boundary Fence18C24.Works to be Contained within Lot18D.Prior to the Commencement of any Works (and continuing where indicated)D1.Protection of Trees18D2.Public Liability Insurance - Works on Public Land18D3.Commencement of Works' Notice19E.During Demolition and Building WorkE1.Cigarette Butt Receptacle19E2.Parking Restrictions19E3.Road Reserve Safety19E4.Temporary Disposal of Stormwater Runoff20E5.Removal of Extra Fabric20		, , .	
C23. Southern Boundary Fence 18 C24. Works to be Contained within Lot 18 D. Prior to the Commencement of any Works (and continuing where indicated) D1. Protection of Trees 18 D2. Public Liability Insurance - Works on Public Land 18 D3. Commencement of Works' Notice 19 E. During Demolition and Building Work E1. Cigarette Butt Receptacle 19 E2. Parking Restrictions 19 E3. Road Reserve Safety 19 E4. Temporary Disposal of Stormwater Runoff 20 E5. Removal of Extra Fabric 20			
C24. Works to be Contained within Lot D. Prior to the Commencement of any Works (and continuing where indicated) D1. Protection of Trees D2. Public Liability Insurance - Works on Public Land D3. Commencement of Works' Notice E. During Demolition and Building Work E1. Cigarette Butt Receptacle E2. Parking Restrictions E3. Road Reserve Safety E4. Temporary Disposal of Stormwater Runoff E5. Removal of Extra Fabric 18 19 19 20		·	
D. Prior to the Commencement of any Works (and continuing where indicated) D1. Protection of Trees D2. Public Liability Insurance - Works on Public Land D3. Commencement of Works' Notice E. During Demolition and Building Work E1. Cigarette Butt Receptacle E2. Parking Restrictions E3. Road Reserve Safety E4. Temporary Disposal of Stormwater Runoff E5. Removal of Extra Fabric D18 18 19 19 19 20		•	
D1. Protection of Trees D2. Public Liability Insurance - Works on Public Land D3. Commencement of Works' Notice E. During Demolition and Building Work E1. Cigarette Butt Receptacle E2. Parking Restrictions E3. Road Reserve Safety E4. Temporary Disposal of Stormwater Runoff E5. Removal of Extra Fabric 18 18 18 19 19 19 19 19 19 19 19 19 20 20	C24.	Works to be Contained within Lot	18
D2.Public Liability Insurance - Works on Public Land18D3.Commencement of Works' Notice19E.During Demolition and Building WorkE1.Cigarette Butt Receptacle19E2.Parking Restrictions19E3.Road Reserve Safety19E4.Temporary Disposal of Stormwater Runoff20E5.Removal of Extra Fabric20	D.	Prior to the Commencement of any Works (and continuing where indicated)	
D3. Commencement of Works' Notice 19 E. During Demolition and Building Work E1. Cigarette Butt Receptacle 19 E2. Parking Restrictions 19 E3. Road Reserve Safety 19 E4. Temporary Disposal of Stormwater Runoff 20 E5. Removal of Extra Fabric 20	D1.	Protection of Trees	18
E. During Demolition and Building Work E1. Cigarette Butt Receptacle E2. Parking Restrictions E3. Road Reserve Safety E4. Temporary Disposal of Stormwater Runoff E5. Removal of Extra Fabric 20	D2.	Public Liability Insurance - Works on Public Land	18
E1. Cigarette Butt Receptacle 19 E2. Parking Restrictions 19 E3. Road Reserve Safety 19 E4. Temporary Disposal of Stormwater Runoff 20 E5. Removal of Extra Fabric 20	D3.	Commencement of Works' Notice	19
E2.Parking Restrictions19E3.Road Reserve Safety19E4.Temporary Disposal of Stormwater Runoff20E5.Removal of Extra Fabric20	E.	During Demolition and Building Work	
E2.Parking Restrictions19E3.Road Reserve Safety19E4.Temporary Disposal of Stormwater Runoff20E5.Removal of Extra Fabric20	E1.	Cigarette Butt Receptacle	19
E3. Road Reserve Safety E4. Temporary Disposal of Stormwater Runoff E5. Removal of Extra Fabric 19 20			
E4. Temporary Disposal of Stormwater Runoff 20 E5. Removal of Extra Fabric 20			
E5. Removal of Extra Fabric 20			
Eb. Dust Emission and Air Quality 20	E6.	Dust Emission and Air Quality	20

I1.	Maintenance of Approved Landscaping	29
I.	Ongoing/Operational Conditions	
G8.	Compliance with Certain Conditions	29
G7.	Landscaping	29
G6.	BASIX Completion Certificate	29
G5.	Certification of Tree Condition	28
G4.	Asbestos Clearance Certificate	28
G3.	Utility Services	28
G2.	Damage to Adjoining Properties	28
G1.	Infrastructure Repair and Completion of Works	27
G.	Prior to the Issue of an Occupation Certificate	
F9.	Site Sign	27
F8.	Protection of Public Places	26
F7.	Excavation/Demolition	26
F6.	Mandatory Critical Stage Inspections	26
F5.	Occupation Certificate	26
гз. F4.	Construction Certificate	25 26
F2.	Appointment of a Principal Certifying Authority (PCA)	25 25
F1. F2.	National Construction Code Home Building Act	25 25
F.	Prescribed Conditions imposed under EP&A Act and Regulations and other relevant Legislation	
E20.	Asbestos Removal	24
E19.	Waste Disposal	24
E18.	Plant and Equipment Kept Within Site	24
E17.	Prohibition on Use of Pavements	24
E16.	Health and Safety	24
E15.	Site Amenities and Facilities	23
E14.	Sediment and Erosion Control Signage	23
E13.	Installation and Maintenance of Sediment Control	23
E12.	Construction Hours (Commercial Core and Mixed-Use Zones)	22
E11.	Special Permits	21
E10.	Protection of Trees	21
E9.	No Removal of Trees on Public Property	21
E7.	Developer's Cost of Work on Council Property	21
E7.	Noise and Vibration	21

A. Conditions that Identify Approved Plans

Development in Accordance with Plans/Documentation

A1. The development must be carried out in accordance with the following drawings and documentation and endorsed with Council's approval stamp, except where amended by the following conditions of this consent.

Drawing No.	Title	Drawn by	Dated	Received
DA1.00	Material Board	Stirling & Andie	17/09/2021	13/10/2021
DA1.02	Site Plan	Stirling & Andie	17/09/2021	13/10/2021
DA1.04	Demolition Plan	Stirling & Andie	17/09/2021	13/10/2021
DA1.06	Demolition/Proposed Ground Floor Plan	Stirling & Andie	17/09/2021	13/10/2021
DA1.07	Proposed Attic Floor Plan	Stirling & Andie	17/09/2021	13/10/2021
DA1.08	Proposed Roof Plan	Stirling & Andie	17/09/2021	13/10/2021
DA1.10	Proposed Landscape Plan	Stirling & Andie	17/09/2021	13/10/2021
DA2.00	Elevation 1 (South)	Stirling & Andie	17/09/2021	13/10/2021
DA2.01	Elevation 2 (East)	Stirling & Andie	17/09/2021	13/10/2021
DA2.02	Elevation 3 (West)	Stirling & Andie	17/09/2021	13/10/2021
DA2.03	Elevation 4 (North)	Stirling & Andie	17/09/2021	13/10/2021
DA2.04	Section AA	Stirling & Andie	17/09/2021	13/10/2021
DA2.05	Front and Rear Fence	Stirling & Andie	17/09/2021	13/10/2021

(Reason:

To ensure that the form of the development undertaken is in accordance with the determination of Council, Public Information)

Plans on Site

A2. A copy of all stamped approved plans, specifications and documents (including the plans, specifications and documents submitted and approved with the Construction Certificate) must be kept on site at all times so as to be readily available for perusal by any officer of Council or the Principal Certifying Authority.

All documents kept on site in accordance with this condition must be provided to any officer of the Council or the certifying authority upon their request.

(Reason:

To ensure that the form of the development undertaken is in accordance with the determination of Council, Public Information and to ensure ongoing compliance)

No Demolition of Extra Fabric

A3. Alterations to, and demolition of the existing building shall be limited to that documented on the approved plans.

(Reason: To ensure compliance with the approved development)

External Finishes and Materials

A4. External finishes and materials must be in accordance with the submitted schedule, numbered DA1.00, dated 17 September 2021, prepared by Stirling & Andie, and received by Council on 13 October 2021, unless otherwise modified by Council's condition of consent or by writing.

(Reason: To ensure that the form of the development undertaken is in accordance with the

determination of Council, Public Information)

C. Prior to the Issue of a Construction Certificate (and ongoing, where indicated)

Dilapidation Report Damage to Public Infrastructure

C1. A dilapidation survey and report (including photographic record) must be prepared by a suitably qualified consultant which details the pre-developed condition of the existing public infrastructure in the vicinity of the development site. Particular attention must be paid to accurately recording any pre-developed damaged areas so that Council is fully informed when assessing any damage to public infrastructure caused as a result of the development. A copy of the dilapidation survey and report is to be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate.

The developer may be held liable for all damage to public infrastructure in the vicinity of the site, where such damage is not accurately recorded and demonstrated as pre-existing under the requirements of this condition.

The developer shall bear the cost of carrying out works to restore all public infrastructure damaged as a result of the carrying out of the development, and no occupation of the development shall occur until damage caused as a result of the carrying out of the development is rectified.

A copy of the dilapidation survey and report must be lodged with North Sydney Council by the Certifying Authority with submission of the Construction Certificate documentation.

(Reason: To record the condition of public infrastructure prior to the commencement of construction)

Dilapidation Survey Private Property (Neighbouring Buildings)

C2. A photographic survey and dilapidation report of adjoining properties (Nos. 25 and 29 Edward Street) detailing the physical condition of those properties, both internally and externally, including, but not limited to, such items as walls, ceilings, roof, structural members and other similar items, SHALL BE submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The survey and report are to be prepared by an appropriately qualified person agreed to by both the applicant and the owner of the adjoining property. A copy of the report is to be provided to Council, if Council is not the Certifying Authority, prior to the issue of any Construction Certificate.

All costs incurred in achieving compliance with this condition shall be borne by the person entitled to act on this Consent.

In the event that access for undertaking the photographic survey and dilapidation report is denied by an adjoining owner, the applicant MUST DEMONSTRATE, in writing, to the satisfaction of Council that all reasonable steps have been taken to obtain access and advise the affected property owner of the reason for the survey and that these steps have failed. Written concurrence must be obtained from Council in such circumstances.

(Note: This documentation is for record keeping purposes only and may be used by an

applicant or affected property owner to assist in any action required to resolve any dispute over damage to adjoining properties arising from the works. It is in the applicant's and adjoining owner's interest for it to be as full and detailed as possible)

(Reason: Proper management of records)

Structural Adequacy (Semi-detached and Terrace Buildings)

C3. A report from an appropriately qualified and practising structural engineer, certifying the structural adequacy of the adjoining properties (Nos. 25 and 29 Edward Street) which certifies their ability to withstand the proposed works and outlines any measures required to be implemented to ensure that no damage will occur to adjoining premises during the course of the works, must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The measures outlined in the certified report must be complied with at all times.

Under no circumstances shall the party or common wall be extended or altered without the prior written consent of the adjoining owner. Any such extension of the party wall shall be noted on title by way of appropriate easement or Section 88B instrument.

(Reason: To ensure the protection and structural integrity of adjoining properties, and that

common law property rights are recognised)

Structural Adequacy of Existing Building

C4. A report prepared by an appropriately qualified and practising structural engineer, certifying the structural adequacy of the property and its ability to withstand the proposed additional, or altered structural loads during all stages of construction shall be submitted to the Certifying Authority for approval prior to issue of any Construction Certificate. The certified report must also include all details of the methodology to be employed in construction phases to achieve the above requirements. The methodology in the certified report must be complied with at all times.

(Reason: To ensure the structural integrity of the building is maintained)

Sediment Control

C5. Where construction or excavation activity requires the disturbance of the soil surface or existing vegetation, erosion and sediment control techniques, as a minimum, are to be in accordance with the publication *Managing Urban Stormwater: Soils and Construction* (4th edition, Landcom, 2004) commonly referred to as the "Blue Book" or a suitable and effective alternative method.

A Sediment Control Plan must be prepared and submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate and prior to any works commencing. The Sediment Control Plan must be consistent with the Blue Book and disclose:

- a) All details of drainage to protect and drain the site during the construction processes;
- b) All sediment control devices, barriers and the like;
- c) Sedimentation tanks, ponds or the like;
- d) Covering materials and methods; and
- e) A schedule and programme of the sequence of the sediment and erosion control works or devices to be installed and maintained.
- f) Methods for the temporary and controlled disposal of stormwater during construction.

All works must be undertaken in accordance with the approved Sediment Control plan.

The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To protect the environment from the effects of sedimentation and erosion from development sites)

Waste Management Plan

- C6. A Waste Management Plan is to be submitted for approval by the Certifying Authority prior to the issue of any Construction Certificate. The plan must include, but not be limited to:
 - a) The estimated volume of waste and method of disposal for the construction and operation phases of the development;
 - b) The design of the on-site waste storage and recycling area; and
 - c) Administrative arrangements for waste and recycling management during the construction process.

The approved Waste Management Plan must be complied with at all times in the carrying out of the development.

(Reason: To encourage the minimisation of waste and recycling of building waste)

Colours, Finishes and Materials (Conservation Areas)

C7. The finishes, materials and exterior colours shall be complementary to the architectural style of the original building and sympathetic to the character of the Conservation Area. The exterior colour scheme is to use neutral tones and/or a traditional colour scheme, and shall not utilise vivid or crisp whites.

A schedule of finishes, materials and external colours shall be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the building plans and specifications submitted fully satisfy the requirements of this condition prior to the release of the Construction Certificate.

(Reason: To ensure that the completed colours, finishes, and materials are complementary to the

Conservation Area)

Skylight(s)

C8. Skylight flashing(s) and frame(s) to be coloured to match the roof material. Skylight(s) to sit no higher than 100 mm above roof plane when in a closed position. Plans and specifications which comply with this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate.

The Certifying Authority must ensure that the building plans and specifications submitted fully satisfy the requirements of this condition.

(Reason: To minimise the visual impact of the skylight(s) on the roof plane)

Heritage Requirements

C9. Details demonstrating compliance with the following are to be submitted with the Construction Certificate:

a) Rear Dormer

The proposed rear dormer is to be set below the existing roof ridge line.

b) Front Fence

The new front fence facing Edward Street is to be a traditional timber picket style fence up to maximum height of 1.2m and must be open in construction (minimum 50%) to allow filtered views of the front garden (i.e., not lapped).

The Certifying Authority must ensure that the building plans and specifications submitted fully satisfy the requirements of this condition.

(Reason: To ensure that the built elements are consistent and sympathetic to the character of the conservation area and the original dwelling)

Work Zone

C10. If a Work Zone is proposed, an application must be made to the North Sydney Local Traffic Committee to install the 'Work Zone'. A Work Zone permit is required to be issued by the Council prior to the issue of any Construction Certificate.

Work Zones are provided specifically for the set down and pick up of materials and not for the parking of private vehicles associated with the site. Works Zones will generally not be approved where there is sufficient space on-site for the setting down and picking up of goods being taken to or from a construction site. If the Work Zone is approved by the Committee, the Applicant must obtain a written copy of the related resolution from the North Sydney Local Traffic Committee and submit a copy of this to the Certifying Authority to enable issue of the Construction Certificate.

Where approval of the 'Work Zone' is given by the Committee, the requirements of the Committee, including installation of the necessary 'Work Zone' signage and payment of any fees, must occur prior to commencement of any works on the site. Further, at the expiration of the Work Zone approval, the developer is required to remove the Work Zone signs and reinstate any previous signs, all at the developer's cost. The requirements imposed by the Committee on the Work Zone permit (or permits) must be complied with at all times.

(Reason: Amenity and convenience during construction)

Parking Meter Relocation

C11. All costs associated with removal/relocation of the existing parking meter and associated meter infrastructure including any changes to signage and/or parking bay line markings, shall be paid in full to North Sydney Council prior to the issue of any Construction Certificate.

An Application to Satisfy DA Consent Condition must be submitted to North Sydney Council for the approval of the Parking Meter Manager. The application must include a copy of the plans of the proposed temporary and permanent driveways for the entire site.

The Certifying Authority must ensure that the specifications submitted, accompanying the issued Construction Certificate, fully satisfy this condition.

(Reason: To ensure the proper management of public land and funds)

Obtain Driveway Crossing Permit under S.138 Roads Act 1993

C12. A driveway crossing and roads infrastructure works permit to suit the approved off-street parking facilities must be granted by the Council prior to the issue of any Construction Certificate. In order to obtain a permit under S.138 of the Roads Act 1993, an application must be made to Council on the 'Vehicular Access Application' form with payment of the adopted assessment/inspection fees. Council will require civil design construction drawings and certification from the applicant's Civil Engineer to verify design details and enable issue of the permit. The requirements of the permit must be complied with at all times.

The civil design drawings must include the following at a minimum:

- a) the vehicular access way must comply with AS 2890.1 and Council's current Vehicular Access Application Guidelines and Specification (gutter bridges not permitted) to ensure that a B85 vehicle will not scrape/strike the surface of the carriageway, layback, vehicular crossing, or parking floor,
- b) the maximum width of the vehicular layback must be 3.5 metres (including the wings),

- c) the vehicular crossover must be set square to the kerb,
- d) the crossing (between the layback and the property boundary) must be placed on a single straight grade of approximately 4.5%, falling to the back of the layback, but taking into account that the change in cross fall grade in between the road shoulder and driveway crossing is no more than 15%; The cross fall of the road shoulder is measured for a distance of 1200 mm falling to the gutter lip, starting from the surface of the existing carriageway 1650 mm from the existing face of kerb;
- e) the gutter levels must match the existing levels and shall not be altered,
- f) transitioning works of (2) footpath panel(s) on both sides of the driveway crossing are required to ensure uniformity in the footpath,
- g) the kerb gutter and road shoulder must be transitioned 1m on both sides of the crossing to ensure uniformity in the road reserve,
- h) the road shoulder must be reconstructed minimum of 600mm from the gutter lip in AC10 50mm thick, adjacent to all new gutter works,
- i) any twisting of driveway access must occur entirely within the subject property,
- j) all inspection openings, utility services must be adjusted to match the proposed driveway levels,
- k) the design detail has to be provided with vehicular access application and must include sections along centreline and extremities are required at a scale of 1:50 to be taken from the centreline of the roadway through to the parking area itself and must include all changes of grade and levels both existing and proposed,
- a longitudinal section along the gutter line at a scale of 1:50 showing how it is intended to blend the vehicular crossing with the existing kerb and gutter; must include all changes of grade and levels both existing and proposed;
- m) a longitudinal section along the rear (Oak Lane) footpath property boundary at a scale of 1:50 is required; must include all changes of grade and levels both existing and proposed;
- n) any new pipelines within council land shall be hot dipped galvanised steel hollow section with a minimum wall thickness of 4.0 millimetres and a section height of 100 millimetres.

The permit must be granted by Council prior to the issue of any Construction Certificate.

All driveway and infrastructure works on the road reserve must be undertaken in accordance with the terms of the permit issued by Council. Inspections by Council will be required as specified. The Certifying Authority issuing the Construction Certificate must ensure that the permit issued by Council is obtained and referenced on and accompanies the Construction Certificate issued.

(Reason: To facilitate appropriate vehicular access to private sites, without disruption to pedestrian and vehicular traffic)

Stormwater Disposal

C13. Stormwater runoff generated by the approved development must be conveyed by gravity to Oak Lane. A licensed tradesman shall install plumbing components to achieve this requirement in accordance with the BCA and current plumbing standards and guidelines. Plans and specifications which comply with this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the building plans and specifications submitted, referenced on, and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To ensure appropriate provision for disposal and stormwater management arising from the development)

Bond for Damage and Completion of Infrastructure Works - Stormwater, Kerb and Gutter, Footpaths, Vehicular Crossing and Road Pavement

- C14. Prior to the issue of any Construction Certificate, security deposit or bank guarantee must be provided to Council to the sum of \$5,000 to be held by Council for the payment of cost for any/all of the following:
 - a) making good any damage caused to any property of the Council as a consequence of the doing of anything to which this consent relates,
 - b) completing any public work (such as road work, kerbing and guttering, footway construction, stormwater drainage and <u>environmental controls</u>) required in connection with this consent.
 - c) remedying any defects in any such public work that arise within six months after the work is completed.

The security required by this condition and in the schedule contained later in these conditions must be provided by way of a deposit with the Council; or other such guarantee that is satisfactory to Council (such as a bank guarantee). Any guarantee provided as security must name North Sydney Council as the nominated beneficiary and must not be subject to an expiry date.

The security will be refundable following the expiration of six months from the issue of any final Occupation Certificate or completion of public work required to be completed (whichever is the latest) but only upon inspection and release by Council's Engineers.

Council shall have full authority to make use of the bond for such restoration works as deemed necessary by Council in circumstances including the following:

- where the damage constitutes a hazard in which case Council may make use of the security immediately;
- the applicant has not repaired or commenced repairing damage within 48 hours of the issue by Council in writing of instructions to undertake such repairs or works;
- works in the public road associated with the development are to an unacceptable quality; and
- the Certifying Authority must ensure that security is provided to North Sydney Council prior to issue of any Construction Certificate.

(Reason: To ensure appropriate security for works on public land and an appropriate quality for new public infrastructure)

Tree Protection Measures to be shown on Construction Drawings

C15. The tree protection measures contained in the arborist report prepared by Hugh the Arborist dated 24 January 2022, shall be shown clearly on the Construction Certificate drawings. Plans and specifications showing the said tree protection measures must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate.

The Certifying Authority must ensure the construction plans and specifications submitted, referenced on, and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To ensure that appropriate tree protection measures are shown on construction

drawings)

Protection of Trees

C16. The following tree(s) are required to be protected and retained as part of the development consent in accordance with AS 4970-2009 – Protection of trees on development sites:

Tree	Location	Height
T1 Cupressus macrocarpa	Within the rear setback of No. 25 Edward Street	10m
T2 Cupressus macrocarpa	Within the rear setback of No. 25 Edward Street on the southern	
T3 Cupressus macrocarpa	boundary with 27 Edward Street	8m
T4 Cupressus macrocarpa	Within the rear setback of No. 25 Edward Street	8m

Plans and specifications complying with this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the building plans and specifications submitted, referenced on, and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

Any tree(s) shown as being retained on the approved plans (regardless of whether they are listed in the above schedule or not) must be protected and retained in accordance with this condition.

(Reason: Protection of existing environmental and community assets)

Garbage and Recycling Facilities

C17. Adequate provision must be made for the storage of waste and recyclable material generated by the premises. Plans and specifications which comply with this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To ensure the provision of appropriate waste facilities and to ensure efficient collection

of waste by collection contractors)

Asbestos & Hazardous Material Survey

C18. A report must be prepared by a suitably qualified person in relation to the existing building fabric to be demolished and/or disturbed identifying the presence or otherwise of asbestos contamination and, if asbestos contamination is present, making recommendations as to the work required to safely address the contamination.

Any demolition works or other works identified in the report as having to be carried out must be carried out in accordance with the recommendations of the report and the following:

- the removal of asbestos must be undertaken by a WorkCover licensed contractor; a)
- b) all removal must be in strict accordance with the requirements of the WorkCover Authority in relation to the removal, handling and disposal of material containing asbestos and any Work Safe Australia requirements.
- during the removal of any asbestos a sign stating "DANGER ASBESTOS REMOVAL IN PROGRESS" c) must be erected in a visible position at the boundary of the site; and
- d) Waste disposal receipts must be provided to the Certifying Authority as proof of correct disposal of asbestos laden waste.

The report must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the report, and other plans, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To ensure the long-term health of workers on site and occupants of the building is not put at risk unnecessarily)

Section 7.12 Development Contributions

C19. A monetary contribution pursuant to the provisions of Section 7.12 of the Environmental Planning and Assessment Act 1979 is to be paid to Council, in accordance with the North Sydney Council's Contribution Plan. Based on the cost of development a total contribution of \$4,800.00 is to be paid to Council to provide for additional local infrastructure improvements.

The contribution MUST BE paid prior to the issue of any Construction Certificate.

The above amount will be adjusted for inflation by reference to the Consumer Price (All Ordinaries) Index applicable at the time of the payment of the contribution.

A copy of the North Sydney Contribution Plan can be viewed at North Sydney Council's Customer Service Centre, 200 Miller Street, North Sydney or downloaded via Council's website at www.northsydney. nsw.gov.au.

(Reason: To retain a level of service for the existing population and to provide the same level of

service to the population resulting from new development)

Security Bond and Fee Schedule

C20. All fees and security deposits/ guarantees in accordance with the schedule below must be provided to Council prior to the issue of any Construction Certificate:

Security deposit/ guarantee	Amount (\$)
Infrastructure Damage Bond	\$5,000.00
TOTAL BONDS	\$5,000.00

Note: The following fees are applicable

Fees	Amount (\$)
Section 7.12 Development Contributions	\$4,800.00
TOTAL FEES	\$4,800.00

Compliance with the development consent) (Reason:

BASIX Commitments

C21. Under clause 97A(3) of the Environmental Planning and Assessment Regulation 2000, it is a condition of this development consent that all the commitments listed in BASIX Certificate No. A426464 for the development are fulfilled. Plans and specifications complying with this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

To ensure the proposed development will meet the Government's requirements for (Reason:

sustainability and statutory requirements)

Landscape Amendments

- C22. The site plan and landscape plan must be amended as follows to provide an appropriate landscaped setting and to demonstrate an improved level of compliance with the landscaped area and unbuilt-upon area controls:
 - 1) A portion of the paved areas located within the rear garden, to an area of approximately 5.7m², must be converted into lawn, garden beds, planters, or some other form of soft landscaping.
 - 2) A portion of the paved area located within the front garden, to an area of approximately 5.1m², must be converted into lawn, garden beds, planters, or some other form of soft landscaping (such as stepping stone pavers between planting).

An amended landscape plan complying with this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the amended landscape plan and other plans and specifications submitted fully satisfy the requirements of this condition.

(Reason: To ensure residential amenity and to demonstrate compliance with Council's

landscaped area controls)

Southern Boundary Fence

C23. Should any change be considered to the existing southern boundary fence shared between Nos. 25-27 Edward Street, North Sydney, the fence must be no higher than the height of the existing fence.

The Certifying Authority must ensure that the plans and specifications submitted fully satisfy the requirements of this condition.

(Reason: To ensure residential amenity)

Works to be Contained within Lot

C24. The approved works must be wholly contained within the lot of No. 27 Edward Street, North Sydney, and must not result in any encroachment into neighbouring lots without the prior written consent of the adjoining owner(s).

Plans and specifications which comply with this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate.

The Certifying Authority must ensure that the building plans and specifications submitted, referenced on, and accompanying the issued Construction Certificate, in order to fully satisfy the requirements of this condition.

(Reason: To ensure the protection and structural integrity of adjoining properties, and that

common law property rights are recognised)

D. Prior to the Commencement of any Works (and continuing where indicated)

Protection of Trees

D1. All trees that are specifically nominated to be retained by notation on plans or by condition as a requirement of this consent must be maintained and protected during demolition, excavation, and construction on the site in accordance with AS4970-2009 (Protection of trees on development sites).

A report containing recommendations, and methods of tree protection prepared by an appropriately qualified person must be provided to the Certifying Authority for approval by an appropriately qualified person prior to commencement of any works on the site. Any recommendations must be undertaken for the duration of works on the site.

(Reason: To ensure compliance with the requirement to retain significant planting on the site)

Public Liability Insurance - Works on Public Land

D2. Any person or contractor undertaking works on public land must take out Public Risk Insurance with a minimum cover of \$20 million in relation to the occupation of public land and the undertaking of approved works within Council's road reserve or public land, as approved by this consent.

The Policy is to note and provide protection/full indemnification for North Sydney Council, as an interested party. A copy of the Policy must be submitted to Council prior to commencement of any works. The Policy must be valid for the entire period that the works are being undertaken.

(Note: Applications for hoarding permits, vehicular crossings etc will require evidence of

insurance upon lodgement of the application)

(Reason: To ensure the community is protected from the cost of any claim for damages arising

from works on public land)

Commencement of Works' Notice

D3. Building work, demolition or excavation in accordance with this development consent must not be commenced until the developer has given at least two days' notice to North Sydney Council of the person's intention to commence building work, demolition or excavation in accordance with this development consent.

(Reason: To ensure appropriate safeguarding measures are in place prior to the commencement

of any building work, demolition or excavation)

E. During Demolition and Building Work

Cigarette Butt Receptacle

E1. A cigarette butt receptacle is to be provided on the site for the duration of excavation/demolition/construction process, for convenient use of site workers.

(Reason: To ensure adequate provision is made for builders' waste)

Parking Restrictions

E2. Existing public parking provisions in the vicinity of the site must be maintained at all times during works. The placement of any barriers, traffic cones, obstructions or other device in the road shoulder or kerbside lane is prohibited without the prior written consent of Council. Changes to existing public parking facilities/restrictions must be approved by the North Sydney Local Traffic Committee. The Developer will be held responsible for any breaches of this condition and will incur any fines associated with enforcement by Council regulatory officers.

(Reason: To ensure that existing kerbside parking provisions are not compromised during works)

Road Reserve Safety

E3. All public footways and roadways fronting and adjacent to the site must be maintained in a safe condition at all times during the course of the development works, with no obstructions caused to the said footways and roadways. Construction materials and plant must not be stored in the road reserve without approval of Council. A safe pedestrian circulation route and a pavement/route free of trip hazards must be maintained at all times on or adjacent to any public access ways fronting the construction site.

Where public infrastructure is damaged, repair works must be carried out in when and as directed by Council officers (at full Developer cost). Where pedestrian circulation is diverted on to the roadway or verge areas, clear directional signage and protective barricades must be installed in accordance with AS1742-3 (1996) "Traffic Control Devices for Work on Roads". If pedestrian circulation is not satisfactorily maintained across the site frontage, and action is not taken promptly to rectify the defects, Council may undertake proceedings to stop work.

(Reason: Public Safety)

Temporary Disposal of Stormwater Runoff

E4. During construction, stormwater runoff must be disposed in a controlled manner that is compatible with the erosion and sediment controls on the site. Immediately upon completion of any impervious areas on the site (including roofs, driveways, paving) and where the final drainage system is incomplete, the necessary temporary drainage systems must be installed to reasonably manage and control runoff as far as the approved point of stormwater discharge. Such ongoing measures must be to the satisfaction of the Certifying Authority.

(Reason: Stormwater control during construction)

Removal of Extra Fabric

E5. Should any portion of the existing building, trees, or curtilage of the site which is indicated on the approved plans to be retained be damaged for whatever reason, all the works in the area of the damaged portion are to cease and written notification of the damage is to be given to Council forthwith. No work is to resume until the written approval of Council to do so is obtained. Failure to comply with the provisions of this condition may result in the Council taking further action including legal proceedings if necessary.

(Reason: To ensure compliance with the terms of this development consent)

Dust Emission and Air Quality

- E6. The following must be complied with at all times:
 - a) Materials must not be burnt on the site.
 - b) Vehicles entering and leaving the site with soil or fill material must be covered.
 - c) Dust suppression measures must be carried out to minimise wind-borne emissions in accordance with the NSW Department of Housing's 1998 guidelines - Managing Urban Stormwater: Soils and Construction.
 - d) Odour suppression measures must also be carried out where appropriate so as to prevent nuisance occurring at adjoining properties.

(Reason: To ensure residential amenity is maintained in the immediate vicinity)

Noise and Vibration

E7. The works must be undertaken in accordance with the "Interim Construction Noise Guideline" published by the NSW Environment Protection Authority, to ensure excessive levels of noise and vibration do not occur so as to minimise adverse effects experienced on any adjoining land.

(Reason: To ensure residential amenity is maintained in the immediate vicinity)

Developer's Cost of Work on Council Property

E8. The developer must bear the cost of all works associated with the development that occurs on Council's property, including the restoration of damaged areas.

(Reason: To ensure the proper management of public land and funds)

No Removal of Trees on Public Property

E9. No trees on public property (footpaths, roads, reserves, etc.) unless specifically approved by this consent shall be removed or damaged during construction including for the erection of any fences, hoardings or other temporary works.

(Reason: Protection of existing environmental infrastructure and community assets)

Protection of Trees

E10. All trees required to be retained as part of this consent must be protected from any damage during construction works in accordance with AS4970-2009.

In the event that any tree required to be retained is damaged during works on the site, notice of the damage must be given to Council forthwith.

Notes:

- If the nominated tree is damaged to a significant degree or removed from the site without prior written approval being obtained from Council, the issuing of fines or legal proceedings may be commenced for failure to comply with the conditions of this consent.
- An application to modify this consent pursuant to Section 96 of the Environmental Planning and Assessment Act 1979 will be required to address the non-compliance with any of the conditions of consent relating to the retention of nominated trees, and Council may require tree replenishment.

(Reason: Protection of existing environmental infrastructure and community assets)

Special Permits

E11. Unless otherwise specifically approved in writing by Council, all works, processes, storage of materials, loading and unloading associated with the development must occur entirely on the property.

The developer, owner or builder may apply for specific permits available from Council's Customer Service Centre for the undermentioned activities on Council's property. In the event that a permit is granted by Council for the carrying out of works, processes, storage of materials, loading and unloading associated with the development on Council's property, the development must be carried out in accordance with the requirements of the permit. A minimum of forty-eight (48) hours' notice is required for any permit:

1) On-street mobile plant

E.g., cranes, concrete pumps, cherry-pickers, etc. - restrictions apply to the hours of operation, the area of operation, etc. Separate permits are required for each occasion and each piece of equipment. It is the developer's, owner's and builder's responsibilities to take whatever steps are necessary to ensure that the use of any equipment does not violate adjoining property owner's rights.

(Reason: Proper management of public land)

2) Hoardings

Permits are required to erect Class A and Class B hoardings. If an 'A' Class hoarding is to alienate a section of Council's property, that section will require a permit for the occupation of Council's property.

(Reason: Proper management of public land)

3) Storage of building materials and building waste containers (skips) on Council's property

Permits to utilise Council property for the storage of building materials and building waste containers (skips) are required for each location. Failure to obtain the relevant permits will result in the building materials or building waste containers (skips) being impounded by Council with no additional notice being given. Storage of building materials and waste containers on open space reserves and parks is prohibited.

(Reason: Proper management of public land)

4) Kerbside restrictions, construction zones

Attention is drawn to the existing kerbside restrictions adjacent to the development. Should alteration of existing kerbside restrictions be required, or the provision of a construction zone, the appropriate application must be made and the fee paid to Council. Alternatives to such restrictions may require referral to Council's Traffic Committee and may take considerable time to be resolved. An earlier application is suggested to avoid delays in construction programs.

(Reason: Proper management of public land)

Construction Hours (Commercial Core and Mixed-Use Zones)

E12. Construction activities and works approved under this consent must be carried out only within the hours stipulated in the following table:

Standard Construction Hours			
Location Day Hours			
Residential	Monday - Friday	7.00 am - 5.00 pm	
	Saturday	8.00 am - 1.00 pm	
	Sunday, Public holiday	No work permitted	

Construction activities for development approved under this consent must be carried out in accordance with the standard construction hours above and any Construction Noise Management Plan required under this consent.

In the event of breach to the approved hours of construction Council take may take enforcement action under Part 9 of the EP&A Act 1979 and in accordance with Council's adopted Compliance and Enforcement Policy.

(Reason: To ensure that works do not interfere with reasonable amenity expectations of

residents and the community)

Installation and Maintenance of Sediment Control

E13. Erosion and sediment controls must be installed and maintained at all times in accordance with the Sediment and erosion control plan submitted and approved with the Construction Certificate.

Erosion and sediment measures must be maintained in accordance with the publication Managing Urban Stormwater: Soils and Construction (4th edition, Landcom, 2004), commonly referred to as the "Blue Book" and can only be removed when development activities have been completed and the site fully stabilised.

(Reason: To protect the environment from the effects of sedimentation and erosion from

development sites)

Sediment and Erosion Control Signage

E14. A durable sign must be erected during building works in a prominent location on site, warning of penalties should appropriate erosion and sedimentation control devices not be maintained. A sign of the type referred to in this condition is available from Council.

(Reason: To protect the environment from the effects of sedimentation and erosion from

development sites)

Site Amenities and Facilities

E15. Where work involved in the erection and demolition of a building is being carried out, amenities which satisfy applicable occupational health and safety and construction safety regulations, including any WorkCover Authority requirements, must be provided and maintained at all times. The type of workplace determines the type of amenities required.

Further information and details can be obtained from the Internet at www.workcover.nsw.gov.au.

(Reason: To ensure the health and safety of the community and workers on the site)

Health and Safety

E16. All work undertaken must satisfy applicable occupational health and safety and construction safety regulations, including any WorkCover Authority requirements to prepare a health and safety plan. Site fencing must be installed sufficient to exclude the public from the site. Safety signs must be erected that warn the public to keep out of the site and provide a contact telephone number for enquiries.

Further information and details regarding occupational health and safety requirements for construction sites can be obtained from the internet at www.workcover.nsw.gov.au.

(Reason: To ensure the health and safety of the community and workers on the site)

Prohibition on Use of Pavements

E17. Building materials must not be placed on Council's footpaths, roadways, parks or grass verges, (unless a permit is obtained from Council beforehand). A suitable sign to this effect must be erected adjacent to the street alignment.

(Reason: To ensure public safety and amenity on public land)

Plant and Equipment Kept Within Site

E18. All plant and equipment used in the undertaking of the development/ works, including concrete pumps, wagons, lifts, mobile cranes, hoardings etc, must be situated within the boundaries of the site (unless a permit is obtained from Council beforehand) and so placed that all concrete slurry, water, debris and the like must be discharged onto the building site, and is to be contained within the site boundaries.

Details of Council requirements for permits on public land for standing plant, hoardings, storage of materials and construction zones and the like are available on Council's website at www.northsydney.nsw.gov.au.

(Reason: To ensure public safety and amenity on public land)

Waste Disposal

E19. All records demonstrating the lawful disposal of waste must be retained and kept readily accessible for inspection by regulatory authorities such as North Sydney Council and the Environmental Protection Authority.

(Reason: To ensure the lawful disposal of construction and demolition waste)

Asbestos Removal

E20. All demolition works involving the removal and disposal of asbestos cement must only be undertaken by contractors who hold a current WorkCover Asbestos or "Demolition Licence" and a current WorkCover "Class 2 (Restricted) Asbestos Licence and removal must be carried out in accordance with National Occupational Health and Safety Commission.

(Reason: To ensure works are carried out in accordance with relevant WorkCover requirements)

F. Prescribed Conditions imposed under EP&A Act and Regulations and other relevant Legislation

National Construction Code

F1. All building work must be carried out in accordance with the provisions of the National Construction Code.

(Reason: Prescribed - Statutory)

Home Building Act

- F2. 1) Building work that involves residential building work (within the meaning and exemptions provided in the Home Building Act 1989) for which the *Home Building Act* 1989 requires there to be a contract of insurance under Part 6 of that Act must not be carried out unless the Principal Certifying Authority for the development to which the work relates has given North Sydney Council written notice of the contract of insurance being issued and of the following:
 - a) in the case of work for which a principal contractor is required to be appointed:
 - i) the name and licence number of the principal contractor, and
 - ii) the name of the insurer by which the work is insured under Part 6 of that Act, or
 - b) in the case of work to be done by an owner-builder:
 - i) the name of the owner-builder, and
 - ii) if the owner-builder is required to hold an owner-builder permit under that Act, the number of the owner-builder permit.
 - 2) If arrangements for doing residential building work are changed while the work is in progress such that the information submitted to Council in accordance with this conditions is out of date, work must cease and no further work may be carried out unless the Principal Certifying Authority for the development to which the work relates (not being the Council), has given the Council written notice of the updated information.

(Note:

A certificate purporting to be issued by an approved insurer under Part 6 of the Home Building Act 1989 that states that a person is the holder of an insurance policy issued for the purposes of that Part is, for the purposes of this clause, sufficient evidence that the person has complied with the requirements of that Part)

(Reason: Prescribed - Statutory)

Appointment of a Principal Certifying Authority (PCA)

F3. Building work, demolition or excavation in accordance with the development consent must not be commenced until the developer has appointed a Principal Certifying Authority for the building work in accordance with the provisions of the EP&A Act and its Regulations.

(Reason: Statutory: To ensure appropriate safeguarding measures are in place prior to the commencement of any building work, demolition or excavation)

Construction Certificate

F4. Building work, demolition or excavation in accordance with the development consent must not be commenced until a Construction Certificate for the relevant part of the building work has been issued in accordance with the provisions of the EP&A Act and its Regulations.

(Reason: Statutory: To ensure appropriate safeguarding measures are in place prior to the

commencement of any building work, demolition or excavation)

Occupation Certificate

F5. A person must not commence occupation or use of the whole or any part of a new building (new building includes an altered portion of, or an extension to, an existing building) unless an Occupation Certificate has been issued in relation to the building or part. Only the Principal Certifying Authority appointed for the building work can issue an Occupation Certificate.

(Reason: Statutory)

Mandatory Critical Stage Inspections

F6. Building work must be inspected by the Principal Certifying Authority on the critical stage occasions prescribed by the EP&A Act and its Regulations, and as directed by the appointed Principal Certifying Authority.

(Reason: Statutory)

Excavation/Demolition

- F7. 1) All excavations and backfilling associated with the erection or demolition of a building must be executed safely and in accordance with appropriate professional standards.
 - 2) All excavations associated with the erection or demolition of a building must be properly guarded and protected to prevent them from being dangerous to life or property.
 - 3) Demolition work must be undertaken in accordance with the provisions of AS2601- Demolition of Structures.

(Reason: To ensure that work is undertaken in a professional and responsible manner and protect adjoining property and persons from potential damage)

Protection of Public Places

- F8. 1) A hoarding and site fencing must be erected between the work site and adjoining public place.
 - 2) If necessary, an awning is to be erected, sufficient to prevent any substance from, or in connection with, the work falling into the public place.
 - 3) The work site must be kept lit between sunset and sunrise if it is likely to be hazardous to persons in the public place.

- 4) Any such hoarding, fence or awning is to be removed when the work has been completed.
- 5) No access across public reserves or parks is permitted.

(Note:

Prior to the erection of any temporary fence or hoarding over property owned or managed by Council, written approval must be obtained. Any application needs to be accompanied by plans indicating the type of hoarding and its layout. Fees are assessed and will form part of any approval given. These fees must be paid prior to the approval being given. Approval for hoardings will generally only be given in association with approved building works, maintenance or to ensure protection of the public. An application form for a Hoarding Permit can be downloaded from Council's website)

(Reason: To ensure public safety and the proper management of public land)

Site Sign

- F9. 1) A sign must be erected in a prominent position on the site
 - a) stating that unauthorised entry to the work site is prohibited;
 - b) showing the name of the principal contractor (or person in charge of the work site), and a telephone number at which that person may be contacted at any time for business purposes and outside working hours; and
 - c) showing the name, address and telephone number of the Principal Certifying Authority for the work.
 - 2) Any such sign must be maintained while to building work or demolition work is being carried out but must be removed when the work has been completed.

(Reason: Prescribed - Statutory)

G. Prior to the Issue of an Occupation Certificate

Infrastructure Repair and Completion of Works

- G1. Prior to the issue of any Occupation Certificate any and all works relating to the development:
 - a) in the road reserve must be fully completed; and
 - b) to repair and make good any damaged public infrastructure caused as a result of any works relating to the development (including damage caused by, but not limited to, delivery vehicles, waste collection, contractors, sub-contractors, concrete vehicles) must be fully repaired;

to the satisfaction of Council Engineers at no cost to Council.

(Reason: Maintain quality of public assets)

Damage to Adjoining Properties

G2. All precautions must be taken to prevent any damage likely to be sustained to adjoining properties. Adjoining owner property rights and the need for owner's permission must be observed at all times, including the entering onto land for the purpose of undertaking works.

(Reason: To ensure adjoining owner's property rights are protected)

Utility Services

G3. All utility services shall be adjusted to the correct levels and/or location/s required by this consent, prior to issue of an occupation certificate. This shall be at no cost to Council.

(Reason: To ensure compliance with the terms of this consent)

Asbestos Clearance Certificate

- G4. For building works where asbestos based products have been removed or altered, an asbestos clearance certificate signed by an appropriately qualified person (being an Occupational Hygienist or Environmental Consultant) must be submitted to and approved by the Certifying Authority (and a copy forwarded to Council if it is not the Certifying Authority) for the building work prior to the issue of any Occupation Certificate, the asbestos clearance certificate must certify the following:
 - a) the building/land is free of asbestos; or
 - b) the building/land has asbestos that is presently deemed safe.

The certificate must also be accompanied by tipping receipts, which detail that all asbestos waste has been disposed of at an approved asbestos waste disposal depot. If asbestos is retained on site the certificate must identify the type, location, use, condition and amount of such material.

(Note: Further details of licensed asbestos waste disposal facilities can be obtained from

www.epa.nsw.gov.au)

(Reason: To ensure that building works involving asbestos based products are safe for occupation

and will pose no health risks to occupants)

Certification of Tree Condition

G5. Prior to the issue of an Occupation Certificate, a report prepared by an appropriately qualified person (being an arborist or the like) must be submitted to the Certifying Authority, describing the health of the tree(s) specifically nominated below: -

Tree	Location	Height
T1 Cupressus macrocarpa	Within the rear setback of No. 25 Edward Street	10m
T2 Cupressus macrocarpa	Within the rear setback of No. 25 Edward Street on the southern	
T3 Cupressus macrocarpa	boundary with 27 Edward Street	8m
T4 Cupressus macrocarpa	Within the rear setback of No. 25 Edward Street	8m

The report must detail the condition and health of the nominated trees upon completion of the works and shall certify that the trees have not been significantly damaged during the works on the site and have reasonable prospects for survival.

(Reason: To ensure compliance with the terms of this consent)

BASIX Completion Certificate

G6. In accordance with Clause 154C of the Environmental Planning and Assessment Regulation 2000, prior to issuing a final occupation certificate the Certifying Authority must apply to the Director-General for a BASIX completion receipt.

(Reason: To ensure compliance with the specified BASIX Certificate)

Landscaping

G7. For building works where asbestos based products have been removed or altered, an asbestos clearance certificate signed by an appropriately qualified person (being an Occupational Hygienist or Environmental Consultant) must be submitted to and approved by the Certifying Authority (and a copy forwarded to Council if it is not the Certifying Authority) for the building work prior to the issue of any Occupation Certificate, the asbestos clearance certificate must certify the following:

The landscaping shown in the approved landscape plan numbered DA1.10, prepared by Stirling & Andie, dated 17 September 2021, with modifications as per **condition C22**, must be completed prior to the issue of any Occupation Certificate.

(Reason: Compliance with the Consent)

Compliance with Certain conditions

G8. Prior to the issue of any Occupation Certificate **Conditions C9, C22** and **C23** must be certified as having been implemented on site and complied with.

(Reason: To ensure the development is completed in accordance with the requirements of this

consent)

I. Ongoing/Operational Conditions

Maintenance of Approved Landscaping

11. The owner(s) of the dwelling at 27 Edward Street is to maintain the landscaping approved by this consent generally in accordance with the drawing numbered DA1.10, prepared by Stirling & Andie, dated 17 September 2021, and as modified by **condition C22**.

Any replacement plants required shall be advanced in growth and be selected to maintain the anticipated mature height, canopy density and nature of those plant species as originally approved.

(Reason: To ensure maintenance of the amenity, solar access, and views of adjoining properties)